

# **TOWN OF FREETOWN**

## **GENERAL AND ZONING BY-LAWS**



Revised - STM of Oct. 24, 2011

(Posted AG decision 11/01/2011)

# TOWN OF FREETOWN GENERAL & ZONING BY-LAWS

## TABLE OF CONTENTS

### **ARTICLE 1 TOWN MEETING**

1.1	Posting of Warrants.....	1
1.2	Election of Officers-Referendum Questions.....	1
1.3	Annual Business Meeting.....	1
1.4	Insertion of Articles.....	1
1.5	Return of Warrant.....	1

### **ARTICLE 2 PROCEDURE AT TOWN MEETING**

2.1	Quorum Requirements.....	2
2.2	Meeting Called to Order.....	2
2.3	Admission of Voters, Etc.....	2
2.4	Appeal Procedure by Voter(s).....	2
2.5	Motion Procedures.....	2
2.6	Motion Reduced to Writing.....	2
2.7	Report of Finance Committee.....	2
2.8	Reconsideration.....	2
2.9	Sense of Meeting.....	2
2.10	Yes-No Ballot.....	3
2.11	Yes-No Ballots-Availability.....	3
2.12	Roberts' Rules of Order.....	3

### **ARTICLE 3 POWERS AND DUTIES OF TOWN OFFICERS**

3.1	Town Seal .....	3
3.2	Board of Selectmen .....	3
3.3	Town Administrator.....	5
3.4	Acting Town Administrator.....	8
3.5	Tax Collector- Denial, Suspension, or Revocation... ..	9
3.6	Fees- Town Clerk & Tax Collector.....	9
3.7	Minutes of Meetings.....	9

### **ARTICLE 4 FINANCE COMMITTEE**

4.1	Committee Members.....	10
4.2	Submission of Budgets.....	10
4.3	Budget Recommendations.....	10

**General & Zoning By-Laws  
Table of Contents**

<b>ARTICLE 5 COUNCIL ON AGING</b>		
5.1	Purpose.....	10
5.2	Appointments.....	10
5.3	Vacancy .....	10
5.4	Election of Officers.....	10
5.5	Annual Report .....	11
<b>ARTICLE 6 SOIL REMOVAL- SOIL CONSERVATION BOARD</b>		
6.1	Members.....	11
6.2	Removal of Earth Minerals.....	11
6.3	Continuous Operation.....	11
6.4	Issuing Permit – Conditions.....	11
6.5	Authorization & Conditions Continued .....	11
6.6	Transfer of Earth Minerals Over Owner’s Land.....	12
6.7	Organization of Board.....	12
6.8	Penalties.....	12
6.9	Definition “Earth Minerals”.....	12
6.10	Definition “Removal”.....	12
6.11	Fees.....	12
<b>ARTICLE 7 CONSERVATION COMMISSION</b>		
7.1	Purpose.....	12
7.2	Jurisdiction.....	13
<b>ARTICLE 8 DISABILITY FUNDS</b>		
8.1	Firefighters Disability Funds.....	13
8.2	Reserve Police Officer’s Disability Fund.....	13
<b>ARTICLE 9 TOWN CONTRACTS</b>		
9.1	Authorization.....	14
9.2	Filing of Contracts.....	14
<b>ARTICLE 10 PERSONNEL CLASSIFICATION AND COMPENSATION PLAN</b>		
10.1	General Provisions.....	14
10.2	Administration and Amendment.....	16
10.3	Classification Plan.....	17
10.4	Compensation Plan.....	17
10.5	Employee Selection.....	18
10.6	Work Policies.....	19
10.7	Effect of Partial Invalidity.....	23
10.8	Positions.....	23

**General & Zoning By-Laws  
Table of Contents**

**ARTICLE 11 PROTECTIVE ZONING BY-LAW**

Outline .....25-30  
11.1 - 11.28 Zoning By-Laws.....31-79

**ARTICLE 12 DEMOLITION BY-LAW**

12.0 Freetown Historical Commission.....79  
12.1 Intent and Purpose.....80  
12.2 Definitions.....80  
12.3 Regulated Buildings and Structures.....80  
12.4 Procedure.....80  
12.5 Determination of Applicability.....82  
12.6 Emergency Demolition.....82  
12.7 Non-Compliance.....82  
12.8 Severability.....82  
12.9 Demolition Delay By-Law Flowchart.....83

**ARTICLE 13 USE OF STREETS, SIDEWALKS, AND PUBLIC PLACES**

13.1 Use of Streets, Sidewalks and Public Places.....84  
13.2 Definitions.....84  
13.3 Parking.....86  
13.4 Police May Prohibit Parking Temporarily.....87  
13.5 Towing.....87  
13.6 Construction Vehicles; Construction Materials;  
Construction in Public Ways.....87  
13.7 One-way Traffic.....87  
13.8 Operation of Vehicles.....87  
13.9 Exemptions and Penalties.....91  
13.10 Handicapped and Veteran Parking By-Laws.....92  
13.11 Possession of Open Containers of Alcohol.....93  
13.12 Consumption of Alcoholic Beverages in Unlicensed  
Food Establishments.....93  
13.13 Public Consumption Or Use of Marijuana Or  
Tetrahydrocannabinol .....93

**General & Zoning By-Laws  
Table of Contents**

<b>ARTICLE 14 RECREATIONAL FACILITIES</b>	
14.1	Duties..... 93
14.2	Admittance..... 94
14.3	Hours of Operation..... 94
14.4	Violations/Enforcement.....94
14.5	Severability.....94
<b>ARTICLE 15 PUBLIC PEACE AND SAFETY</b>	
15.1	Public Indecency.....94
<b>ARTICLE 16 FALSE ALARM BY-LAW</b>	
16.1	Intent..... 95
16.2	Definitions..... 95
16.3	Three or More False Alarms..... 96
16.4	Previously Installed Alarms..... 96
16.5	Violation..... 96
16.6	Fine..... 96
<b>ARTICLE 17 DOG LICENSING, CONTROL AND REGULATIONS</b>	
17.1	Definitions..... 96
17.2	Licenses..... 97
17.3	Rabies..... 98
17.4	Fees..... 98
17.5	Restraint.....98
17.6	Impoundment.....98
17.7	Redemption of Impounded Animals..... 98
17.8	Warrant – Unlicensed Dogs..... 99
17.9	Emergency Treatment of Dogs and Cats on Public Ways 99
17.10	Killing of Certain Dogs.....99
17.11	Damage to Live Stock and Fowls..... 99
17.12	Hunting Dogs.....100
17.13	Interference .....100
17.14	Records.....100
17.15	Enforcement.....100
17.16	Killing of Dogs for Humane Purposes.....100
17.17	Dogs on School Property: Complaints Made to Dog Officer.....100
17.18	Right of Entry.....100
17.19	Abandonment of Dogs or Other Animals.....101
17.20	Penalty.....101

**General & Zoning By-Laws  
Table of Contents**

**ARTICLE 18 CAT LICENSING, CONTROL AND REGULATIONS**

- 18.1 Licenses.....101
- 18.2 Rabies.....101
- 18.3 Deleted
- 18.4 Deleted
- 18.5 Deleted
- 18.6 Deleted
- 18.7 Deleted
- 18.8 Deleted
- 18.9 Enforcement.....102
- 18.10 Killing of Cats for Humane Purposes.....102
- 18.11 Deleted
- 18.12 Right of Entry.....102
- 18.13 Deleted.....102
- 18.14 Penalty.....102

**ARTICLE 19 UNREGISTERED MOTOR VEHICLES**

- 19.1 Definitions.....102
- 19.2 General Information.....103
- 19.3 Written Approval Required.....103
- 19.4 Limitations.....103
- 19.5 Aggrieved Party.....103
- 19.6 Permit Criteria.....104
- 19.7 Exclusions.....104
- 19.8 Penalties.....104
- 19.9 Severability.....105

**ARTICLE 20 JUNK & USED AUTO DEALERS AND COLLECTORS**

- 20.1 Licensing Procedures.....105
- 20.2 Rules & Regulations.....105
- 20.3 Third Class Licenses.....105
- 20.4 Second Class Licenses .....105

**General & Zoning By-Laws  
Table of Contents**

**ARTICLE 21 TIRE STORAGE AND REGULATIONS**

21.1 Tire Storage.....105  
21.2 Tire Regulations..... 105

**ARTICLE 22 VOLATILE LIQUIDS**

22.1 Disposal of Volatile Liquids.....106  
22.2 Disposal by Collection..... 106  
22.3 Penalty.....106  
22.4 Regulations.....107

**ARTICLE 23 COAL ASH**

23.1 Prohibition of Coal Ash.....107  
23.2 Board of Health – Coal Ash Projects.....107

**ARTICLE 24 MISCELLANEOUS CONTROLS & REGULATIONS**

24.1 Covering Wells.....107  
24.2 Substances Pumped on Street.....108  
24.3 Littering.....108  
24.4 Video Game Rooms; Go Carts/All Terrain.....108  
24.5 By-Law for Open Burning and Burning Permit Fee.....108  
24.6 Pyrotechnics.....108  
24.7 Depositing Snow on Roads and Sidewalks.....108

**ARTICLE 25 PROSECUTIONS AND PENALTIES**

25.1 Prosecutions for Offenses.....109  
25.2 Penalties.....109  
25.3 Non-Criminal Disposition.....109

**ARTICLE 26 APPROVAL, EFFECTIVE DATE OF BY-LAWS**

26.1 Approval of By-Laws.....110  
26.2 Provision of By-Laws.....110

**General & Zoning By-Laws  
Table of Contents**

**ARTICLE 27 NON-STORMWATER DISCHARGES TO THE MUNICIPAL STORM DRAINAGE SYSTEM OF THE TOWN OF FREETOWN**

- 27-1 Objective/Intent.....110
- 27-2 Definitions.....110
- 27-3 Applicability.....112
- 27-4 Authority..... 112
- 27-5 Responsibility for Administration.....112
- 27-6 Severability.....112
- 27-7 Prohibited Activities.....112
- 27-8 Suspension of Municipal Storm Drainage System Access...113
- 27-9 Industrial or Construction Activity Discharges.....113
- 27-10 Monitoring of Discharges..... 113
- 27-11 Requirement to Prevent, Control and Reduce Storm Water  
Pollutants by the Use of Best Management Practices.....114
- 27-12 Watercourse Protection.....114
- 27-13 Notification of Spills.....114
- 27-14 Enforcement.....115

**ARTICLE 28 TAX INCREMENT FINANCING BOARD (TIFB)**

- Organization.....116
- Powers and Duties.....116
- Tax Increment Financing Parcels.....116
- Exemptions from Property Tax.....116
- Reporting.....116
- Revocation.....116
- Approval by the MA Econ. Assist. Coord. Council.....117
- Severability.....117

# **ARTICLE 1**

## **TOWN MEETING**

### **1.1 Posting of Warrants**

Every Town Meeting shall be called by a Warrant directed to a constable, or other duly appointed person, by posting attested copies of the said Warrant in not less than six (6) public places in the town at least fourteen (14) days before the time of holding the Annual Meeting, and at least fourteen (14) days before the time of holding any Special Town Meeting. *ATM-5/9/77*

- A. Availability of Warrants** - A copy of the Warrant containing the articles shall be made available to all registered voters at least seven (7) days before the time of holding the business portion of the Annual Meeting, and at least seven (7) days before the time of holding any Special Town Meeting. *ATM 5/3/75, STM-1/28/80,*

### **1.2 Election of Officers – Referendum Questions**

The Annual Town Meeting for the election of Officers and referendum questions shall be held on the first Monday in April and for such purpose the polls shall be open from twelve o'clock noon until eight o'clock p.m. in each precinct of Town. The Town shall in every year when the term of office of any incumbent expires and except when other provision is made by law, choose by ballot from the Registered Voters the following Town Officers: A Moderator, One Selectman, who shall also serve as a member of the Board of Health and a member of the Personnel Board; One Assessor; a Highway Surveyor; two Library Trustees; one Cemetery Commissioner; a Tree Warden; one Water Commissioner; one Planning Board member; a Town Clerk; one or two School Committee members, as appropriate. The Term of office for each such Office shall be three (3) years except for the Planning Board member which term of office shall be five (5) years. The Town shall elect two Finance Committee members in 1992, two Finance Committee members in 1993 and three Finance Committee members in 1994, all for three year terms, with successive elections every three years thereafter. In 2004, the Town shall increase the size of the School Committee from three to five members by electing two additional members, one for a three year term and one for a two year term, and thereafter all five School Committee members shall be elected for three year terms. *ATM 5/9/77, STM 10/28/91, STM 10/27/03, ATM 5/5/07, STM 11/08/10*

### **1.3 Annual Business Meeting**

The Annual Business Meeting shall be held on the first Monday in June at 7:30 p.m.  
*ATM 3/9/74 ATM-5/3/75, STM-3/9/98, ATM-5/6/00, ATM-6/1/09*

### **1.4 Insertion of Articles**

Every article for insertion in the Warrant for the Annual Town Meeting must be presented in writing to the Selectmen at least sixty (60) days before the business portion of the Annual Town Meeting. At the same time a copy of each article shall be filed with the Clerk of the Finance Committee. Each of the articles, unless inserted by the Selectmen shall be signed personally by not less than ten (10) registered voters for the Annual Town Meeting and not less than One hundred (100) registered voters for a Special Town Meeting. The Selectmen shall call a Special Town Meeting upon request in writing of Two hundred (200) or more registered voters, said meeting to be held not later than forty-five (45) days after receipt of such request and shall insert in the Warrant therefor all subjects the insertion of which shall be requested by said petition. *ATM 5/3/75, ATM-5-9/77, ATM-6/21/82, STM 2/25/08*

### **1.5 Return of Warrant**

The Constable or other duly appointed person to serve the Warrant for a Town Meeting shall, immediately after making service thereof, deliver to the Town Clerk the original warrant, with his return endorsed thereon stating fully the manner in which he served the same.

## **ARTICLE 2**

### **PROCEDURE AT TOWN MEETING**

#### **2.1 Quorum Requirements**

Each annual town meeting shall be called to order by the Moderator promptly at the appointed hour or as soon thereafter as fifty (50) registered voters are proven to be present and each special town meeting shall be called to order by the Moderator promptly at the appointed hour or as soon thereafter as ten (10) registered voters are proven to be present. In the absence of the Moderator such meeting shall be called to order by the Town Clerk, who shall preside until a temporary Moderator is chosen to act during the absence of the Moderator.

#### **2.2 Meeting Called to Order**

Immediately after calling of the meeting to order by the Moderator the Warrant for the Town Meeting and the return by the person who served the same shall first be read by the Town Clerk, unless the meeting votes that the reading of the articles in the Warrant is omitted.

#### **2.3 Admission of Voters, Etc.**

No person, except registered voters of the town, shall be admitted to any annual or special town meeting unless permission is granted by the Moderator or by a vote of the Town Meeting. If ordered by the Moderator, or by vote of the meeting, the voting lists of the town shall be used to check the names of registered voters.

#### **2.4 Appeal Procedure by Voter(s)**

Any voter may appeal from the decision of the Moderator and when properly seconded by seven or more voters, no other business except a motion to adjourn or lay on the table, shall be in order until the question of appeal has been decided. The question of appeal shall be decided without debate and by a rising vote, and shall be put as follows: "Shall the decision of the Moderator stand as the judgment of the meeting?" and the result shall be decided by the Moderator after a report of the count of the Clerk.

#### **2.5 Motion Procedures**

Unless otherwise provided by law or by-laws all motions shall require only a majority vote. Every article in the warrant shall be taken up in its order upon the warrant unless otherwise voted by the meeting, and no motion or resolution, the matter of which is not set forth in some article in the warrant, shall be entertained excepting only for the purpose of obtaining the sense of the meeting; but no such motion or resolution shall be entertained if seven voters object thereto.

#### **2.6 Motion Reduced to Writing**

Every motion shall be reduced to writing and signed by the person presenting it when so requested by the Moderator, and before receiving any motion the Moderator may require that it be seconded; a motion may be withdrawn by the mover if, no objection is made.

#### **2.7 Report of Finance Committee**

No article carrying an expenditure or appropriation of money, except where such expenditure is required by law, shall be acted upon at any Town Meeting until a report whereon has been made by the Finance Committee.

*ATM-5/9/77*

#### **2.8 Reconsideration**

No vote shall be reconsidered except upon a motion to that effect or upon a notice of such motion given at the same session of the meeting. Such motion or notice shall be made only by a voter on the prevailing side when the vote is taken.

#### **2.9 Sense of Meeting**

When a question is put (in case only a majority is required) the sense of the meeting shall be determined by the voices of the voters and the Moderator shall first announce the vote as it appears to him by sound. If the Moderator is unable to decide by the sound of the voices, or if his announcement is then upon doubted by any two voters rising in their places for that purpose, one making the appeal and the other seconding it, the Moderator shall without debate determine the vote by ordering a show of hands and he may appoint tellers, who shall be sworn to the faithful

## ARTICLE 2.9 (cont.)

discharge of their duties by the Town Clerk who shall make a record of such oath, to make and return the count or he may order a ballot vote. *ATM-3/2/1970*

### A. Declaration of two-thirds (2/3) vote. *STM 10/27/08, STM06/01/09*

Whenever a two-thirds (2/3) vote of Town Meeting is required by statute, such vote may be declared by the Moderator without a count and recorded as such by the Town Clerk. If a vote so declared by the Moderator is immediately challenged by seven (7) or more voters, the Moderator shall verify the vote by calling for a hand count by the tellers.

## 2.10 Yes-No Ballot

The vote on any motion, provided the meeting so orders, shall be taken by a “Yes” and “No” ballot with the use of the check list.

## 2.11 Yes-No Ballots-Availability

The Town Clerk shall provide and have in readiness for use at town meetings a sufficient supply of “Yes” and “No” ballots. Such ballots shall not be distinguished from each other in size, shape, color, paper, ink, in size and style of type, or in any other way which would make it possible to distinguish what was printed on said ballots other than by examination of the word printed thereon.

## 2.12 Roberts’ Rules of Order

The procedure and conduct of the annual and special business Town Meeting of the Town not provided herein shall be governed by Roberts’ Rules of Order, newly revised, current edition, so far as its rules and practices are applicable and not inconsistent with the other by-laws of the Town. *ATM-6/21/82*

## ARTICLE 3

### POWERS AND DUTIES OF TOWN OFFICERS

#### 3.1 Town Seal

The Town Clerk shall have the custody of the Town Seal.

##### A. Executed Instruments – Town Seal

All sealed instruments which may hereafter be executed by the Town, pursuant to a vote of the Town or otherwise, shall be sealed with such seal and subscribed by a majority of the Board of Selectmen or by such committee or agent as may be authorized to act.

#### 3.2 Board of Selectmen *STM 11/8/04*

The Board of Selectmen, unless specifically limited by statute, shall:

- (A) Serve as the goal setting, long range planning and policy making body of the town, recommending major courses of action to the town meeting, and adopting policy directives and guidelines which are to be implemented by officers, boards, committees, commissions, and employees of the town.
- (B) Have the power to enact rules and regulations to implement policies and to issue interpretations.
- (C) Exercise, through the Town Administrator, general supervision over all matters affecting the interests or welfare of the town.
- (D) Have the responsibility and authority for licensing and other quasi-judicial functions as provided by the General Laws and the Town of Freetown by-laws.
- (E) Be responsible for the preparation of all town meeting warrants.
- (F) Have the authority to make investigations and may authorize the Town Administrator or other agents to investigate the affairs of the town and conduct of any town department, office, or agency, including any doubtful claims against the town, and for this purpose the Board of Selectmen may subpoena witnesses, administer oaths, take testimony, and require the production of evidence. The report of any such investigation shall be placed on file in the office of the town clerk, and a report summarizing such investigation shall be printed in the next annual town report.
- (G) Review the annual proposed budget submitted by the Town Administrator and make recommendations with respect thereto as they deem advisable. The Town Administrator shall present the budget, incorporating the recommendations of the selectmen, to the finance committee.
- (H) Negotiate collective bargaining agreements and other contracts and/ or services not otherwise designated.

## ARTICLE 3 (3.2 cont.)

### **(I) Power of Appointment** *ATM 5/9/77, STM 10/15/79*

By majority vote, make appointments to town offices, as authorized or required by General Laws or by By-Law, including:

- 1) Chief of the Police Department, Chief of the Fire Department, Town Accountant, Building Commissioner, two (2) Constables (after notice being duly advertised for one (1) month prior to said appointment), Civil Defense Director and Town Counsel; as well as such other appointments as are required by the General Laws or Bylaws, including veterans' agent, animal inspector, sealer of weights and measures, and members and employees of the police department
- 2) After July 1, 2006, a Town Administrator.

### **(J) Power of Removal and Suspension**

- 1) By majority vote, to remove or suspend from office any appointed officer or employee of the town not subject to contractual agreements or collective bargaining contracts with the town for cause after notice and, if so requested by the officer or employee, a hearing; provided, however, that this section shall not apply to an officer who is appointed pursuant to the authority of the General Laws for a term found in law unless the applicable General Law provides for such suspension or removal .
  - (i.) Any such officer or employee shall continue to receive his/her salary until removed from office.
  - (ii) The failure of the Board of Selectmen to reappoint an officer or employee at the expiration of the term of that officer or employee shall not constitute a removal or suspension, and nothing in this section shall be construed as granting a right to a hearing to an officer or employee who is not so reappointed.

- (K) The Board of Selectmen shall be the agents of the Town to institute, prosecute, and defend any and all claims, actions and proceedings to which the Town is a party, or in which the interests of the Town are or may be involved.
- (L) Recordings Registry of Deeds – It shall be the duty of the Board of Selectmen to see that every conveyance to the Town of any interest in land is properly recorded in the Registry of Deeds.
- (M) The Board of Selectmen shall have the general direction and management of the property and affairs of the town in all matters not otherwise provided for by law or by these by-laws.
- (N) The Board of Selectmen is authorized to sell on behalf of the Town, and without a vote of the Town, any and all personal property belonging to the Town, which they determine as no longer needed by the Town, at Public Auction or Private Sale, upon such terms as they deem proper provided the fair market value of such property does not exceed the sum of Five Thousand (\$5,000) dollars, and provided further that if the fair market value exceeds two thousand (\$2,000) dollars the sale of said property shall be by public auction.  
*STM 12/14/87*
- (O) The Board of Selectmen shall require that all bills against the Town be clearly itemized and, except for bills for salaries of all town officers, approved by the officer on whose order the bill is contracted before giving an order to the Treasurer for payment.
- (P) All heads of departments of the Town shall make an itemized statement of receipts and expenditures for publication in the Annual Town Report. The Selectmen shall cause the Town Report to be printed and made available to the inhabitants at least seven (7) days before the time of holding the Annual Town Meeting.
- (Q) The Board of Selectmen is authorized to accept and enter into contracts for the expenditure of any funds allotted or to be allotted by the Federal Government, the Commonwealth and/or County for the construction, reconstruction and improvement of Town roads.
- (R) Until such time that a Town Administrator is first appointed or in the absence of a Town Administrator or an Acting Town Administrator, the Board of Selectmen is authorized to assume and act on the duties normally required of a Town Administrator or Acting Town Administrator.
- (S) Powers of Contract. Any contracts negotiated on behalf of the Town shall be subject to final approval of, and execution by, the Board of Selectmen.

## ARTICLE 3 (3.2 cont.)

### (T) Fee Schedule – Ambulance *ATM 5/1/89, ATM 5/3/04*

The Board of Selectmen may establish reasonable fees for use of the ambulance(s). *ATM 5/1/89, ATM 5/3/84*

### (U) Fee Schedule – Transfer Station *STM 9/11/89, ATM 5/3/04*

The Board of Selectmen may establish reasonable fees for the use of the Transfer Station. Such fee schedules may be implemented after two (2) public hearings, the date, time, place and subject of which must be published seven (7) days in advance in a least one newspaper of general circulation; and after publication of the final rate schedule in at least one newspaper of general circulation ten (10) days in advance of such schedule. *STM 9/11/89, ATM 5/3/04*

## 3.3 Town Administrator *STM 11/08/04, AG 3/11/05*

### (A) Appointment, Term of Office

The Town Administrator shall be appointed by the Board of Selectmen for a term not to exceed 3 years, as the Board may determine, and may be appointed for successive terms of office.

### (B) Compensation

The Board of Selectmen shall set the compensation for the Town Administrator, not to exceed an amount appropriated by the Town Meeting.

### (C) Qualifications

- (1) The Town Administrator shall be appointed on the basis of his/her educational, executive and administrative qualifications and experience. His/her education shall consist of at least a Master's Degree in Public Administration or a Master's Degree in Business Administration or a Master's Degree related to either field of study, granted by an accredited degree granting college or university, and his/her professional experience shall include at least five (5) years previous experience in at least one of the following: Town Manager, Assistant Town Manager, Town Administrator or Assistant Town Administrator
- (2) The Town Administrator shall devote full time to the duties of said office and shall not engage in any other business or occupation during the term of his employment by the town.
- (3) The Town Administrator shall hold no elective office during his/her tenure as Town Administrator, but the Board of Selectmen may appoint the Town Administrator to any non-elective office or position consistent with the responsibilities of the Town Administrator.
- (4) The Board of Selectmen may from time to time establish additional qualifications for the office of Town Administrator. To the extent permitted by law, the terms of the Town Administrator's employment may be the subject of a written agreement between the parties setting forth the length of service, compensation, vacation, sick leave, benefits, and such other matters, excluding tenure, as are customarily included in an employment contract.
- (5) The Town Administrator shall not have served in an elective office in the town government of the Town of Freetown for at least one (1) full year prior to his/her appointment.
- (6) Before entering upon his/her duties, the Town Administrator shall be sworn to the faithful and impartial performance thereof by the town clerk. The Town Administrator shall execute a bond in the favor of the Town for the faithful performance and with such sureties as may be fixed by the Board of Selectmen; the cost of said bond shall be borne by the Town.

### Duties

#### (D) General Duties

The Town Administrator shall:

- (1) Be responsible for coordination of operational and strategic planning for the town.

## ARTICLE 3 (3.3D cont.)

- (2) Supervise and direct the efficient and responsible administration of all officers and employees appointed by the Town Administrator and/or Board of Selectmen and their respective offices and departments, and of all functions for which the Town Administrator is given responsibility by the Board of Selectmen, the laws of the commonwealth, and by-laws passed by town meeting.
- (3) Subject to any applicable provisions of the General Law relating thereto, may assume, temporarily, the duties of any office which the administrator is authorized to fill by appointment.
- (4) Be responsible for administration of the personnel plan including personnel evaluation policies, practices, enforcement of labor contracts, labor relations, and state and federal equal opportunity law compliance functions of the town.
- (5) Keep full and complete records of the office and annually submit to the selectmen, unless requested to do so more frequently, a full written report of the operations of the office of Town Administrator. The Town Administrator may also prepare reports to boards and committees and for town meeting.
- (6) Advise the selectmen of all matters requiring action by them or the town.
- (7) Attend all regular and special meetings of the Board of Selectmen, unless excused and shall have a voice but no vote in all of its discussions.
- (8) Attend all sessions of the Town Meeting and shall answer all questions directed at him or her relating to Town affairs.
- (9) Be responsible for the negotiation of all contracts, which are subject to execution by the Board of Selectmen
- (10) Administer, either directly or through a person or persons appointed by him, in accordance with this bylaw, all provisions of general and special laws applicable to said town, all by-laws, and all regulations established by the Board of Selectmen.
- (11) Oversee the activities of the town counsel under the direction of the Board of Selectmen.
- (12) Receive and address citizen's complaints and problems.
- (13) Be responsible for the management of all town insurance programs.
- (14) Represent the town at local, state and regional meetings and undertake public relations activities under the direction of the Board of Selectmen.
- (15) Perform such other duties consistent with the office, as may be required of the administrator by by-law or by vote of the Board of Selectmen or town meeting.
- (16) Have access to all municipal books, papers and documents or information necessary for the proper performance of the duties of the Town Administrator. The Town Administrator may, without notice, cause the affairs of any division or department under the administrator's supervision of the job-related conduct of any officer or employee thereof to be examined.
- (17) To perform any other duties as are required to be performed by the Town Administrator by votes of the town meeting, or votes of the Board of Selectmen, or otherwise

### **(E) Financial Duties**

The Town Administrator shall:

- (1) Be the chief administrative officer of the town and shall be responsible to the Board of Selectmen for the effective management of all town affairs placed in the administrator's charge by this by-law, the Board of Selectmen or vote of town meeting and the implementation of town policies placed in the administrator's charge by the Board of Selectmen.

## ARTICLE 3 (3.3E cont.)

- (2) Be responsible for the design and preparation of the municipal budget, filing grant applications, and controlling budget expenditures, including approval of the warrants for the payment of town funds prepared by the town accountant. Without limiting the generality of the foregoing the Town Administrator shall have the following specific budgetary powers:
- (a) The Town Administrator shall submit to the Board of Selectmen a written proposed budget for town government for the ensuing fiscal year, including the budget as proposed by the school department. The proposed budget shall detail all estimated revenue from all sources, and all proposed expenditures, including debt service for the previous, current, and ensuing years. It shall include proposed expenditures for both current operations and capital projects during the ensuing year, detailed by agency, department, committee, purpose, and position, together with proposed financing methods; and the proposed budget shall include estimated surplus revenue and free cash available at the close of the fiscal year, including estimated balances in special accounts. The town may establish additional financial information and reports to be provided by the Town Administrator.
  - (b) The Town Administrator shall report on the probable amount required to be levied and raised by taxation to defray all expenses and liabilities of the town together with an estimate of the tax rate necessary to raise such amount.
  - (c) The calendar dates on or before which the proposed budget, revenue statement, and tax rate estimate are to be submitted to the Board of Selectmen, and the budget presented by the Town Administrator to the finance committee will be set by the respective Board or Committee.
  - (d) To assist the Town Administrator in preparing the proposed annual budget of revenue and expenditures, all boards, officers, and committees of the town, including the school committee, shall furnish all relevant information in their possession and submit to the Town Administrator, in writing, a detailed estimate of the appropriations required and available funds.
  - (e) The Town Administrator shall submit annually to the Board of Selectmen and the finance committee a five year capital improvements program to include: (a) a list of all capital improvements proposed to be undertaken during the next five years, together with supporting data; (b) cost estimates, methods of financing, and recommended time schedule; (c) the estimated annual cost of operating and maintaining any facility to be constructed or acquired; and (d) other information that may be required from time to time.

### (F) Purchases by Town Administrator

- 1) The Town Administrator shall be responsible for purchasing all supplies, materials and equipment, and shall award all contracts for all departments and activities of the town under his/her supervision; and he/she shall make all purchases for departments and activities not under his/her supervision but not including food for schools, school books and other instructional materials, supplies and equipment, library books and related printed and audio visual material unless otherwise specifically requested by the Regional School Committee, Local School Committee or the Library Trustees and only to such extent and for such period as the Regional School Committee, Local School Committee or the Library Trustees shall from time to time specify. Purchases for departments and activities not under his/her supervision shall be made only upon and in accordance with a requisition duly signed by the head of any such department.
- 2) All purchases or contracts shall be made in accordance with G.L. c. 30B; G.L. c. 30, § 39; and G.L. c. 149, as amended; and any and all other applicable statutes.
- 3) All contracts for services negotiated by the Town Administrator shall be ratified by a majority vote of the Board of Selectmen.

### (G) Powers to Appoint

- 1) The Town Administrator shall recommend candidates to the Board of Selectmen for appointment to the following town offices: veterans' agent, animal inspector, sealer of weights and measures, and members and employees of the police department.

## ARTICLE 3 (3.3G cont.)

- 2) Officers appointed under this by-law shall perform their duties in accordance with the General Laws and Town By-Laws.
- 3) The Town Administrator shall have the power to appoint on merit and fitness alone the inspector of wires of such other individual town officers, employees, and members of boards and commissions for whom appointment is not otherwise provided by the General Laws or by-laws.
- 4) The Town Administrator shall have the power to remove any official or employee appointed by the Town Administrator for cause after notice and, at the request of the employee or official, a hearing.
- 5) The Town Administrator shall supervise the boards, committees, commissions and employees that the administrator appoints, and, at the request of the Board of Selectmen, those appointed by the Board of Selectmen.

### (H) Removal of the Town Administrator

The Board of Selectmen may terminate the Town Administrator for cause after notice and, at the request of the Town Administrator, a hearing.

### 3.4 Acting Town Administrator *STM 11/08/04*

- (A) Temporary Absence – By letter filed with the town clerk, the Town Administrator shall recommend a qualified town administrative officer or employee who, with the approval of the Board of Selectmen, shall exercise the powers and perform the duties of Town Administrator during a temporary absence. The Board of Selectmen may not revoke such designation until at least ten (10) working days have elapsed.
- (B) Acting Town Administrator – After the Town Administrator has been absent for at least ten (10) working days, the Board of Selectmen may appoint as an Acting Town Administrator any qualified town administrative officer or employee or other qualified person to serve until the Town Administrator shall return. The term of service of an acting Town Administrator may not exceed six (6) months, but one additional renewal not to exceed three (3) months may be approved by vote of the Board of Selectmen. Compensation for such person shall be set by the Board of Selectmen.
- (C) Vacancy – Upon the creation of a vacancy due to the permanent absence or disability of the Town Administrator rendering the Administrator unable to perform the duties of the office or the removal or resignation of the Town Administrator, the Board of Selectmen shall forthwith fill the vacancy.
- (D) Powers and Duties – The powers of a temporary or acting Town Administrator under (A) and (B) above shall be limited to matters not admitting of delay and shall include authority to make temporary, emergency appointments or designations to town office or employment but not to make permanent appointments or designations.

### Severability

This by law shall be interpreted insofar as possible as consistent with state law. In the event of an inconsistency, however, state law shall control. This by-law shall be interpreted insofar as possible as consistent with existing by-laws. In the event of an inconsistency, however, this by-law shall control.

## ARTICLE 3 (cont.)

### **3.5 Tax Collector Denial, Suspension, or Revocation**

- a. The Tax Collector shall annually furnish to each department, board, commission, or division, hereinafter referred to as the licensing authority, that issues licenses or permits including renewals and transfers, a list of any person, corporation, or business enterprise, hereinafter referred to as the party, that has neglected or refuse to pay any local taxes, fees, assessments, betterments, or other municipal charges for not less than a twelve month period, and that has not filed in good faith a pending application for an abatement of such tax or a pending petition before the appellate tax board
- b. The licensing authority may deny, revoke, or suspend any license or permit, including renewals and transfers, of any party whose name appears on said list furnished to the licensing authority from the tax collector, providing however, that written notice is given to the party and to the tax collector, as required by the applicable provisions of law, and that the party is given a hearing, to be held not earlier than fourteen days after said notice. Said list shall be prima facie evidence for denial, revocation, or suspension of said license or permit to any party. The tax collector shall have the right to intervene in any hearing conducted with respect to such license denial, revocation, or suspension. Any findings made by the licensing authority with respect to such license denial, revocation, or suspension shall be made only for the purposes of such proceeding and shall not be relevant to or introduced in any other proceeding at law, except for any appeal from such license denial, revocation, or suspension. Any license or permit denied, suspended, or revoked under this section shall not be reissued or renewed until the license authority receives a certificate issued by the tax collector that the party is in good standing with respect to any and all municipal charges, payable to the municipality as of that date of the issuance of that certificate.
- c. Any party shall be given an opportunity to enter into a payment agreement, thereby allowing the licensing authority to issue a certificate indicating said limitations to the license or permit and with validity of said license or permit shall be conditioned upon the satisfactory compliance with said agreement. Failure to comply with said agreement shall be grounds for the suspension or revocation of said license or permit; provided however, that the holder be given notice and a hearing as required by applicable provision of law.
- d. The Board of Selectmen may waive such denial, suspension, or revocation if it finds there is no direct or indirect business interest by the property owner, its officers, or stockholders, if any, or members of his immediate family, as defined in section one of chapter two hundred and sixty-eight in the business or activity conducted in or on said property.
- e. This By-Law shall apply to all local licenses or permits except the following: Open burning (c. 48 §. 13); bicycle permits (c. 85 §11A); sales of articles for charitable purposes (c. 101 §33); children's work permits (c. 149 §69); clubs, associations dispensing food or beverage (c. 140 §. 21E); dog licenses (c. 140 §137); fishing, hunting or trapping licenses (c. 131 §12); marriage licenses (c. 207 §28); and theatrical events, public exhibitions (c. 140 §181) and certificates of occupancy. *ATM 6/22/92, ATM 5/3/04 posted 7/26/04,*

### **3.6 Fees**

To require the Town Clerk and Collector of Taxes to forward all fees collected by virtue of their elected offices to the Town Treasurer for deposit in the Town Treasury, effective July 1, 1986. *ATM 5/5/86, STM 10/27/03*

### **3.7 Minutes of Meetings** *ATM 5/3/04 posted 7/26/04*

All elected and appointed boards, committees, commissions, and trustees shall create and maintain minutes of all posted and emergency meetings in accordance with the provisions of G.L. c. 39, § 23B, the Open Meeting Law, and of G.L. c. 66, the Public Records Law. All governmental bodies, with the exception of the School Committee, shall submit to the Town Clerk within two weeks of approval copies of minutes of open meetings held in accordance with G.L. c.39, §23B. Copies of executive session minutes shall be forwarded to the Town Clerk forthwith after publication will no longer defeat the purposes of the executive session.

## **ARTICLE 4**

### **FINANCE COMMITTEE**

#### **4.1 Committee Members**

The Finance Committee shall consider any and all municipal questions for the purpose of making reports or recommendations thereon to the voters of the town. Such committee shall consist of seven (7) voters who shall serve without pay, none of whom during their service on such committee shall hold any regular elective, or appointed town office, having to do with the expenditures of town money. *AG-7/7/70*  
*STM-10/28/91 (Deleted word "nine")*

#### **4.2 Submission of Budgets**

It shall be the duty of the Finance Committee to inform themselves concerning those affairs and interests of the Town, the subject matter of which is included in the Warrant for its town meeting, and the Selectmen, the School Committee, and departments not under their supervision, and all other town officers be required to furnish to said Committee, in writing, not later than February 1<sup>st</sup> of each year, in as much detail as possible, their report of the previous year with their estimates and recommendations of the amounts necessary to be appropriated for the support of their several departments for ensuing year. The Finance Committee shall then investigate the estimates and recommendations so presented and give opportunity to said various boards and officers to be heard and explain such estimates and recommendations. The Finance Committee shall inform all town officers, boards and department heads in writing of recommended changes in submitted budget estimates prior to the preparation of the town budgets to be acted upon at the Annual Town Meeting. *ATM 3/11/67*

The Committee shall also hold public meetings and invite any town officer, citizen or person to attend, and to give such information as he may have that will assist the Committee in any matter coming before it for consideration. *ATM-5/3/75\*\*STM-12/2/76*

#### **4.3 Budget Recommendations**

The Committee shall, prior to each annual business Town Meeting or when necessary prior to a Special Town Meeting, prepare a budget showing in detail the anticipated income and expenditures of the Town for the then current year, together with its advice and recommendations with reference to the various appropriations of the town funds, and other municipal matters coming before such Town Meeting. The Finance Committee shall at each annual Town Meeting present and explain such budget with its advice and recommendations and it shall also at each Special Town Meeting give its advice and recommendations with reference to any appropriations of the town funds or other municipal matter coming before such meeting. *ATM-5/3/75*

## **ARTICLE 5**

### **COUNCIL ON AGING** *ATM 3/6/71 , ATM 5/6/02*

#### **5.1 Purpose**

The Board of Selectmen shall appoint a Council on Aging for the purpose of co-ordinating or carrying out programs designed to meet the problems of the aging in cooperation with programs of the Commission on Aging established under Chapter 6, § 73 of the General Laws.

#### **5.2 Appointments**

The Board of Selectmen shall appoint the Council on Aging consisting of seven (7) members. Upon acceptance of this by-law, the Board shall appoint three (3) members for three (3) years, two (2) members for two years and two (2) members for one (1) year. Thereafter, each member shall be appointed for a three (3) year term. Members can be re-appointed for concurrent terms. The members of the Council shall serve without pay.

#### **5.3 Vacancy**

Whenever a vacancy shall occur in the membership of the Council, by reason of death, resignation, inability to act or for any other reason, the vacancy shall be filled by appointment by the Selectmen for the remainder of the term.

#### **5.4 Election of Officers**

The Council on Aging at its first annual meeting and thereafter, annually in April of each year, shall elect from its membership, A President, 1<sup>st</sup> Vice President, 2<sup>nd</sup> Vice President, Secretary and Treasurer. Each officer shall hold office until the next annual election. In the event a vacancy occurs in any of the offices above, the Council shall hold a special meeting for the purpose of electing one of its members to fill such vacancy.

## ARTICLE 5 (cont.)

### **5.5 Annual Report**

The Council shall prepare and submit an annual report of its activities to the Town and shall send a copy thereof to the Commission on Aging.

## **ARTICLE 6**

### **SOIL REMOVAL – SOIL CONSERVATION BOARD**

*Soil Removal by-laws accepted by vote of the Town at the ATM 3/10/56, ATM 5/3/75*

#### **6.1 Members**

A Soil Conservation Board is hereby established in the Town of Freetown for the purpose of regulating the removal of earth minerals from land within the town and in enforcing the provisions of this by-law.

The members of the Board shall consist of the Board of Selectmen, one member of the Planning Board to be selected by such Board, one member of the Conservation Commission to be selected by such Commission.

*STM 10/25/76, STM 10/22/01*

The Planning Board and Conservation Commission shall annually in June submit to the Board in writing the names of their respective members who will serve on the Soil Conservation Board for the term of the forthcoming fiscal year. *STM 10/25/76*

#### **6.2 Removal of Earth Minerals**

The stripping or removal of earth minerals from any parcel of land not in public use in the Town of Freetown, except as hereinafter provided is prohibited, unless a written permit therefor is obtained from the Board after a public hearing of which due notice is given.

- A. **Denial to Remove** - After permission for a earth mineral permit has been denied by the Board, no operator or owner shall be allowed to reapply for a period of one (1) year.

#### **6.3 Continuous Operation**

Whenever the Board is satisfied that the removal of any earth minerals had previously been undertaken in a particular location and was in continuous operation, at the time when notice of the warrant for the Town Meeting at which this by-law was adopted was given, a permit for the further continuance of such operation with the same territorial limits shall be issued without a hearing; but such permit may be issued subject to conditions in the same manner as other permits.

#### **6.4 Issuing Permit – Conditions**

In issuing a permit under this By-Law, the Board may impose such conditions not specifically provided for herein as it may deem necessary for the adequate protection of the neighborhood and the Town. Any conditions imposed by the Board shall be attached to and made a part of the permit. The Board shall require a bond for the compliance with said conditions as evidence of good faith for the completion of any proposed construction. The Board shall after a public hearing on proof of violation of any condition, revoke any permit so issued. No permit shall be issued under the provisions of said By-Law for a period of more than three (3) years. No revocation shall endure for less than thirty (30) days.

#### **6.5 Authorization & Conditions Continued**

Earth minerals may be removed from any parcel of land within the town only after a permit authorizing such removal has been issued by the Board after satisfactory evidence that such removal will not be seriously detrimental, injurious or hazardous to the neighborhood; provided further that the Board shall impose reasonable conditions as to the method of removal, the maintaining or re-establishment of ground levels and grades, and the planting of the area to suitable cover, as it may deem necessary. The Board may also designate the Town roads over which such earth minerals may be transported in the process of removal. Removal of earth minerals under authority of this section shall be further subject to the provision of Section 6.3 and 6.4.

## **ARTICLE 6 (cont.)**

### **6.6 Transfer of Earth Minerals Over Owner's Land**

No permit shall be required by an owner of real estate for the transfer of earth minerals from one part of his own premises to another part thereof for the improvement of his own premises, nor shall any permit be required for removal of earth minerals in connection with the improvement or construction of any road over his premises provided such earth minerals so removed are used on said premises to improve the same and is not contrary to the regulations of this by-law as adopted. No permit shall be required by quarries operating at the time this by-law is adopted so long as the sale of earth minerals is not involved.

### **6.7 Organization of Board**

No person interested in the application for a permit for the removal of earth minerals, shall be eligible to participate in the action of the Board with reference to such permit. Replacement of any member or members so disqualified shall be determined by the other members of the Soil Conservation Board. A majority of the Board shall constitute a quorum. The Board shall elect its own Chairman and Secretary. Its Secretary need not be a member of the Board. The Secretary shall keep a true record of the proceedings of the Board, which shall be public record.

### **6.8 Penalties**

The penalty for violation of this article shall be for the first offense, \$50.00; for the second offense, \$100.00; and for each subsequent offense, \$200.00

### **6.9 Definition "Earth Minerals"**

"Earth Minerals" are defined in this by-law to include all forms of soil without limitation, specifically including loam, sand, gravel, clay, humus, peat, hardpan or rock, iron, coal, etc. *ATM 3/3/75*

### **6.10 Definition "Removal"**

"Removal" is defined as stripping, digging, excavating, or blasting of earth minerals from a lot for the purpose of removing or clearing it away from the lot. *ATM 3/3/75*

**6. 11** The Soil Conservation Board may establish reasonable fees for Soil Removal Permits and Soil Removal Operations. Such fee schedule may be implemented after a public hearing, the time, date, and place subject of which must be published seven (7) days in advance in at least one newspaper of general circulation. *STM 10/22/01*

## **ARTICLE 7**

### **CONSERVATION COMMISSION** *ATM 5/6/71, ATM 5/03/75, ATM 5/5/80, ATM 5/05/03*

#### **Town of Freetown Wetlands Protection Bylaw**

##### **7.1 Purpose**

The purpose of this bylaw is to protect the wetlands, water resources, and adjoining land areas in the Town of Freetown by controlling activities deemed by the Conservation Commission likely to have a significant or cumulative effect upon resource area values, including but not limited to the following: public or private water supply, groundwater, flood control, erosion and sedimentation control, storm damage prevention including coastal storm flowage, water quality, water pollution control and prevention, fisheries, land containing shellfish, wildlife habitat, rare species habitat including rare plant species, agriculture, aquaculture, and recreation values, deemed important to the community (collectively, the "resource area values protected by this bylaw"). The Conservation Commission has the authority to adopt rules and regulations for the use of conservation land (G.L. Ch. 40 §8C). This bylaw is intended to utilize the Home Rule authority of this municipality to protect additional resource areas, for additional values, with additional standards and procedures stricter than those of the Wetlands Protection Act (G.L. Ch. 131 §40) and Regulations thereunder (310CMR 10.00), subject, however, to the rights and benefits accorded to agricultural uses and structures of all kinds under the laws of the Commonwealth.

## ARTICLE 7 (cont.)

### 7.2 Jurisdiction

Except as permitted by the Conservation Commission or as provided in this bylaw, no person shall commence to remove, fill, dredge, build upon, degrade, discharge into, or otherwise alter the following resource areas:

- 1) within one hundred feet (100') of any of the following:
  - freshwater or coastal wetlands; marshes; wet meadows; bogs; swamps; vernal pools; banks; reservoirs; lakes; flats; ponds of any size; rivers; streams; creeks; beaches; dunes; estuaries; the ocean; lands under water bodies; lands subject to flooding or inundation by groundwater or surface water; lands subject to tidal action, coastal storm flowage, or flooding; and
- 2) lands abutting any of the aforesaid resource areas as set out in Section 7.1 "Purpose" (collectively the "resource areas protected by this bylaw"), or
- 3) within 200 feet of any perennial river or stream.

Said resource areas shall be protected whether or not they border surface waters. This bylaw is adopted under the Home Rule Amendment of the Massachusetts Constitution and the Home Rule statutes, independent of the Wetlands Protection Act (G.L. Ch. 131 §40) and Regulations (310 CMR 10.00) hereunder.

## ARTICLE 8

### DISABILITY FUNDS

#### 8.1 Firefighters Disability Funds

\$5,000 Raised to establish a call firefighters' disability fund. Payments from this fund shall be made in instances where a call firefighter is disabled because of injury or incapacity sustained in the performance of duty and is unable to perform the usual duties of his/her regular occupation at the time such injury or in-capacity was incurred. The call firefighter shall receive from the call firefighter disability fund, for the period of such injury or incapacity, a sum equal to seventy-two (72%) per-cent of the compensation payable to the entry level of a permanent firefighter less any related insurance payments made to him/her. Such payment shall not exceed his/her compensation from his/her regular occupation.

The period for which such compensation is authorized shall not exceed a total of one hundred four (104) weeks provided, however, that no payments shall be made under this section after said call firefighter has been retired or pensioned in accordance with M.G.L., Chapter 32, § 85h, or after a physician designated for such purpose by the fire chief has determined that such incapacity no longer exists.

All amounts payable under this section shall be paid at the same time and same manner as if he/she were a permanent firefighter and for all purposes shall be deemed to be the regular compensation of such firefighter.

*ATM 5/5/86*

#### 8.2 Reserve Police Officer's Disability Fund

\$500.00 voted to establish a Reserve Police Officer's Disability Fund. Payments from this fund shall be made in instances where a Reserve Police Officer is disabled because of injury or incapacity sustained in the performance of duty and is unable to perform the usual duties of his/her regular occupation at the time of such injury or incapacity was incurred. The Reserve Police Officer shall receive from the Reserve Police Officer Disability Fund, for the period of such injury or incapacity, a sum equal to seventy-two (72%) percent of the compensation payable to the entry level or if applicable, Step 2 to prevent the reduction of the Reserve Police Officer's pay rate, of a permanent police officer less any related insurance payment made to him/her. Such payment shall not exceed his/her compensation from his/her regular occupation. Payment shall not commence until the injured/incapacitated party signs the Reimbursement Agreement.

## ARTICLE 8 (8.2 cont.)

The period for which such compensation is authorized shall not exceed a total of ONE HUNDRED FOUR (104) weeks, provided, however, that no payments shall be made under this section after said Reserve Police Officer has been retired or pensioned in accordance with M.G.L. 32, §85H, or after a PHYSICIAN designated for such purpose by the Board of Selectmen has determined that such incapacity no longer exists. All amounts payable under this section shall be paid at the same time and same manner as if he/she were a permanent police officer and for all purposes shall be deemed to be the regular compensation of such police officer.

*ATM 5/6/96*

## ARTICLE 9

### TOWN CONTRACTS *ATM 5/9/77, ATM 5/5/80, STM 1/6/86, STM 3/12/90, ATM 5/6/02*

#### 9.1 Authorization

The Officer or Board authorized to make the contract, may, on all contracts other than purchase contracts, require a suitable performance bond, the obligation of such bond to be secured by sureties acceptable to such officer or board.

*ATM-5/9/77*

#### 9.2 Filing of Contracts

Every officer of the town who makes or executes a contract on behalf of the town shall furnish the contract or an executed copy thereof to the Town Clerk within one week after its execution and the Town Clerk shall keep such contract or copy on file for public inspection during business hours. All allowances under and additions and extras to such contracts shall be filed with the Town Clerk together with a sworn statement of the officer, board or committee making such allowance or additions that the same are correct and in accordance with the contract.

## ARTICLE 10

### PERSONNEL CLASSIFICATION AND COMPENSATION PLAN

#### 10.1 General Provisions

- A) Authorization - Pursuant to the authority contained in Section 108A and 108C of Chapter 41, of the General Laws of the Commonwealth of Massachusetts, there shall be established plans which may be amended from time to time by vote of the Town at the Town Meeting:
- 1) classifying positions in the service of the Town, other than those filed by popular election, those under the direction and control of the School Committee, the position of Town Counsel and certain positions for which the compensation is on a fee basis or the incumbents of which render professional intermittent or causal service and which do not appear in Section 10.4 following and those positions covered by contracts with the Town, into groups and classes doing substantially similar work or having substantially similar responsibilities;
  - 2) authorizing a compensation plan for positions in the classification plan;
  - 3) providing for the administration of said classification and compensation plans, and
  - 4) establishing employee selection standards, work policies, and benefits for employees occupying positions in the classification plan.
- B) Definitions – As used in these by-laws, the following words and phrases shall have the following meanings unless a different construction is clearly required by the context or by the laws of the Commonwealth of Massachusetts:
- “**Administrative Authority**”, the elected or appointed official of board having jurisdiction over a function or activity;

## ARTICLE 10 (10.1B cont.)

“**Anniversary Date**”, one year from the date of appointment, the date of the last step increase or the date of promotion whichever is applicable;

“**Board**”, the Board of Selectmen;

“**Class**”, a group of positions in the Town service sufficiently similar in respect to duties and responsibilities so that the same descriptive title may be used to designate each position allocated to the class, that the same qualifications shall be required of the incumbents, that the same tests of fitness may be used to choose qualified employees and that the same scale of compensation can be made to apply with equity;

“**Classification**”, class title- plus class specifications which are to be on file with the Board of Selectmen and which are incorporated by reference;

“**Compensation Grade**”, a range of salary or wage rates appearing in Section 10.4;

“**Continuous Employment**”, uninterrupted employment (either full-time or part-time), except for required military service and for authorized vacation or other leave of absence;

“**Department**”, any department, board, committee, or other agency of the Town subject of these by-laws;

“**Employee**”, an employee of the Town occupying a position in the classification plan;

“**Full-time Employment**”, employment for not less than five days a week for fifty-two weeks per annum minus legal holidays and authorized leave of absence including vacation, sickness, bereavement or other reason;

“**Position**”, an office or post of employment in the Town service with duties and responsibilities calling for the full-time, part-time or seasonal employment of one person in the performance and exercise thereof.

“**Promotion**”, a change from a position of lower class and/or compensation grade to a position with greater responsibilities in a higher class and/or compensation grade;

“**Range**”, the dollar difference between minimum and maximum rates;

“**Rate**”, a sum of money designated as compensation for personal services on a hourly, daily, weekly, monthly, annual or other basis;

“**Seasonal Employment**”, employment on a seasonal rather than a year round basis;

“**Group**” or “**Occupational Group**”, a group of classes designated by occupation as appearing in Section 10.4;

“**Increment**”, the dollar difference between step rates;

“**Maximum Rate**”, the highest rate in a range, which an employee normally is entitled to obtain;

“**Minimum Rate**”, the lowest rate in a range, being normally the hiring rate of a new employee;

“**Part-time Employment**”, employment for less than full-time weekly employment;

“**Permanent Position**”, a full time or part-time position in the Town service which has required or which is likely to require the services of an incumbent in continuous employment for a period of fifty-two calendar weeks per annum;

“**Step Rate**”, a rate in a range of a compensation grade;

## **ARTICLE 10 (10.1B cont.)**

**“Temporary Position”**, a position in the Town service which requires or is likely to require the services of an incumbent for a period less than fifty-two calendar weeks in continuous employment;

**“Town”**, the Town of Freetown

- C) **Personnel Policy** – The following personnel policy, having been signed and approved by the Board of Selectmen of the Town on the eighth day of September 1975, is hereby incorporated into the personnel by-laws of the Town;

It is the declared personnel policy of the Town of Freetown that:

- 1) Employment in the town government shall be based on merit and fitness, free of personal and political consideration, free of discrimination because of age, sex, race, national, or ethnic origins, or religion, and free of discrimination against the physically handicapped;
- 2) Just and equitable incentive and conditions of employment shall be established and maintained to promote efficiency and economy in the operation of town government;
- 3) Positions having similar duties and responsibilities shall be classified and compensated on a uniform basis;
- 4) Appointments, promotions and other actions requiring the application of merit shall be based on qualifications, performance and evaluation;
- 5) High standards of morale shall be maintained by the fair and equitable administration of this policy and by every consideration of the rights and interests of all employees consistent with the best interests of the public and of the Town;
- 6) Continuity of employment with the Town shall be subject to good behavior, the satisfactory performance of work, the necessity for the performance of work, and the availability of appropriated funds.

### **10.2 Administration and Amendment**

#### **A. Administration**

- 1) The Board of Selectmen, referred to herein as the Board, shall be responsible for the administration of the classification and compensation plans and these by-laws. The Board shall establish such procedures as it deems necessary for the proper administration of said plans and by-laws. The Board may employ assistance and incur expenses as deemed necessary subject to the appropriation of funds therefore.
- 2) Adequate personnel records of all employees occupying positions subject to the classification and compensation plans shall be maintained by and held in the custody of the Board.
- 3) The Board from time to time of its own motion, shall investigate the work the work features and rates of salaries or wages of any or all positions subject to the provisions of these by-laws. Such reviews shall be made at such intervals as determined to be necessary and to the extent to which the Board considers practicable.
- 4) The Board shall maintain written job descriptions or specifications of the classes in the classification plan, each consisting of a statement describing the essential nature of the work and the characteristics that distinguish the class from other classes. The description of any class shall be construed solely as a means of identification and not as prescribing what the duties or responsibilities of any position shall be, or as modifying, or in any way affecting the power of any administrative authority, as otherwise existing, to appoint, to assign duties to, to direct and control the work of any employees under the jurisdiction of such authority.

## ARTICLE 10 (10.2 cont.)

- 5) Upon the recommendation of a department head, supported by evidence in writing or special reasons and/or exceptional circumstances satisfactory to the Board, the Board may authorize an entrance rate higher than the minimum rate for such a position, or may deny an annual step rate increase, or such other variance in the compensation plan as it may deem necessary for the proper functioning of Town services. No variance shall become effective unless, or until the necessary funds have been appropriated therefore.

### **B. Amendment of the Plans**

- 1) The classification plan and/or the compensation plan and/or other provisions of these by-laws may be amended by vote of the Town at a town meeting in the same manner as other by-laws of the Town may be amended.
- 2) A proposed amendment, other than one originating with the Board, shall be filed with the Town Clerk, who shall record same and submit three copies thereof to the Board. The Board shall hold a public hearing to consider any such proposed amendment, after having given at least ten days written public notice thereof.
- 3) The Board, of its own motion, may propose an amendment to the classification plan, compensation plan, or other provisions of these by-laws after having held a public hearing on the proposed amendment according to the procedure outlined in the preceding sub-section.
- 4) The Board shall report for its recommendations on any proposed amendment to the Finance Committee for its consideration and shall make known its recommendations with regard to any amendment at the Town Meeting at which such amendment is to be acted upon.

### **10.3 Classification Plan**

- 1) All positions in the Town service, except those excluded in Section 10.1(A), are hereby classified by titles appearing in the "Classification Plan" which may be amended from time to time by vote of the Town at a town meeting and which is to be on file with the Board of Selectmen and which is incorporated by reference.
- 2) The title of each class, as established by the classification plan, shall be title of each incumbent of a position so allocated and shall be used on payrolls, budget estimates, and other official records pertaining to the position.
- 3) Whenever a new position is established by the fixing of compensation thereof, or the duties of an existing position are so changed that, in effect, a new position is created, and upon presentation of substantiating data satisfactory to the Board, the Board shall allocate such new or changed position to its appropriate class.
- 4) No position may be reclassified until the Board shall have determined that such reclassification is consistent with the classification plan.

### **10.4 Compensation Plan**

#### **A. General Provisions**

- 1) The compensation plan shall consist of schedules which provide minimum and maximum salaries or wages for individual compensation grades. A "General Schedule" shall be maintained for hourly compensation grades; a "Special Schedule" shall be maintained for salaried compensation grades; and, an "Appointed Schedule" shall be maintained for appointed positions of less than full time employment. Such schedules may be amended from time to time by vote of the Town at a town meeting and are incorporated by reference.
- 2) No administrative authority shall fix the compensation of any employee in a position in the classification plan except in accordance with the compensation plan.

## ARTICLE 10 (10.4A cont.)

- 3) No person shall be paid as an employee in any position subject to the provisions of the classification plan under any title other than those appearing in the classification and compensation plans.
- 4) Each employee shall continue to be paid on the same basis as in effect at the time of the adoption of these by-laws unless otherwise provided in the compensation plan. All employees employed by the Town at the time of the adoption of these by-laws shall have the initial date of July 1, 1986.
- 5) An employee in continuous employment shall, subject to the provisions of Section 10.2 (5), Paragraph 5, annually receive the step increase between his or her present step and the next higher step for the grade level for his or her position.

Any employee who will have attained more than twenty years of creditable service with the Town upon retirement and who has given advanced notice to the Board of not less than one year, nor more than three years of their intention to so retire shall receive, in addition to such steps as they are otherwise entitled, a pre-retirement step increase, which shall be equivalent to two regular step increases. Such pre-retirement step shall become effective on the first day of the next calendar year, or on the first day of the next fiscal year, following such notice, whichever shall come first. An employee who has not retired three years after having given advance notice of intent to retire shall revert to such pay step as they would have been had they not received the pre-retirement step, and they shall forfeit the next two regular steps.

- 6) An employee occupying a seasonal position shall be paid the next higher step in accordance with the provisions of the preceding paragraph and only after the completion of the annual period of seasonal employment specified by the administrative authority for the class to which he or she is appointed and then only upon recommendation of the administrative authority.
- 7) An employee receiving a promotion to a high position or to a new position as defined in Section 10.3 (3), or higher compensation grade, shall, upon assignment resulting from such promotion, receive such step rate in the new position as recommended by the administrative authority but, in no case, at a lower rate of compensation than two steps higher than his or her former grade and step before the promotion.
- 8) The step rate adjustments provided in this section shall be subject to the availability of appropriated funds and shall be tied to satisfactory work performance as provided for in applicable provisions of Section 10.6 (G) (H).
- 9) The prescribed rates of compensation provided for in this section shall not include allowances for official travel or other expenditures incurred on behalf of the Town. Employees shall be reimbursed for such expenditures in accordance with Section 10.6 (F).
- 10) Prior to April 1<sup>st</sup> of each year, the Board of Selectmen shall hold a public hearing, after having given at least ten days written public notice thereof, to determine what, if any, annual cost of living increase shall apply to the Compensation Plan Schedules. At the conclusion of such hearing, the Board shall determine what, if any, annual cost of living increase shall be applied to the Compensation Plan Schedules effective for the next Fiscal Year. Any such annual cost of living increase shall be applied as a percentage increase and shall be applied to all grades and steps equally.

### 10.5 Employee Selection

#### A. Recruitment

- 1) In order to attract competent employees to fill vacancies in the Town service, the Board shall cause notices for job vacancies to be publicly advertised in at least one newspaper of general circulation within the Town.
- 2) Applicants for vacancies will not be limited to residents of the Town, but priority consideration shall be given to Town residents whenever possible.

## ARTICLE 10 (10.5A cont.)

- 3) All applicants for job vacancies shall be required to complete a standardized employment application form which shall be filed with the administrative authority and made part of the personnel records of the Town.
- 4) The administrative authority may cause character reference checks to be made of all applicants for positions coming under their jurisdiction, and the “findings thereof shall be made part of the personnel records of the Town.”
- 5) All applicants shall be interviewed by the administrative authority to determine level of skills, training and performance.

### **B. Appointment**

- 1) Before appointment to a position included in the classification plan of the Town which requires continuous employment, whether full-time or part-time, a candidate may be required to pass a physical examination satisfactory to the Board. The examining physician shall be designated by the Board and the examination shall be conducted at the expense of the Town . The examining physician shall advise the Board as to whether or not, in his professional judgment, the applicant is physically qualified to perform the duties of the position being sought.
- 2) Appointment to a position on the classification plan shall be the responsibility of the administrative authority having jurisdiction over the duties of that position.
- 3) The administrative authority shall be responsible for orienting new employees to their jobs, work policies of the Town, and performance standards expected of them. In addition, the administrative authority shall provide necessary supervisory and on-the-job training and assessment training needs to establish necessary training programs.

### **C. Promotions**

- 1) Vacancies in positions above the entrance level shall be filled by promotion whenever, in the judgment of the administrative authority, it is in the best interest of the Town service to do so. Promotions shall give appropriate consideration to the applicant’s qualifications, record of work performance and seniority.
- 2) Notice of vacancies in such positions shall be made known to all affected employees with the classification group.

## **10.6 Work Policies**

### **A. Work Week**

The work week for positions in the classification and compensation plans shall be established and maintained by the Board of Selectmen based on the needs of the Town.

### **B. Overtime Compensation**

All full-time employees shall be compensated at one and one-half times their regular rate for hours worked in excess of those constituting their normal work day of eight hours or normal work week, which in all cases shall be considered to be 40 hours. The overtime rate of one half the regular rate will only apply to work performed by an employee within his/her department(s), and all work performed for other Boards or Departments will be compensated at the regular rate established for the work actually performed unless the total hours exceed 40 hours per week. All overtime will be subject to the Federal Fair Labor Standards Laws and other Regulations regarding employees. Police Department and Fire Department personnel shall be paid in accordance with the standards and exceptions contained in the Fair Labor Standards Act.

## ARTICLE 10 (10.6 cont.)

### C. Paid Holidays

- 1) The following days shall be recognized as legal holidays within the meaning of these by-laws and employees shall be excused from all duty except those of an emergency nature as determined by the appropriate administrative authority of those required to maintain essential Town services:

New Year's Day	Labor Day
Martin Luther King Day	Columbus Day
Washington's Birthday	Veterans' Day
Patriot's Day	Thanksgiving Day
Memorial Day	Christmas Day
Independence Day	

- 2) A full-time employee shall be entitled to these designated paid holidays on the following terms:
  - a) If paid on an annual basis, he/she shall be granted each holiday without loss of pay.
  - b) If paid on an hourly basis, he/she shall receive one days pay at his/her regular rate based on the number of hours regularly worked on the day on which the designated holiday occurs.
- 3) A part-time employee in continuous employment shall be entitled to these designated paid holidays on the following terms;
  - a) This benefit shall be limited to employees whose work each year is not less than 1,000 hours. (Based on 50 working weeks each year, it would be minimum of 20 hours per week.)
  - b) Compensation paid for such holiday shall be equal to the pay received by the part-time employee in continuous service for the average of hours worked per week for the base period divided by five. The Base Period shall be the ninety (90) day period immediately preceding the Holiday.
- 4) An employee in season employment or in other than continuous employment status shall not be entitled to the paid holiday benefits set forth in this section.

### D. Vacation Policy

- 1) A full-time employee commencing employment shall be granted five (5) working days' vacation without loss of pay in the first year with said vacation to be taken only after the completion of six (6) months employment during that year. During the second year, a full-time employee shall be granted ten (10) working days' vacation without loss of pay, of which five (5) days to be taken only after the completion of eighteen months of continuous employment. Thereafter, a full-time employee shall be granted ten (10) days' vacation without loss of pay per year. After five years of continuous employment, each employee will receive fifteen (15) days' vacation, and after ten (10) years of continuous employment each employee will receive twenty (20) days vacation, and after fifteen (15) years of continuous employment, each employee will receive one (1) additional day of vacation for each year worked up to twenty (20) years. In no instance shall an employee receive pay for more than fifty-two weeks in any year.
- 2) A part-time employee in continuous employment during any year shall be granted five (5) working days' vacation to be taken only after the completion of six months continuous employment during the first year. Such vacation pay shall be determined and based on the average part-time weekly rate of pay for that position. During the second year, a part-time employee in continuous employment status, after the completion of eighteen months of service, shall be granted ten (10) working days' vacation without loss of pay which shall be based on the average part-time weekly rate of pay for the position. Thereafter, a part-time employee in continuous service shall be granted (10) working days' vacation without loss of pay per year. Said pay shall likewise be based on the average weekly rate of pay for the position. After seven years of continuous employment each employee will receive fifteen (15) days vacation and after ten (10) years of continuous employment each part-time employee will receive twenty (20) days' vacation. All vacation time shall be taken during each year, and in no instance shall any employee receive pay for more than fifty-two (52) weeks in any one year.

## ARTICLE 10 (10.6D cont.)

- 3) An employee in seasonal employment or in other than continuous employment status shall not be entitled to the paid vacation benefits set forth in this section.
- 4) Upon the death of an employee who is eligible for vacation under these rules, payment shall be made to the spouse or to the estate of the deceased in an amount equal to the vacation allowance as earned up to the employee's death but which has not been taken.
- 5) Employees who are eligible for vacation under these rules and whose services are terminated by dismissal through no fault or delinquency of their own, by retirement, or by entrance into the Armed Forces shall be paid an amount equal to the vacation allowance as accrued but not taken up to such termination of employment

### E. Paid Leave

- 1) A full-time employee shall be entitled, in each year, to one day leave with pay, to be used for illness or accident, for each month of continuous employment during that year. If such leave is not used in any year, then that unused portion may be accumulated for use in subsequent years. Leave for illness or accident in excess of one hundred (100) days shall be granted only in unusual circumstances and only with the approval of the administrative authority and the Board.

UNUSED SICK LEAVE REIMBURSEMENT – The total unused sick leave a full-time employee may accumulate is one (100) days. All sick leave accumulated over one hundred (100) days shall go into an Employee's retirement sick leave reimbursement account. At retirement or death, an Employee shall be paid for all unused sick leave days in the Employee's retirement sick leave reimbursement account up to a maximum amount of sick leave days to be accumulated of one hundred thirty-five (135) days. The rate of pay for these days shall be one (1) day's pay for every three (3) days so accumulated up to a maximum of forty-five (45) days pay. At the death of an employee, payment shall be made to his or her surviving spouse, if any, or in the absence of a surviving spouse, to his or her estate. In all cases such leave days shall not include Saturdays, Sundays, or holidays as defined in Section 10.6 (1). In the event of illness or accident during an employee's vacation period the vacation duration shall not be increased or altered in any way.

- 2) A part-time employee in continuous service shall be entitled, in each year to one day leave with pay, to be used for illness or accident, for each month of continuous employment during that year. If such leave is not used in any fiscal year, then the unused portion may be accumulated for use in subsequent years, up to a maximum of 30 days leave. Leave in excess of 30 days shall be subject to the provisions of (1) above.
- 3) An employee shall be entitled to leave with pay for illness or accident only, if, when, and as such leave is earned. In no event shall earned days for illness or accident be construed as additional vacation allowance. In the event of termination of employment for any reason, there shall be no compensation paid by the Town for any days accumulated but not actually used by the employee.
- 4) Leave with pay shall be granted to full-time and part-time employees in continuous service for death in the immediate family, for jury duty, for military training with a National Guard or reserve unit, or for other unavoidable absence from assigned duty as may be determined by the Board. All such leaves shall be subject to Board approval.
- 5) Up to three (3) days of sick leave each year may be utilized in cases of emergency or critical illness in employee's immediate family or for other personal reasons which require absence with the approval of the Department Head.

### F. Reimbursable Expenses

- 1) Employees shall be reimbursed by the Town for use of private vehicle necessary for the official conduct of Town Business at a rate equal to that allowed by the Internal Revenue Service for business use or automobiles. Such mileage expense reimbursement shall be subject to the approval of the administrative authority.

## ARTICLE 10 (10.6F cont.)

- 2) Out-of pocket expenses incurred on behalf of the town shall be reimbursed to the employee subject to the approval of the administrative authority.
- 3) Out-of pocket tuition expenses in the amount of 50-per cent shall be reimbursed for job related educational courses, upon successful completion or a passing grade of the course, not to exceed one course per year, subject to the prior approval of the administrative authority and the Personnel Board.

### G. Probation

- 1) Employees subject to the provisions of the personnel-by-laws and classification and compensation plans, shall at the time of their original appointment, be subject to a period of probation. The normal period of probation shall be one year, provided that the Board acting upon the recommendation of the administrative authority may specify a longer probationary period in individual cases. No probationary period may be reduced to less than twelve months.
- 2) Continuous employment in the service of the Town shall be determined by satisfactory performance of work which shall be annually evaluated by the administrative authority. The work and conduct of probationary employees shall be subject to close scrutiny and if found to be below standards satisfactory to the administrative authority, the employees may be removed or demoted at any time during the probationary period. Such removals or demotions shall not be subject to review or appeal.
- 3) An employee shall be retained beyond the end of the probationary period only if the administrative authority affirms in writing to the Board that the services of the employee have been found to be satisfactory.

### H. Separations

- 1) The tenure of every employee in continuous employment status shall be conditioned on good behavior and the satisfactory performance of duties. Any employee may be temporarily separated by layoff or suspension, or permanently separated by resignation or dismissal.
- 2) Whenever there is lack of work or lack of funds requiring reductions in the number of employees in department or division of the town service, the required reduction shall be made in such job class or classes as the department head may designate provided that employees shall be laid off in the inverse order of their relative length and quality of service and determined by rules governing the evaluation of service. Within each affected job class all temporary employees shall be laid off before any employees in continuous service.
- 3) When in judgment of the administrative authority an employee's work performance or conduct justifies disciplinary action short of dismissal, the employee may be suspended for a period of time without pay. A suspended employee may not request a hearing before the Board unless the suspension is for more than fifteen working days, or unless the employee has already received a previous suspension within the six months immediately prior thereto.
- 4) An employee in continuous service may be dismissed or demoted whenever, in the judgment of the administrative authority, the employee's work or misconduct so warrants. When the administrative authority decides to take such action he shall file with the employee and the Board a written notification containing a statement of the substantial reasons for the action. The employee shall be notified in writing not later than two days before the effective date of the action. The notice shall inform the employee that he shall be allowed two calendar weeks from the effective date of the action to file a request for a hearing before the Board.
- 5) If the employee files a request for a hearing in writing within the prescribed period, the Board shall schedule a hearing within two calendar weeks. At the discretion of the employee, the hearing may be held in closed session or open to the public.
- 6) In conducting a hearing the proceedings shall be informal and it shall be assumed that the action complained of was taken in good faith unless proved otherwise.

## ARTICLE 10 (10.6H cont.)

- 7) If the Board finds the action of the administrative authority was in apparent violation of the Town Personnel Policy as expressed in Section 10.1(C). or that the administrative authority failed to follow the proper procedure outlined in (4) above, the employee shall be reinstated to his former position without loss of pay. In all other cases the Board may sustain or modify the action taken by the administrative authority.
- 8) An employee may resign his position at any time by notifying the administrative authority in writing. An employee resigning in good standing may be eligible for reinstatement within two years after the effective date of resignation.
- 9) An employee holding a position which is subject to periodic appointment and who has held continuous employment with the Town for three (3) years or more, shall, if he is denied reappointment to his/her position, be entitled to a hearing in the same manner as provided by this Section for employees who may be dismissed or demoted.

### I. Employee Group and Retirement Benefits

- 1) The Town shall continue to pay that portion of the premium for group hospital, medical, surgical and life insurance, under the Bristol County Group Plan or any other group hospital, medical and surgical insurance made available for eligible employees, as is authorized under certain provisions of Chapter 32-B of the General Laws of the Commonwealth.
- 2) Eligible employees automatically become members of the Bristol County Contributory Retirement Plan and as such are covered by the retirement benefits of this plan.
- 3) Eligible employees shall continue to be covered by Workmen's Compensation Insurance.

### J. Longevity Policy *STM 10/22/2001, ATM 6/7/2010*

Full-time employees covered by these by-laws shall be entitled to longevity pay. Effective July 1, 2010 longevity pay shall be computed on the following basis.

After 5 years of service	\$300.00
After 10 years of service	\$350.00
After 15 years of service	\$425.00
After 20 years of service	\$500.00
After 25 years of service	\$600.00

Payment shall be a lump sum payment made within thirty (30) days of the annual date upon which the employee becomes entitled to the longevity pay.

## 10.7 Effect of Partial Invalidity

The invalidity of any section of these by-laws shall not invalidate any other section or provision thereof.

## 10.8 Positions

- 1) **Administrative Assistant**  
**Building Commissioner**  
**Call Fire Personnel**  
**Council on Aging Director**  
**Library Director**  
**Dog Officer**  
**Election Workers**

Said positions shall be eligible for periodic pay increases, when deemed appropriate, in the same manner as those granted to employees covered by collective bargaining agreements. And further the holder of positions named above will not be involved in any negotiations with respect to salaries. (*ATM 5/7/01*)

## ARTICLE 10 (10.8 cont.)

- 2) **Fire Chief** - The Fire Chief's Compensation shall be 1.8 times the Step 3 Firefighter rate contained in the Firefighters collective bargaining agreement, together with all of the fringe benefits provided for under said collective bargaining agreement.
- 3) **Fire Regular Deputy Chief** – The Fire Regular Deputy Chief's compensation shall be ten (10%) percent above the Fire Captain's rate contained in the Firefighters' collective bargaining agreement, together with all of the fringe benefits provided for under said collective bargaining agreement.
- 4) **Town Accountant, Election Officers, Registrars** – Said positions shall be eligible for periodic pay increases, when deemed appropriate, in the same manner as those granted to employees covered by collective bargaining agreements.
- 5) **Miscellaneous** -
 

Civil Defense Director	\$1050.00
Weights & Measurers	\$ 656.00
Poundkeeper	\$ 200.00
Animal Inspector	\$ 695.00
Veterans' Agent	\$2900.00

<u>Positions</u>	<u>Applicable Grades</u>
Asst. Building Inspector	GS 10 thru GS 11
Lock-up Attendant	GS 4 thru GS 5
Assistant Treasurer	GS 10
Student Police Officer	
Assistant Town Clerk	
Council on Aging Van Drivers	
Assistant Assessor	GS 9
Police Chief	SS 9 thru SS 10
Senior Clerks	GS 5 thru GS 8
Junior Clerks	GS 4 thru GS 6
Police & Fire Signal Operator	GS 6 thru GS 7 Full Time GS 5 thru GS 6 Part Time
*Senior Dispatcher/Secretary	GS 8 thru GS 9
Custodian	GS 4 thru GS 6
Recreation	GS 1 thru GS 2
Recreation Director	GS 4 thru GS 5
Machine Operators	GS 7 thru GS 10
Truck Drivers	GS 6 thru GS 7
Mechanic	
Assistant Mechanic	
Landfill Operator/Building Dept.	
Asst. Landfill Operator/Building	
Maintenance Worker	
Library Worker	GS 9
Librarian	GS 4 thru GS 6
Library Technician	GS 3 thru GS 4
Library Custodian	GS 3 thru GS 4
Assistant Dog Officer	GS 7

\*Dispatcher shift differential: 6% of applicable grades. Differential shall apply on Saturday, Sundays, Holidays, and to night shifts during the week.

**TOWN OF FREETOWN  
PROTECTIVE BY-LAWS**

as of 11/08/2010

**ARTICLE 11**

**ZONING BY-LAWS OUTLINE**

11.1	Purpose .....	31
11.2	Definitions.....	31
11.3	Lot Sizes & Setback Requirements.....	34
	A: Lot size-Area.....	34
	B: Frontage.....	34
	C: Lot Sizes Minimum Requirements.....	34
	D: Lot Sizes: Existing Lots.....	34
	E: Lot Coverage.....	34
	F: Additional Dwelling Units- Minimum Requirements.....	34
	G: Setback Requirements.....	35
	1. Single family and Duplex Structures on pre-existing lots	
	2. All other circumstances	
	H: Residential Parking requirements.....	37
	I: Lots created prior to May 5, 1980.....	37
11.4	Permits .....	37
11.5	Administration.....	37
	A. Special Permit Granting Authority.....	37
	B. Board of Appeals.....	37
11.6	Special Permit Use – Multi-Unit Dwellings, Apartments, Townhouses, Condominiums, etc.....	38
	A. Purpose .....	38
	B. Special Permit.....	38
	C. Special Permit Requirements.....	38
	D. Density.....	38
	E. Frontage.....	38
	F. Minimum Setbacks.....	39
	G. Access and Parking .....	39
	H. Outside Use and Recreational Space Requirements.....	39
	I. Private water supply and sewerage disposal system.....	39
	1. Waste Disposal	
	J. Fifty foot buffer zone.....	39
	K. Traffic Study.....	39
	L. Certification by a Registered Professional Engineer.....	39
	M. Utility Provision.....	39
	1. Accessory Use Buildings	
	N. Ability of Special Permit Authority.....	39
	O. Invalidity.....	39
11.7	Trailer parks.....	40
	A. No person shall park, store or occupy a mobile home except.....	40
	B. Overnight Occupancy of Mobile Homes.....	40
	C. Trailers.....	40
	D. Mobile homes: prior non-conforming use.....	40

## ARTICLE 11 (Outline cont.)

11.8	Construction for Which a Building Permit was Legally Issued.....	41
	A. Exempted Uses.....	41
	B. Accessory Use.....	41
	A. Non-conforming use discontinued or abandoned after two years.....	41
	D. Enforcement.....	41
	D. Violation of the provisions of the laws.....	41
	F. Invalidity.....	41
11.9	An Appeal to the Board of Appeals.....	41
11.10	Swimming Pools.....	41
	A. Permitted accessory use.....	41
11.11	Floodplain Overlay District	
	A. Statement of Purpose.....	41
	B. Floodplain District Boundaries and Base Flood Elevation and Floodway Data.....	42
	C. Base Flood Elevation on Floodway Data.....	42
	D. Notification of Watercourse Alteration.....	42
	E. Use Regulations.....	42
	F. Permitted Uses.....	43
	G. Definitions.....	43
11.12	Planning Board.....	45
11.13	Hazardous Waste Facilities.....	45
11.14	Private or Commercial Dump.....	45
11.15	Home Occupations.....	45
11.16	Special Permits – Home Occupations.....	45
11.17	100 foot High Structures.....	45
11.18	Zoning Districts.....	46
	A. Purpose.....	46
	B. Scope.....	46
	C. Minimum Provisions.....	46
	D. Establishment of Districts.....	46
	1. Types of Districts	
	2. Location of Districts	
	E. Industrial Districts (1), (I/2) .....	46
	F. Village Residential District and Village Business.....	47
	1. Purpose	
	2. Density and Dimensional Regulations	
	3. Uses Permitted by Right, by Special Permit and Prohibited	

## ARTICLE 11 (11.18 Outline cont.)

G. District Regulation.....	48
1. Existing Uses and Non-Conforming Uses	
a.) Reconstruction of Non-Conforming Structure	
b.) Abandonment	
c.) Expansion, Alteration or Change of Use of One or Two Family Residential Non-Conforming Uses	
d.) Expansion, Alteration or Change of Use of Non-Conforming Uses other than One or Two family residential uses	
H. Uses.....	48
1. Table of Use Regulations	
I. Special Permits.....	52
1. Application	
2. Special Permits Table of Use Regulations	
J. Special Permits for Adult Entertainment Establishments.....	53
1. Authority	
2. Purpose	
3. Minimum Provisions	
4. Compliance	
5. Appeals	
6. Invalidity	
11.19 Accessory Apartment .....	54
A. Purpose.....	54
B. Residential District/Village Residential.....	54
C. General Use District.....	54
11.20 Signs.....	55
A. Authority .....	55
B. Purpose and Scope.....	55
C. Administration and Enforcement.....	55
1. Applicability	
2. Building Inspector	
3. Special Permit Granting Authority	
4. Registration of Signs	
5. Length of Time given for Compliance	
6. Application	
7. Building Inspector Action	
8. Special Permits	
9. Fees	
D. General Regulations.....	56
1. General Guideline	
2. Permitted Government or Special Signs	
3. Residences	
4. Religious Institutions	
5. Temporary Signs	
a) Permitted Temporary Signs	
b) Temporary Sign Limitations	

## ARTICLE 11 (11.20 Outline cont.)

6. Directional Signs	
7. Illumination	
8. Height	
9. Signs Cannot Interfere with Traffic	
10. Construction	
11. Maintenance	
12. Prohibited Signs	
13. Signs Exempt from Permit and License Requirements	
E. Residential Districts.....	59
1. Multi-family Dwelling Developments	
F. General, Business & Industrial Districts.....	59
1. Wall Signs	
2. Window Signs	
3. Projecting Signs or Hanging Signs	
4. Standing Signs	
5. Signs at Gasoline Filling Stations and Garages	
6. Off Premises Signs	
7. Menu Boards	
G. Non-Conformance of Signs.....	60
H. Violations.....	60
1. Inconsistent with Plan or Permit	
2. Failure to Obtain Permit	
3. Failure to Remove Sign	
4. Separate Violation Each Day	
5. Separate Violations	
I. Invalidity.....	61
11.21 Drive Through By-Law .....	61
A. Purpose.....	61
B. All drive-through facilities shall comply with the following standards.....	61
C. Invalidity.....	61
11.22 Retail and Wholesale Establishments.....	62
A. Purpose.....	62
B. Definitions.....	62
C. Standards.....	62
D. Invalidity.....	63
11.23 Site Plan Review By-law.....	63
A. Findings.....	63
B. Powers and Administrative Procedures.....	63
C. Purposes.....	63
11.24 Land-Based Wind Energy Facilities.....	64
A. Purpose.....	64
B. Applicability.....	64
C. Definitions.....	64

## ARTICLE 11 (11.20 Outline cont.)

D. General Requirements for all Wind Energy Facilities.....	65
1. Compliance with Laws, Ordinances and Regulations	
2. Building Permit and Building Inspection	
3. Fees	
E. Site Plan Review.....	65
1. General	
2. Required Documents	
F. Site Control.....	66
G. Operation & Maintenance Plan.....	66
H. Utility Notification.....	66
I. Temporary Meteorological Towers (Met Towers) .....	66
J. Design Standards.....	66
1. Appearance, Color and Finish	
2. Lighting	
3. Signage	
4. Utility Connections	
5. Appurtenant Structures	
6. Height	
K. Safety and Environmental Standards.....	67
1. Emergency Services	
2. Unauthorized Access	
3. Setbacks	
4. Setback Waiver	
5. Shadow/Flicker	
6. Sound	
7. Land Clearing, Soil Erosion and Habitat Impacts	
L. Monitoring and Maintenance.....	68
1. Wind Energy Facility Conditions	
2. Modifications	
M. Abandonment or Decommissioning.....	68
11.25 South Main Street Corridor Overlay.....	69
A. Purposes.....	69
B. Special Permit Granting Authority.....	69
C. Relationship to Other Districts.....	69
D. Requirements.....	69
1. Traffic Impact Study	
2. Curb Cut Permit	
3. Multiple Parcel Regulation	
E. Description.....	70
11.26 Adult Retirement Community.....	70
A. Purpose and Scope.....	70
B. Definitions.....	70
C. Restrictions.....	71
D. Operation.....	72

## ARTICLE 11 (11.20 Outline cont.)

11.27 Continuing Care Retirement Community.....	72
A. Purpose and Scope.....	72
B. Definitions.....	72
C. Restrictions.....	74
D. Operation.....	75
11.28 Large-Scale Ground-Mounted Solar Photovoltaic Installations	
A. Purpose.....	75
B. Applicability.....	75
C. Definitions.....	75
D. General Requirements for all Large Scale Solar Power Generation Installations..	76
1. Compliance with Laws, Ordinances and Regulations	
2. Building Permit and Building Inspection	
3. Fees	
E. Site Plan Review.....	76
1. General	
2. Required Documents	
F. Site Control.....	77
G. Operation & Maintenance Plan.....	77
H. Utility Notification.....	77
I. Dimension and Density Requirements.....	77
1. Setbacks	
2. Appurtenant Structures	
J. Design Standards.....	77
1. Lighting	
2. Signage	
3. Utility Connections	
K. Safety and Environmental Standards.....	78
1. Emergency Services	
2. Land Clearing, Soil Erosion and Habitat Impacts	
L. Monitoring and Maintenance.....	78
1. Solar Photovoltaic Installation Conditions	
2. Modifications	
M. Abandonment or Decommissioning.....	78
1. Removal Requirements	
2. Abandonment	
3. Financial Surety	

## ZONING BY-LAWS ATM 10/7/96, ATM 5/6/02

**11.1 PURPOSE:** The purpose of this By-Law is to promote the health, safety, convenience, morals and welfare of the inhabitants of the town of Freetown. For its use in conjunction with this By-Law, the current Town of Freetown Zoning Map, signed by the Planning Board and filed with the office of the Town Clerk, together with all explanatory matter thereon, is hereby incorporated in, and made a part of this By-Law. *ATM 5/2/78, STM10/27/08*

**11.2 DEFINITIONS:** For the purpose of these by-laws certain terms and words shall have the following meanings. Words used in the present tense include the future; the singular includes the plural, the plural includes the singular; the word "used" includes the words "designed", "arranged", "intended" or "offered" when in conjunction with occupancy or how something is to be used; the words "building", "structure", "lot", "land" or "premises" shall be construed as though followed by the words "or any portion thereof"; the word "shall" is always mandatory and not merely directory; the word "may" is intended to be permissive; the word "person" includes corporations, trusts, estates, partnerships, or other entities as well as an individual. Terms and words not defined herein but defined in the State Building Code or By-Laws of the Town of Freetown shall have the meanings given therein unless a contrary intention clearly appears. Words not defined in either place shall have the meaning given in the Merriam Webster Dictionary, Home and Office Edition. Uses listed in the Table of Use Regulations under the classes Business and Industrial Uses shall be further defined by the current Standard Industrial Classification Manual published by the Executive Office of the President, Office of Management and Budget. *STM 10/27/08*

**Accessory Apartment:** An accessory Apartment is a second dwelling unit located within a structure originally designed, constructed and occupied as a detached single-family dwelling unit, subordinate in size to the principal dwelling unit in a manner that maintains the appearance of the structure as a single-family home. *STM 3/24/97*

**Accessory Building or Use:** A building or use customarily subordinate to and incidental to and located on the same lot with the principal building or use, except that if more than 30 percent of the lot area is occupied by such building or use, it shall no longer be considered accessory. *STM 5/1/89*

Adult Entertainment Establishments shall include and be defined as follows: *STM 3/24/97*

- 1) **Adult Bookstore:** An establishment having greater than ten percent (10%) of its stock in trade printed matter, books, magazines, and other matter which are distinguished or characterized by their emphasis depicting, describing, or relating to sexual conduct or sexual excitement as defined in M.G.L. Chapter 272, § 31.
- 2) **Adult Motion Picture Theater:** An enclosed building or outdoor facility used for presenting material distinguished or characterized by an emphasis on matter depicting, describing, or relating to sexual conduct or sexual excitement as defined in M.G.L. Chapter 272, § 31.
- 3) **Adult Paraphernalia Store:** An establishment having greater than ten percent (10%) of its stock devices, objects, tools, or toys which are distinguished or characterized by their association with sexual activity, including sexual conduct or sexual excitement as defined in M.G.L. Chapter 272, § 31.
- 4) **Adult Video Store:** An establishment having greater than ten percent (10%) of its stock in trade, videos, movies, or other film material which are distinguished or characterized by their emphasis depicting, or relating to sexual conduct or sexual excitement as defined in M.G.L. Chapter 272, §31.
- 5) **Adult Live Entertainment Establishments:** Establishments which displays live nudity for its patrons. An establishment which provides live entertainment for its patrons which includes the display of nudity, as that term is defined in M.G.L. Chapter 272, § 31.

**Agriculture:** The use of land, buildings or structures for agriculture and farming including floriculture, aquaculture, horticulture and viticulture: farming in all its branches and the cultivation and tillage of the soil; dairying; the production, cultivation, growing and harvesting of any agricultural, floriculture or horticultural commodities; the raising of livestock, the keeping and raising of poultry, swine, cattle and other domesticated animals used for food purposes, bees, fur bearing animals; and any practices, including any forestry or lumbering operations performed by a farmer, who is hereby defined as one engaged in agriculture or farming as herein defined.

**Alteration:** A change or modification of a building or structure or the service equipment thereof, that affects safety or health and that is not classified as an ordinary repair, so as to provide no increase in its height or gross floor area.

## ARTICLE 11 (11.2 cont.)

**Banquet/meeting/reception hall:** A public or private meeting facility which may also include on-site kitchen/catering facilities. A banquet/meeting/reception hall usually serves as a location for activities such as weddings and other such gatherings by appointment only. Banquet/meeting/reception halls have limited hours of operation and usually are not open on a daily basis. *STM 10/27/08*

**Biohazards:** Biohazards are infectious agents or hazardous biological materials that present a risk or potential risk to the health of humans, animals or the environment. The risk can be direct through infection or indirect through damage to the environment. *ATM 06/07/2010*

**Bio-hazardous materials:** include certain types of recombinant DNA; organisms and viruses infectious to humans, animals or plants (e.g. parasites, viruses, bacteria, fungi); and biologically active agents (i.e. toxins, allergens, venoms) that may cause disease in other living organisms or cause significant impact to the environment or community. *ATM 06/07/2010*

**Building:** See Definition for “Structure”. *STM 5/1/89*

**Building, Attached:** A building having any portion of one or more walls in common with the adjoining buildings. *STM 3/24/97*

**Building Coverage:** That percentage of the lot area covered by the horizontal projection of the largest single floor area of the principal building plus all accessory buildings and impervious areas including accessory structures not on permanent foundations and above ground swimming pools. *STM 5/1/89, STM 10/27/08*

**Building, Detached:** A building having open space on all sides. *STM 3/24/97*

**Building, Principal:** A building in which is conducted the principal use of the lot on which it is located. *STM 3/24/97*

**Duplex House:** A free standing building exclusively for residential uses by two families but not more than two families.

**Dwelling:** A building designed or used exclusively as the living quarters for one or more families. *STM 5/1/89*

**Dwelling, Single family detached:** A single unit providing independent living facilities for one household, including permanent provisions for living, sleeping, cooking, eating and sanitation.

**Dwelling Unit:** A single independent housekeeping unit with permanent provisions for living, sleeping, eating, cooking and sanitation, occupied or intended for occupancy by one separate family. *STM 5/1/89*

**Hotel or Motel:** A building or group of buildings providing accommodations for compensation on a transient basis.

**Industry:** Extraction, developing, manufacturing, assembling, processing or treatment of raw or processed materials, parts, or assemblies using other than manual power. A **Light Industry** is one using quiet motive power and processes which do not generate more noise, odor, smoke, fumes, vibrations, glare, electrical or magnetic interference, or hazard of fire, explosion or pollution of ground water than could be expected of any of the other permitted uses in that location. A **Heavy Industry** is one generating one or more of the above neighborhood impacts.

**Lot:** An area of land in one ownership with definite boundaries recorded in the Registry of Deeds or in Land Court in accordance with State Statute, Chapter 183, § 6A. *STM 5/1/89*

**Lot Line, Front:** The property line between a lot and the street or the line defining the limit of a right of way set aside for road purposes. On a corner lot the owner shall designate one street line as the front line for the purpose of determining what line will be designated as the rear line. *STM 10/27/08*

**Lot Line, Rear:** The lot line opposite the front lot line. *STM 3/24/97*

**Lot Line, Side:** Any lot line not a front or rear lot line. *STM 3/24/97*

**Manufacturing:** Fabrication, assembly, finishing, packaging, processing or research.

## ARTICLE 11 (11.2 cont.)

**Mobile Home and/or “Trailer Coach”:** Any vehicle or object on wheels having no motive power of its own but which is drawn by or used in connection with a motor vehicle, and which is so designed and constructed, or re-constructed or added to by means of such accessories, as to permit use and occupancy thereof for human habitation whether resting on wheels, jacks, or other foundation. *ATM 3/6/71, STM 5/1/89*

**Mobile Home Park:** Any lot, track, or parcel of land used or intended to be occupied by two or more mobile homes for a period of over three weeks in any calendar year. A park shall be one unit per 40,000 square feet, excluding water and public land. *ATM 3/6/71, STM 5/1/89*

**Non-Conforming District Use:** A building or land lawfully occupied at the time of the adoption of this By-Law or of amendments thereto by a use which does not conform to the adopted regulations of the district in which it is situated.

**Recreational Vehicle:** A vehicle or vehicular attachment which is designed for sleeping or living quarters for one or more persons, with or without utilities, flush toilets, or bath facilities, is used for recreational purposes, is not a residence and including among other items, a travel trailer, a pick-up camper; a tent trailer, beach buggy, and a motor home. *ATM 3/6/71, STM 5/1/89*

**Setback, Front:** A front setback shall be measured from the front lot line to the closest point of the structure. Excluding: Decorative trim, gutters, fascia, soffit, bulkheads, and unenclosed stairways. *STM 5/1/89, STM 3/24/97, ATM 5/3/04*

**Setback, Rear:** A rear setback shall be measured from the rear lot line to the closest point of the structure. Excluding: Decorative trim, gutters, fascia, soffit, bulkheads, and unenclosed stairways.

**Setback, Side:** A side setback shall be measured from the nearest side lot line to the closest point of the structure. Excluding: Decorative trim, gutters, fascia, soffit, bulkheads, and unenclosed stairways. *STM 5/1/89, STM 3/24/97, ATM 5/3/04*

**Special Permit:** A written authority granted after a duly advertised public hearing to locate, build, or use structures or land in accordance with the provisions of this By-Law, for certain uses, including the expansion or alteration of existing non-conforming uses and buildings.

### **Street:**

- (a) A public way or a way which the Town Clerk certifies is maintained and used as a public way, or
- (b) A way shown on a plan theretofore approved and endorsed in accordance with the subdivision control law, or
- (c) A way in existence when the subdivision control law became effective in Freetown, having, in the opinion of the Planning Board, sufficient width, suitable grades, and adequate construction to provide for the needs of vehicular traffic in relation to the proposed use of the land abutting thereon or served thereby, and for the installation of municipal services to serve such land and the buildings erected or to be erected thereon. *STM 5/1/89*

**Structure:** Any combination of materials attached to or requiring a fixed location on or in the ground. Includes, but not limited to, a principal building or a shed, garage, stable, greenhouse, bridge, trestle, tower, framework, stadium, reviewing stand, platform, in-ground swimming pool, or other accessory building. *STM 5/1/89, STM 3/24/97*

**Trailer:** A vehicle without motive power, designed to be towed by a passenger automobile or other powered vehicle of similar size but not designed and intended for human occupancy, such as utility trailers, boat trailers, and horse trailers. *ATM 3/6/71, STM 5/1/89*

**Use:** The purpose for which a structure or lot is arranged, designed, or intended to be used, occupied or maintained.

**Use, Accessory:** A use incidental and subordinate to the principal use of a structure or lot, or a use, not the principal use, which is located on the same lot as the principal structure. *STM 3/27/97*

**Use, Principal:** The main or primary purpose for which a structure or lot is designed, arranged, or intended, or for which it may be used, occupied, or maintained under this by-law. Any other use within the main structure or the use of any other structure or land on the same lot and incidental or supplementary to the principal use and permitted under this by-law shall be considered an accessory use.

## ARTICLE 11 (11.2 cont.)

**Use, Substantially Different:** A use by reason of its normal operation would cause readily observable differences in patronage, service, sight, noise, employment or similar characteristics from the use to which it is being compared.

### 11.3. Lot Sizes & Setback Requirements

**A. Lot Size –Area:** Land laid out into lots for any purpose after the adoption of this By-law shall have a minimum frontage on a street or way of 175 feet and a minimum area of 70,000 square feet, a minimum of 52,000 square feet of which must be of non- resource area (as defined by M.G.L. Chapter 131, §40); 30,000 square feet of this non- resource area must be contiguous. Newly created lots shall accommodate a one hundred foot diameter circle that touches the required frontage and is entirely within the lot being created.  
*ATM 3/7/59, ATM 3/6/71, ATM 3/10/73, STM 9/22/86, ATM 5/3/04, STM 11/8/04*

\*For purposes of this by-law, a street or way shall mean:

- a) A public way, or a way which the Clerk of the Town certifies is maintained and used as a public way, or
- b) A way shown on a plan heretofore approved and endorsed in accordance with the protective By-Laws; or
- c) A way in existence when subdivision control law became effective in the Town having, in the opinion of the Planning Board, sufficient width, suitable grades and adequate construction to provide for the needs of vehicular traffic in relation to the proposed use of the land abutting thereon or served thereby, and for the installation of municipal services to serve such land and the buildings erected or to be erected thereon.

**B. Frontage:** Frontage on a street or way shall be measured from its intersection with one side lot line to its closest intersection with another side lot line of the same lot, with the following exceptions and limitations:

- (a) Lots that have frontage on two or more streets shall utilize any one frontage length but not include more than one in computation of total frontage.
- (b) Lots that have more than one length of frontage on the same street shall utilize any one frontage length but not include more than one in computation of total frontage.
- (c) Where a curve defines the intersection of two street layouts, the measurement of frontage on any one street shall extend along the curve to the mid-point.
- (d) **Lot Orientation and Access from Frontage:**  
The selected frontage shall serve as the basis for determining applicable building setbacks. The selected frontage shall be suitable for the development of an access route or driveway to the building site. *ATM 3/7/59, ATM 5/5/80, ATM 5/26/81, STM 9/22/83, STM 10/27/08*

**C. Lot Sizes Minimum Requirements:** No existing lot shall be reduced in frontage or area below the aforesaid minimum requirements. *ATM 3/10/73, ATM 5/5/80*

**D Lot Sizes –Existing Lots:** Nothing in these By-Laws shall prohibit the construction of a single-family dwelling on existing lots smaller than 70,000 square feet and 175 feet of frontage or on existing lots containing wetland areas providing: *ATM 3/10/73, ATM 5/5/80, ATM 5/26/81, ATM 5/5/86, STM 9/22/86*

- (a) The lot was a legally created lot shown on a plan of land approved by the Planning Board and duly recorded with the Register of Deeds prior to any increases in minimum area and frontage approved by town vote.
- (b) The lot was not held in common ownership with any adjoining land of the same owner.
- (c) Construction of dwellings on such undersized lots must conform to current State and Local Health Regulations applicable to the type of structure proposed.
- (d) Existing lots containing wetlands shall be subject to review of the Freetown Conservation Commission and its rulings and conditions, if any.

**E. Lot Coverage:** Maximum percentage of land covered by structures. Residential District: 30%, Village Residential District: 65%, Village Business District: 70%, General Use District: 50%, Business Use District 80%, Industrial and Industrial/2 Districts: 80%. *ATM 5/3/04, STM 10/27/08*

**F. Additional Dwelling Units-Minimum Requirements:** No single family dwelling shall hereafter be constructed or placed upon a lot having less than 175 feet frontage and 70,000 square feet, a minimum of 52,000 square feet of which must be of non-resource area as defined by M.G.L. Chapter 131, §40. An additional attached dwelling unit is allowed to create a duplex unit providing there is a minimum of an additional 50 feet of frontage and 40,000 square feet of non-resource area. *ATM 3/10/73, ATM 5/5/80, ATM 5/26/81, STM 9/22/86, STM 10/27/08*

## ARTICLE 11.3 (cont.)

**G. Setback Requirements:** *STM 5/26/81, STM 9/22/86, STM 5/1/89, STM 11/1/94, STM 3/24/97*

1) **Single family and Duplex Structures on pre-existing lots:** Single family and duplex structures on pre-existing non-conforming lots with less than 175 feet of frontage and less than 70,000 square feet of area legally created and recorded prior to 09/22/86, in non-industrial zones and not held in common ownership:

Principal Building:	30 feet from the street line 20 feet from rear and side property lines
Accessory Buildings	30 feet from street line 6 feet from rear and side property lines

2) **Setbacks for all other circumstances:** *STM 05/01/1989, STM 10/27/2008, ATM 06/07/2010, STM 11/8/2010*

**INDUSTRIAL/ INDUSTRIAL 2 DISTRICT** *ATM 06/07/2010, STM 11/08/2010*

Height and Setback Requirements for Industrial and Industrial/2 districts for structures over forty (40) feet in height: The maximum height of any principal or accessory building within **the** Industrial or Industrial/2 district shall be determined according to its distance from the nearest street or from any General or Residential Districts. The maximum height shall be seven (7) floors or eighty (80) feet at two hundred (200) feet of setback.

<b><u>USE</u></b>	<b><u>SETBACKS FROM PROPERTY LINES</u></b>		
	<b><u>SIDE</u></b>	<b><u>REAR</u></b>	<b><u>FRONT</u></b>
<b><u>GENERAL USE DISTRICT</u></b>			
Single family or duplex, Principal building	20'	20'	50'
Multi-family Principal building	100'	100'	100'
Residential accessory building greater than 300 square feet in area	10'	10'	50'
Residential accessory building less than or equal to 300 square feet in area	6'	6'	50'
Business principal building	40'	40'	50'
Business, accessory building	40'	40'	50'
Retail fuel station canopy	20'	20'	20'
<b><u>RESIDENTIAL DISTRICT</u></b>			
Single family or duplex, Principal building	20'	20'	50'
Multi-family Principal building	100'	100'	100'
Residential accessory building greater than 300 square feet in area	10'	10'	50'

**ARTICLE 11 (11.3G cont.)**

<b><u>USE</u></b>	<b><u>SETBACKS FROM PROPERTY LINES</u></b>		
	<b><u>SIDE</u></b>	<b><u>REAR</u></b>	<b><u>FRONT</u></b>
Residential accessory building less than or equal to 300 square feet in area	6'	6'	50'
Public Utility Structure Including water/sewer infrastructure	10'	10'	10'
<b><u>VILLAGE RESIDENTIAL DISTRICT</u></b>			
All principal uses	10'	10'	10'
Accessory uses	6'	6'	10'
<b><u>VILLAGE BUSINESS DISTRICT</u></b>			
All Principal Uses	10'	10'	10'
Accessory uses	6'	6'	10'
<b><u>BUSINESS DISTRICT</u></b>			
Business principal building	50'	40'	50'
Business, accessory building	50'	40'	50'
Retail fuel station canopy	50'	20'	20'
Public Utility Structure Including water/sewer infrastructure	6'	6'	10'
<b><u>INDUSTRIAL/ INDUSTRIAL 2 DISTRICT</u></b> <i>ATM 06/07/2010, STM 11/8/10</i>			
Industrial structure: Less than or equal to three (3) floors or forty (40) feet in height	50'	40'	50'
Greater than three (3) floors or forty (40) feet in height	50'	40'	200'
Accessory structure	50'	20'	50'
Research laboratory	50'	40'	50'
Dry cleaning plant	50'	40'	50'
Uses accessory to permitted scientific research and development, whether or not located on the same lot as the principal permitted use	50'	40'	50'
Commercial tower And/or antenna. See also Article 11, Section 11.17	1.5x tower height	1.5x tower height	1.5x tower height
Wind Turbine See also Article 11 Section 11.24	3x blades highest point	3x blades highest point	3x blades highest point
Adult Entertainment Establishments	150'	150'	150'
Public Utility Structure Including Water/sewer infrastructure	6'	6'	10'
Large-scale ground-mounted Solar photovoltaic installations	20'	25'	50'

## ARTICLE 11 (11.3G cont.)

- 3) No building, structure, including accessory buildings or structures erected or placed upon a lot for a specific use shall be changed to or used for a different use, unless the building or structure complies with the setback and district use requirements for the new use.
- 4) Construction of new structures, additions, or expansions of existing structures within these setbacks will require a variance or special permit from the Board of Appeals.

**H. Residential Parking Requirements:** All single family and duplex dwellings shall be provided with a minimum of two off-street parking spaces per dwelling unit that shall conform to the same setbacks as are applicable to single family and duplex structures. *STM 9/22/86*

**I. Lots created prior to May 5, 1980:** The frontage and area requirements of Section 11.3D and 11.3F shall not apply to a lot for single family residential use which on May 5, 1980 was not held in common ownership with any adjoining land and contained at least 30,000 square feet of area and 150 feet of frontage. *ATM 5/26/80*

**11. 4 Permits:** No building or structure shall be erected or enlarged in the Town without a permit from the Board of Selectmen or their appointed agent upon application therefore accompanied by a plan or sketch, substantially to scale, showing the lot lines and dimensions and the location of the proposed building or structure.

### **11. 5 Administration:**

**A. Special Permit Granting Authority:** *STM 10/27/08, ATM 6/7/10*

1. The special permit granting authority will issue permits in accord with the procedure and provisions of § 9 of chapter 40A.
2. Each application for a special permit shall be filed by the petitioner with the town clerk and a copy of said application, including the date and time of filing certified by the town clerk, shall be filed forthwith by the petitioner with the special permit granting authority.
3. Zoning by-laws shall provide that a special permit granted under this section shall lapse within a specified period of time, not more than two years, which shall not include such time required to pursue or await the determination of an appeal referred to in section seventeen, from the grant thereof, if a substantial use thereof has not sooner commenced except for good cause, or in the case of permit for construction, if construction has not begun by such date except for good cause.
4. Unless otherwise specified in this By-Law, the Special Permit Granting Authority is the Planning Board.

**B. Board of Appeals:** There is hereby established a Board of Appeals of three (3) members and two (2) associate members to be appointed by the Selectmen, as provided in Chapter 40A of the General Laws, which shall act on all matters within its jurisdiction under this By-Law in the manner prescribed in Chapter 40A of the General Laws.

*ATM 5/3/76*

The Board of Appeals shall have the following powers: *ATM 5/1/78*

1. To hear and decide appeals in accordance with §8 of Chapter 40A.
2. To hear and decide petitions for variances in accordance with §10 of Chapter 40A.
3. To hear and decide applications for those uses for which approval of the Board of Appeals is required in accordance with the provisions of this By-Law and for special permits when not otherwise specified, including the power to grant variances for use, Chapter 40A § 10, Chapter 808 of the Acts of 1975. *STM 10/28/02*
4. To hear and decide applications for expansion of non-conforming uses. *STM 10/27/08*

The Board of Appeals shall not grant approval for enlargement or extension unless it shall find that such extension shall not be substantially more detrimental to the neighborhood than the existing non-conforming use. *STM 10/27/08*

In exercising the powers granted by this section, the Board of Appeals shall act in accordance with the provisions of § 11, 14, 15 and 16 of Chapter 40A of the General Laws. *ATM 5/3/76*

## ARTICLE 11 (11.6 cont.)

### 11.6 Special Permit Use – Multi-unit Dwellings of Three Units or More Including Apartments, Townhouses, Condominiums, etc. *STM 9/22/86*

- A. **Purpose:** To protect the public interest in preservation of groundwater resources, wetlands, to assure traffic safety, protect and promote land values and to generally provide guidelines that will allow development of multi-family structures without detrimental effect upon the neighborhood in which they are located.
- B. **Special Permit:** Except as provided otherwise in this By-Law no multi-family structure shall be USED, CONVERTED, CONSTRUCTED OR RECONSTRUCTED without the issuance of a Special Permit from the Planning Board. *STM 10/27/08*
- C. **Special Permit Requirements:** Application for special permits for multi-family structures shall be on such forms or in such manner as the special permit granting authority may specify and in accordance with its rules and regulations and shall be submitted together with all required exhibits and site plans.

The plans shall include, but not be limited to pertinent information in regard to the following: lot boundaries, names of abutting owners, streets contiguous to the site, vegetation, existing and proposed roadways, existing and proposed buildings, location of sources of water, sewage disposal, parking, ponds, wetlands, known permanent monuments and other cross-sections, profiles and contour maps required to describe the proposal. These plans shall be prepared by a registered engineer. The site plan shall show existing, intermediate and final ground levels with those of adjacent properties and shall indicate natural surface water flows and drainage ditches, if any.

The special permit granting authority shall determine that the proposal generally conforms to the principles of good engineering, sound planning and correct land use and that the applicant has the means to implement the proposal if a special permit is granted. Applicants may be required, as a condition to special permit, to guarantee that all conditions and features of the plan are completed by posting a suitable bond or deed covenant.

No special permit for the construction of multi-family structures shall be granted unless the special permit granting authority finds the proposal is not contrary to the best public interest of the inhabitants of the Town of Freetown and conforms to the specific requirements as outlined in the following regulations.

Once the plans are formally accepted for consideration by the special permit granting authority they will be accepted or rejected within 120 days. Copies of the plan will be referred to the following Boards or individuals within fourteen days for their review and input:

Conservation Commission	Board of Health
Building Inspector/Zoning Enforcement Officer	Chief of Police
Fire Chief	Water Commission
Board of Selectmen/ Town Administrator	Sewer Commission
Highway Department/Public Works Department/Highway Surveyor	

Comments from these officials must be received by the special permit granting authority within thirty (30) days of the plans' distribution or else the special permit granting authority will assume their acceptance of the plan. Failure of any of these town officials to report on the proposal does not in any way exempt the applicant from compliance with the rules and regulations administered by those boards or individual officials.

A public hearing will be held after the time allowed for review by town officials and before a vote relative to approval of the plan. Publication and notices to abutters of the public hearing and costs of conducting the hearing will be borne by the applicant. *STM 10/27/08*

- D. **Density:**
- The minimum lot area requirement for each apartment building shall be 70,000 square feet for the first unit and 40,000 square feet for each additional unit.
  - The minimum lot area shall be exclusive of all streets and ways, wetland and swamp area as defined by M.G.L.W. Ch. 131, § 40.
  - Buildings designed for this use shall have a maximum of two stories for living space and a maximum height of 30 feet.
- E. **Frontage:**  
175 feet for the first unit and an additional 50 feet for each additional unit.

## ARTICLE 11 (11.6 cont.)

### F. **Minimum Setbacks:**

- a. From street frontage: 100 feet.
- b. Side yard: 100 feet minimum.
- c. Rear Yard: 100 feet minimum.
- d. Distance between proposed buildings: 100 feet.

### G. **Access and Parking:**

- a. Driveways shall not be less than 20 feet wide and more than 200 feet in length unless approved by the Planning Board.
- b. Parking areas, adequately lighted, shall be provided at the minimum rate of two autos per dwelling unit and located a minimum of 100 feet from any existing street line and at least 50 feet from any lot line and shall be at least 30 feet from first floor windows unless screened from headlight glare. Parking areas shall be screened from view from town roads.
- c. Driveways, parking areas and storm drainage shall be constructed and paved according to the rules and regulations of the Planning Board governing the subdivision of land as adopted under the subdivision control law. No such driveway or parking area will be allowed to shed water upon town ways.
- d. Additional guest parking areas may be required at the discretion of the Planning Board.
- e. All street level apartments shall be provided with wheelchair access for the handicapped.

### H. **Outside Use and Recreational Space Requirements:**

- a. There shall be a minimum of 15 times the residential floor space area developed as graded, open-lawn area for the purpose of general space.
- b. Natural features of the remaining landscape shall be maintained where possible.
- c. An indoor recreational area shall be provided, adequate for the purpose of group or guest entertainment by the residents of the building.

### I. **Private Water Supply and Sewerage Disposal System:**

A private water supply and sewage disposal system shall follow the regulations and recommendations of the Freetown Board of Health. (Bonds or other financial guarantees may be required to assure maintenance)

- 1) **Waste Disposal:** There shall be satisfactory design and location of collection points for the disposal of solid wastes/rubbish.

J. **Fifty-foot Buffer Zone:** Fifty-foot buffer zones are required adjacent to side and rear lot lines. These areas shall be densely planted with evergreen screen plants and such additional requirements, as the permit granting authority deems necessary to protect the privacy of the abutting properties.

K. **Traffic Study:** A traffic study shall be required when more than fifty units are proposed for the purpose of assessing the impact on traffic safety on town ways.

L. **Certification by a Registered Professional Engineer:** Certification by a Registered Professional Engineer that construction has been completed in accordance with applicable regulations will be required prior to release of bond or deed covenant, if any, and final inspection by the Building Inspector for the issuance of occupancy permits. The costs of inspection and certification are to be borne by the applicant.

M. **Utility Provisions:** All existing and proposed utilities shall be installed underground at the time of initial construction of apartment development.

1. **Accessory Use Buildings:** Accessory use buildings, garages, storage sheds, maintenance buildings, additional recreational facilities shall conform to the same setback and height restrictions as the apartment dwelling units.

N. **Ability of Special Permit Authority:** Nothing in these by-laws shall limit the ability of the special permit granting authority to impose additional reasonable requirements in order to protect the health and welfare of the future tenants of the structure, the abutters and other inhabitants of the Town.

O. **Invalidity:** The invalidity of any section or provision of this By-Law shall not affect the validity of any other section or provision thereof.

## ARTICLE 11

### 11.7 Trailer Parks *STM 10/17/77, ATM 3/6/71, STM 10/27/08*

Trailer parks shall not be allowed in any part of the town except that the Board of Selectmen may in specific cases, after public notice and hearing and subject to appropriate conditions and safeguards, and only after approval by 2/3 vote at a special or annual town meeting, permit the establishment of a trailer park upon determining that the establishment of such a park will substantially serve the public conveniences and welfare, will not be obnoxious or detrimental to the neighborhood and will be in harmony with the general purpose and intent of the protective By-Law. Once the plans are formally accepted for consideration by the Board of Selectmen they will be accepted or rejected within 120 days. Copies of the plan will be referred to the following Boards or individuals within fourteen days for their review and input:

Conservation Commission	Board of Health
Building Inspector/Zoning Enforcement Officer	Chief of Police
Fire Chief	Water Commission
Sewer Commission	Planning Board
Highway Department/Public Works Department/Highway Surveyor	

Comments from these officials must be received by the Board of Selectmen within thirty (30) days of the plans' distribution or else the special permit granting authority will assume their acceptance of the plan. Failure of any of these town officials to report on the proposal does not in any way exempt the applicant from compliance with the rules and regulations administered by those boards or individual officials.

A public hearing will be held after the time allowed for review by town officials and before a vote relative to approval of the plan. Publication and notices to abutters of the public hearing and costs of conducting the hearing will be borne by the applicant.

- A. No person shall park, store or occupy a mobile home except:
  - (1) By non-paying guests of the owner or occupant of a lot subject to the issuance of a permit by the Board of Selectmen or its agent prior to the occupancy of the lot by the mobile home and only for a period not to exceed three weeks in any calendar year. A permit may be granted by the Board of Selectmen or its agent for only one additional three week period for the same mobile home in any calendar year. In such granting, such permits the Board of Selectmen shall determine whether or not there shall be any detriment to the neighboring areas.
  - (2) As a temporary office or dwelling incidental to construction on the lot which the mobile home is located provided that a building permit for said construction has been issued by the Town; that occupancy of the mobile home does not exceed a period of twelve months; that the mobile home shall be equipped with running water and connections to a septic tank or sanitary sewer in a manner approved by the Board of Health and in accordance with all laws and regulations with respect to health and sanitation as applied to said mobile home; and that a permit shall have been issued to the owner of the lot by the Board of Selectmen or its agent.
- B. Overnight occupancy of mobile homes or recreational vehicles, on public roads, ways or beaches shall be prohibited except in areas designated for that purpose by the Board of Selectmen.
  - 1. Overnight occupancy of a recreational vehicle by non-paying guests of the owner or occupant of a lot shall be permitted for a period not to exceed 72 hours without a permit or for a period not to exceed three weeks with a permit from the Board of Selectmen, or its agent.
- C. Trailers and unoccupied recreational vehicles defined herein shall be permitted to be parked or stored on any lot.
- D. Mobile homes placed or located on any premises at the time of passage of this by-law in conformance with a valid permit issued by the Board of Selectmen shall thereafter be governed as a prior non-conforming use.

## ARTICLE 11

**11.8 Construction For Which a Building Permit was Legally Issued:** Any construction or use for which a building permit was legally issued prior to the first publication of notice of the Planning Board hearing respecting this By-Law or any amendment thereto shall be permitted, notwithstanding non-compliance with the requirements of this By-Law or amendments thereto, provided such construction was commenced within six (6) months after the issuance of the permit and, in cases involving construction, such construction was continued through to completion as continuously and expeditiously as is reasonable.

- A. **Exempted Uses:** Nothing in this By-Law shall prohibit, regulate or restrict the use of land or structures in any district for religious purposes or for educational purposes on land owned or leased by the Commonwealth or any of its agencies, subdivisions or bodies politic or by a religious sect or denomination, or by a nonprofit educational corporation.
- B. **Accessory Use:** In all districts activities accessory to activities otherwise permitted within the district as a matter of right, which activities are necessary in connection with scientific research or scientific development or related production, whether or not on the same parcel as activities permitted as a matter of right, may be permitted upon approval of the Board of Appeals as provided in Section 11.5.
- C. **Non-conforming Use:** When a non-conforming use is discontinued or is abandoned for a period of more than two (2) years, it shall not be re-established, unless a permit for a longer period of time has been granted by the Board of Appeals in conformance with § 14 and 15 of Chapter 40A, and any future use shall be in conformance with this By-Law, provided that this section shall apply to use for agriculture, horticulture or floriculture only as provided in §3 of Chapter 40A of the General Laws.
- D. **Enforcement:** If the Inspector of Buildings is requested in writing to enforce the provisions of this By-Law and the Inspector of Buildings declines to act, he shall notify in writing, the party requesting such enforcement of any action or refusal to act and the reasons therefore, within fourteen (14) days of receipt of such request.
- E. **Violation of the provisions of the bylaws:** Any person who shall violate any of the provisions of these By-Laws, shall be subject to a penalty of not more than \$100.00 dollars for each offense, except as otherwise provided by law, and all such money so collected shall be paid into the treasury of the town. Each day that such violation continues shall be a separate offense.
- F. **Invalidity:** The invalidity of any section or provision of this By-Law shall not affect the validity of any other provision thereof.

**11.9 An Appeal to the Board of Appeals:** An appeal to the Board of Appeals as established under Article 11, Section 11.5 of the By-Laws of the Town of Freetown above may be taken by any person aggrieved by reason of his inability to obtain a permit from the Board of Selectmen or its agent under the provisions of the above Sections 11.7 and 11.8.A, B, C, D inclusive. *ATM 3/7/59*

**11.10 Swimming Pools: Permitted accessory use:** Swimming Pools are a permitted accessory use. If having a depth of four feet or more and a capacity of four hundred cubic feet or more, they are considered structures, and must comply with regulations of the Board of Health regarding minimum standards for residential swimming pools. *STM 9/2/75, ATM 5/1/89, STM 10/27/08*

**11.11 Floodplain Overlay District:** *ATM 5/5/80, STM 10/27/2008, ATM 6/1/2009*

### A. **Statement of Purpose**

The purposes of the Floodplain District are to:

1. Ensure public safety through reducing the threats to life and personal injury;
2. Eliminate new hazards to emergency response officials;
3. Prevent the occurrence of public emergencies resulting from water quality, contamination, and pollution due to flooding;
4. Avoid the loss of utility services which if damaged by flooding would disrupt or shut down the utility networks and impact regions of the community beyond the site of flooding;
5. Eliminate the costs associated with the response and cleanup of flooding conditions;
6. Reduce damage to public and private property resulting from flooding waters.

## ARTICLE 11 (11.11 cont.)

### B. Floodplain District Boundaries and Base Flood Elevation and Floodway Data

#### 1. Floodplain District Boundaries and Base Flood Elevation Data

The Floodplain District is herein established as an overlay district. The District includes all special flood hazard areas within the Town of Freetown designated as Zone A and AE on the Bristol County Flood Insurance Rate Map (FIRM) issued by the Federal Emergency Management Agency (FEMA) for the administration of the National Flood Insurance Program. The map panels of the Bristol County FIRM that are wholly or partially within the Town of Freetown are panel numbers 25005C0254F, 25005C0258F, 25005C0261F, 25005C0262F, 25005C0263F, 25005C0264F, 25005C0266F, 25005C0267F, 25005C0268F, 25005C0269F, 25005C0286F, 25005C0287F, 25005C0288F, 25005C0289F, 25005C0291F, 25005C0293F, 25005C0357F, 25005C0359F, 25005C0376F, 25005C0377F, 25005C0378F, and 25005C0381F dated July 7, 2009. The exact boundaries of the District may be defined by the 100-year base flood elevations shown on the FIRM and further defined by the Bristol County Flood Insurance Study (FIS) report dated July 7, 2009. The FIRM and FIS report are incorporated herein by reference and are on file with the Town Building Commissioner and Conservation Commission.

### C. Base Flood Elevation and Floodway Data

1. Floodway Data. In zones A, A1-30, and AE, along watercourses that have not had a regulatory floodway designated, the best available Federal, State, local, or other floodway data shall be used to prohibit encroachments in floodways which would result in any increase in flood levels within the community during the occurrence of the base flood discharge.
2. Base Flood Elevation Data. Base flood elevation data is required for subdivision proposals or other developments greater than 50 lots or 5 acres, whichever is the lesser, within unnumbered A zones.

### D. Notification of Watercourse Alteration

In a riverine situation, the Town of Freetown Board of Selectmen shall notify the following of any alteration or relocation of a watercourse:

Adjacent Communities

NFIP State Coordinator  
 Massachusetts Department of Conservation and Recreation  
 251 Causeway Street, Suite 800  
 Boston, MA 02114-2104

NFIP Program Specialist  
 Federal Emergency Management Agency, Region I  
 99 High Street, 6<sup>th</sup> Floor  
 Boston, MA 02110

### E. Use Regulation

#### 1. Reference to existing regulations

The Floodplain District is established as an overlay district to all other districts. All development in the district, including structural and non-structural activities, whether permitted by right or by special permit must be in compliance with Chapter 131, Section 40 of the Massachusetts General Laws and with the following:

- a. Section of the Massachusetts State Building Code which addresses floodplain and coastal high hazard areas (currently 780 CMR 3107, "Flood Resistant Construction");
- b. Wetlands Protection Regulations, Department of Environmental Protection (DEP) (currently 310 CMR 10.00);
- c. Inland Wetlands Restriction, DEP (currently 310 CMR 13.00);

## ARTICLE 11 (11.11E cont.)

- d. Minimum Requirements for the Subsurface Disposal of Sanitary Sewage, DEP (currently 310 CMR 15, Title 5);

Any variances from the provisions and requirements of the above referenced state regulations may only be granted in accordance with the required variance procedures of these state regulations.

### 2. Other Use Regulations

- a. In Zone AE, along watercourses that have a regulatory floodway within the Town of Freetown as designated on the Bristol County FIRMs, encroachments are prohibited in the regulatory floodway which would result in any increase in flood levels within the community during the occurrence of the base flood discharge.
- b. All subdivision proposals must be designated to insure that:
- i. Such proposals minimize flood damage;
  - ii. All public utilities and facilities are located and constructed to minimize or eliminate flood damage; and
  - iii. Adequate drainage is provided to reduce exposure to flood hazards, (Existing contour intervals of site and elevations of existing structures must be included on plan proposal).

### F. Permitted Uses

The following uses, which are of low flood damage potential and cause no obstructions to flood flows, are permitted provided they are allowed in the underlying district and they do not require structures, fill or storage of materials and/or equipment:

1. Agricultural use such as farming, grazing, truck farming, horticulture, etc.
2. Forestry and nursery uses.
3. Outdoor recreational uses, including fishing, boating, play areas, etc.
4. Conservation of water, plants, wildlife.
5. Wildlife management areas, foot, bicycle, and/or horse paths.
6. Temporary non-residential structures used in connection with fishing, growing, harvesting, storage, or sale of crops raised on the premises.

### G. Definitions

**AREA OF SPECIAL FLOOD HAZARD** is the land in the floodplain within a community subject to a one-percent or greater chance of flooding in any given year. The Zone may be designated as Zone A or AE.

**BASE FLOOD** means the flood having a one-percent chance of being equaled or exceeded in any given year.

**DEVELOPMENT** means any manmade change to improved or unimproved real estate, including but not limited to building or other structures, mining, dredging, filling, grading, paving, excavation, or drilling operations.

**DISTRICT** means floodplain district.

**FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA)** administers the National Flood Insurance Program (NFIP).

**FLOOD HAZARD BOUNDARY MAP (FHBM)** means an official map of a community issued by FEMA where the boundaries of the flood and related erosion areas having special hazards have been designated as Zone A or E.

**FLOOD INSURANCE STUDY** means an examination, evaluation, and determination of flood hazards, and, if appropriate, corresponding water surface elevations, or an examination, evaluation and determination of flood related erosion hazards.

**FLOODWAY** means the Channel of a river or other watercourse and the adjacent land areas that must be reserved in order to discharge the base flood without cumulatively increasing the water surface elevation.

## ARTICLE 11 (11.11G cont.)

**LOWEST FLOOR** means the lowest floor of the lowest enclosed area (including basement or cellar). An unfinished or flood resistant enclosure, usable solely for parking of vehicles, building access or storage in an area other than a basement area is not considered a building's lowest floor, PROVIDED that such enclosure is not built so as to render the structure in violation of the applicable non-elevation design requirements of NFIP Regulations 60.3.

**MANUFACTURED HOME** means a structure, transportable in one or more sections, which is built on a permanent chassis and is designed for use with or without a permanent foundation when connected to the required utilities. For floodplain management purposes the term "manufactured home" also includes park trailers, and other similar vehicles placed on site for greater than 180 consecutive days. For insurance purposes, the term "manufactured home" does not include park trailers, travel trailers, and other similar vehicles.

**MANUFACTURED HOME PARK OR SUBDIVISION** means a parcel (or contiguous parcels) of land divided into two or more manufactured home lots for rent or sale.

**NEW CONSTRUCTION** means, for floodplain management purposes, structures for which the "start of construction" commenced on or after the effective date of a floodplain management regulation adopted by a community. For the purpose of determining insurance rates, NEW CONSTRUCTION means structures for which the "start of construction" commenced on or after the effective date of an initial FIRM or after December 31, 1974, whichever is later.

**ONE-HUNDRED YEAR FLOOD** – see BASE FLOOD

**REGULATORY FLOODWAY** – see FLOODWAY

**SPECIAL FLOOD HAZARD AREA** means an area having special flood and/or flood-related erosion hazards, shown on a FHBM or FIRM as Zone A, or AE.

**STRUCTURE** means, for floodplain management purpose, a walled and roofed building, including a gas or liquid storage tank, that is principally above ground, as well as a manufactured home. STRUCTURE, for insurance purposes, means a walled and roofed building, other than a gas or liquid storage tank, that is principally above ground and affixed to a permanent site, as well as a manufactured home on foundation. For the latter purpose, the term includes a building while in the course of construction, alteration, or repair, but does not include building materials or supplies intended for use in such construction, alteration, or repair, unless such materials or supplies are within an enclosed building on the premises.

**SUBSTANTIAL DAMAGE** means damage of any origin sustained by a structure whereby the cost of restoring the structure to its before-damaged condition would equal or exceed 50 percent of the market value of the structure before the damage occurred.

**SUBSTANTIAL IMPROVEMENT** means any repair, reconstruction, or improvement of a structure, the cost of which equals or exceeds 50 percent of the market value of the structure either (a) before the improvement or repair is started, or (b) if the structure has been damaged and is being restored, before the damage occurred. For the purposes of this definition, "substantial improvement" is considered to occur when the first alteration of any wall, ceiling, floor, or other structural part of the building commences, whether or not that alteration affects the external dimensions of the structure.

**ZONE A** means the 100-year floodplain area where the base flood elevation (BFE) has not been determined. To determine the BFE, use the best available federal, state, local, or other data.

**ZONE AE** (for new and revised maps) means the 100-year floodplain where the base flood elevation has been determined.

**ZONE X** is an area identified in the community Flood Insurance Study as an area of moderate or minimal flood hazard. Zone X replaces Zones B and C on new and revised maps.

## ARTICLE 11

### **11.12 Planning Board:**

A. **Associate Member:** The Freetown Planning Board, when acting as the SPGA is authorized in M.G.L. Chapter 40A, §9, to create an Associate Planning Board Member. This Associate Member will be chosen by majority vote of the Board of Selectmen and the Planning Board, each person having one vote, and will have a 3-year term. This Associate Member may sit on the Planning Board for the purpose of acting on a special permit application in the case of absence, inability to act, or conflict of interest, on the part of any member of the Planning Board or in the event of a vacancy on the Board. *STM 3/24/97, STM 10/27/03, STM 10/27/08*

### **11.13 Hazardous Waste Facilities:**

The operation of hazardous waste facilities, including the operation of such facilities at commercial dump sites or sanitary landfills is prohibited within the Town of Freetown. *STM 1/24/03*

### **11.14 Private or Commercial Dump:**

That the operation of a private or commercial dump or sanitary landfill, refuse transfer station, refuse incinerator or compacting or treatment station is prohibited in the Town of Freetown.

### **11.15 Home Occupations:**

Voted to approve a By-Law permitting home occupations not currently permitted under Chapter 40A within residential structures on legally created pre-existing, non-conforming lots. Home occupations shall be defined as: A home occupation is a use conducted entirely within an enclosed dwelling, employing only the inhabitants thereof, and is clearly incidental and secondary to residential occupancy and does not change the character thereof and constitutes no more than twenty-five (25%) percent of ground floor area. Specifically excluded is the storage and display of merchandise not produced by such home occupation, any activity involving any building alterations, window display, construction features, equipment, machinery, or outdoor storage, any of which is visible from off the lot on which such use is located. Any proposed business or occupation, which in the opinion of the Building Inspector exceeds the limitations defined herein, shall be subject to the review, approval, and conditions of a special permit issued by the special permit granting authority.

### **11.16 Special Permits- Home Occupations:**

Voted to allow the Zoning Board of Appeals to issue special permits for home occupations which do not comply with Article 11 (Section 11.15). Such permits may be granted after the filing of an application for special permit and a public hearing held in accordance with Chapter 40A of Massachusetts General Law. Any permits issued may also impose conditions, safeguards, and limitations on time, use, or ownership. Other conditions that may apply include but are not limited to the following:

The proposed use is appropriate to the specific site in question. Adequate and appropriate facilities will be provided for the proper operation of said use.

There will be no hazard to pedestrians or vehicles.

There will be no nuisance or adverse effect upon the neighborhood. Setback requirements of front, side, or rear yards may be greater than the minimum otherwise prescribed by existing By-Law.

Requirements of screening of service or parking areas of the site by walls, fence, planting, or other approved means.

### **11.17 Height Limitations:** *STM 11/01/1994, STM 10/27/2008, ATM 06/07/2010, STM 11/08/2010*

Building heights in the General Use, Residential Use, Village Residential Use, Village Business, and Business Use districts shall not exceed three (3) floors or forty (40) feet in height. For structures located in Industrial and Industrial/2 Districts over three (3) floors or forty (40) feet in height: the maximum height for any non-accessory building within the Industrial (I) and Industrial/2 (I/2) district shall be determined according to its distance from the nearest street or from any General or Residential districts. Height requirements for antennas, water tanks, chimneys, towers, spires, and the like as well as other structural features not used for human occupancy that are in excess of one hundred feet shall require the granting of a special permit by the Planning Board. A projection erected that shall exceed the height shown above may be authorized by special permit providing the special permit granting authority finds the proposal is not contrary to the best interest of the inhabitants of the Town of Freetown and is in accordance with Article 11, Section 11.5A.

## ARTICLE 11

### **11.18 Zoning Districts:** *ATM 5/7/01, ATM 06/07/2010, STM 11/08/2010*

**A: Purpose:** The purpose of this By-Law shall be to promote the welfare of the inhabitants of the Town of Freetown; to conserve the value of land and buildings; to encourage the appropriate use of land throughout the town; to preserve and increase its amenities; and to provide for the Town the protection authorized by the General Laws, Chapter 40A, as amended.

**B. Scope:** This By-Law will not apply to buildings, structures and uses of land lawfully begun or in existence at the time this By-Law is adopted; but all new construction, relocation, expansion, alteration, or change of use shall conform to the provisions of this By-Law.

**C. Minimum Provisions:** The provisions of this By-Law shall be deemed to be minimum requirements adopted for the purposes stated in Section 11.18A. Whenever any other By-Law of the Town of Freetown or any law or regulation of the Commonwealth of Massachusetts imposes greater restrictions than this By-Law, such other By-Law, law or regulation shall prevail to the extent of such greater restrictions. *STM 10/28/02*

### **D. Establishment of Districts:**

- 1) **Types of Districts:** For the purpose of this By-Law, the Town of Freetown is hereby divided into the following types of use districts: *STM 03/24/1997, ATM 05/07/2001, STM 10/27/2008, ATM 06/07/2010*
  - a) R – Residential
  - b) I – Industrial
  - c) I/2 - Industrial/2
  - d) B - Business
  - e) G - General Use
  - f) Open Space & Recreation
  - g) VR – Village Residential
  - h) VB – Village Business
- 2) **Location of Districts:** The sections of the Town to which these By-Laws are applicable and the boundaries of the districts above referred to are hereby established as shown on the map entitled "Zoning Map Town of Freetown," dated September 17, 2008 and on file with the Town Clerk, which accompanies and is hereby declared to be a part of these By-Laws

### **E. Industrial Districts (I), (I/2)**

In an industrial district buildings and structures may be constructed, altered, enlarged, reconstructed and used and land may be used for manufacturing, processing, fabrication, assembling, research and development and bio-technology activities, information and information processing, data collection and data storage, records keeping, instructional and training facilities, telecommunications, public distribution and maintenance facilities not otherwise prohibited by law or ordinance and uses ancillary thereto excluding research or use of radioactive, biohazardous or explosive materials. Retail sale shall not be permitted, except that retail sales of products manufactured on the premises are permitted but shall be limited to an area which is 5 percent of the gross floor space, or 1,000 square feet, whichever is less. The uses permitted under this section are subject to the following provisions:

- (1) All operations are conducted and all materials used in such operations or held in storage are contained within enclosed buildings or enclosed by a solid wall, fence or planting of such nature and height as to conceal such operation or materials from view from any public way or area or neighboring premises.
- (2) Waste materials produced by such operations are either disposed of, stored in buildings or enclosed as specified in (1) above.
- (3) Dust, smoke, fumes, gas, glare, noxious odors, noise and vibrations are limited so as not to be injurious to the public health or to the use of neighboring property as provided by the laws of the Commonwealth.
- (4) No more than eighty (80) percent of the lot is covered by improvements, meaning buildings, parking areas, driveways and access road, and outside storage and assembly areas.

## ARTICLE 11 (11.18E cont.)

- (5) Buildings housing manufacturing operations shall be set back at least fifty feet (50') from any street and side lot line and at least forty feet (40') from any rear lot line. The setback areas shall be left in a natural unimpaired state or landscaped.
- (6) Structures greater than three (3) floors or forty (40) feet in height shall maintain a setback of at least two hundred feet from the nearest street or from any General or Residential districts.
- (7) Adequate provision is made for the off street accommodation of all vehicles including those of employers, employees, customers and visitors.
- (8) Illumination of buildings, yards and signs shall not constitute a hazard to auto drivers and the light sources of such illumination shall be shielded from adjacent residential districts and streets. Flashing, moving or intermittent illumination shall not be permitted.

### F. VR - Village Residential and VB - Village Business

1. **Purpose:** It is the intent of the Village Residential District and the Village Business District to preserve the architectural and historic character of Assonet Village and East Freetown Village. A mix of limited commercial and residential uses is permitted to allow development keeping with the look and feel of Freetown's historic villages. Additionally, the Town of Freetown's intent for the Village Residential District and Village Business District is:

- a. To encourage rehabilitation of existing structures and development of new buildings with high architectural standards that is compatible with the historic development pattern that gives Assonet Village and East Freetown Village their special character. New development/redevelopment in Assonet Village and East Freetown Village should meet the following design guidelines: Any extension, alteration or reconstruction of existing buildings should reflect the original design insofar as practical. New construction should reinforce the architectural style of existing buildings in terms of building design, siding, material and texture, color and bulk, and should result in a harmonious blend of the new and old. Use of brick, clapboard, shingle, masonry or non-reflective materials is encouraged. Sheet metal, reflective materials or similar siding lacking texture is strongly discouraged.
- b. Uses allowed by-right and by special-permit are encouraged, but not required, to meet these policy goals.
  1. To maintain the historic village scale and mix of residential, commercial, and community land uses in Assonet Village and East Freetown Village.
  2. To attract new investment and help create new jobs in Assonet Village and East Freetown Village.
  3. To improve the safety and comfort for pedestrians in Assonet Village and East Freetown Village.
  4. To encourage village commercial uses that will primarily serve the needs of the people of Freetown and the surrounding communities and, secondarily attract visitors to utilize these villages.

2. **Density Regulations**

- a. The lot requirements for the Village Residential District shall be the same as the Residential District; the lot requirements for newly created lots in the Village Business District shall be the same as the Business District. No lot shall be developed or redeveloped under this bylaw unless it meets the State's Title V septic requirements or connects to a public sewer system.
- b. No more than one (1) principal building shall be located on a lot.

3. **Uses permitted by right, by special permit and prohibited** are delineated in Section G.1 the Table of Use. Development that does not require a Special permit within a Village should meet the following performance standards:

- a. **Design guidelines:** The design guidelines listed in Section 11.18.E.1.a, paragraph 2 have been met to the greatest extent feasible.
- b. **Nuisance:** The proposed use(s) will not create a noise, dust, odor or vibration nuisance to abutting properties.
- c. **Parking:** The number of parking spaces to be provided shall be as noted in Section 4, Off Street Parking and Loading requirements of the Rules and Regulations of the Planning Board as Special Permit Granting Authority.

## ARTICLE 11 (11.18F cont.)

- d. **Pedestrian access:** Provision for safe and convenient pedestrian access shall be incorporated into plans for new construction and redevelopment of buildings and parking areas. New construction should improve pedestrian access to building, sidewalks and parking areas and should be completed with considerations of pedestrian safety, handicapped access and visual quality.
- e. **Landscaping:**
  1. A landscaped buffer strip may be required adjacent to adjoining residential uses. This buffer strip shall be planted with a combination of grass, appropriate shrubs and shade trees.
  2. Exposed storage areas, machinery, garbage "dumpsters," service areas, truck loading areas, utility buildings and structures shall be screened from the view of abutting properties and streets using plantings, fences and other methods compatible with the goals of this regulation.

General performance standards for special permits are found in the Rules and Regulations of the Planning Board as Special Permit Granting Authority. Approval criteria for issuing special permits are found in sub-section H of this zoning bylaw.

### G. **District Regulation:** *STM 10/27/08*

1) **Existing Uses and Non-Conforming Uses:** The lawful use of any structure or land existing at the enactment or subsequent amendment of this By-Law may be continued although such structure or use does not conform to the provisions of this By-Law, subject, however, to the following exceptions:

- a.) **Reconstruction of Non-Conforming Structure:** In event that a non-conforming structure is destroyed by fire or other natural cause, the same may be reconstructed or repaired at the same location for the same non-conforming use, provided the new structure would not exceed in size and square footage the original structure and that such construction is commenced not later than 24 months from the occurrence of such natural cause.
- b.) **Abandonment:** A non-conforming use which has been abandoned for a period of 24 months shall not be re-established. Any further use shall conform to the current district standards.
- c.) **Expansion, Alteration or Change of Use of One or Two Family Residential Non-Conforming Uses:** Existing one or two family residential structures which are non-conforming uses, may expand or be altered without a Special Permit from the Planning Board if the expansion or alteration meets the setback, height, and lot coverage standards of the zoning district in which the residential use is located.
- d.) **Expansion, Alteration or Change of Use of Non-Conforming Uses Other Than One or Two Family Residential Uses:** Non-Conforming uses other than a one or two family residential use may be expanded, altered or changed to another non-conforming use only by Special Permit granted by the Planning Board. The Planning Board shall not issue a Special Permit unless the Board finds that the expansion, alteration or change shall not be substantially more detrimental to the neighborhood than the existing non-conforming use.

**H. Uses:** A use listed in the table in Section 11.18, G-1 is permitted in any district under which it is denoted by the letter "Y" subject to such requirements as may be specified elsewhere in this, or other, By-Law. If designated in the Table by the letters "SP" the use may be permitted as an exception only if the Special Permit Granting Authority so determines and grants a Special Permit, subject to such restrictions as set forth elsewhere in this By-Law and such further restrictions as said Special Permit Granting Authority may establish. The letter "N" shall designate that the use is not permitted.

## ARTICLE 11 (11.18 cont.)

### 1. Table of Use Regulations:

R - Residential, B - Business, I - Industrial, I/2 - Industrial 2, G – General, OSR – Open Space & Recreation, VB - Village Business and VR - Village Residential *STM 3/24/97, ATM 5/7/07, STM 10/27/08, ATM 6/1/09, ATM 06/07/2010*

<u>USE</u>	<u>DISTRICT</u>							
	<u>R</u>	<u>B</u>	<u>I</u>	<u>I/2</u>	<u>G</u>	<u>OSR</u>	<u>VR</u>	<u>VB</u>
Single-family detached dwellings	Y	SP	N	N	Y	N	Y	Y
A duplex house	Y	SP	N	N	Y	N	Y	Y
Multi-Family	SP	SP	N	N	SP	N	SP	SP
Accessory Apartments	SP	N	N	N	SP	N	SP	SP
Dwelling units located above a first-floor non-residential use	N	SP	SP	N	SP	N	SP	SP
Home Occupations that comply with Section 11.15	Y	Y	N	N	Y	N	Y	Y
Home Occupations that do not comply with Section 11.15 to subject to Section 11.16	SP	SP	N	N	SP	N	SP	SP
Hotel or Motel	N	Y	Y	Y	N	N	N	N
Bed and Breakfast, up to 6 guest rooms	SP	Y	Y	Y	Y	N	SP	SP
Rooming house	N	N	N	N	N	N	N	N
Agriculture including the care, feeding or sheltering of farm animals, including the raising of crops- indoors or outdoors on parcels 5 acres or greater	Y	Y	Y	Y	Y	Y	Y	Y
Religious, educational, or municipal use by the Town of Freetown	Y	Y	Y	Y	Y	Y	Y	Y
For Profit Education	N	SP	SP	N	SP	N	N	SP
Museum or Art Gallery less than 2,500 sf	SP	Y	SP	SP	Y	N	SP	SP
Museum or Art Gallery of 2,500 sf or greater	N	Y	SP	SP	SP	N	N	SP
Retail or wholesale business or service less than 10,000 sf. not involving manufacture on the premises	N	Y	SP	SP	Y	N	N	Y

**ARTICLE 11 (11.18 cont)**

<u>USE</u>	<u>DISTRICT</u>							
	<u>R</u>	<u>B</u>	<u>I</u>	<u>I/2</u>	<u>G</u>	<u>OSR</u>	<u>VR</u>	<u>VB</u>
Retail or wholesale business or service of 10,000 sf. or greater not involving manufacture on the premises	N	SP	SP	SP	SP	N	N	SP
Business or professional office less than or equal to 10,000 sf.	N	Y	Y	Y	SP	N	N	SP
Business or professional office 10,000 sf. or greater	N	Y	Y	Y	SP	N	N	SP
Restaurant less than or equal to 2,500 sf	N	Y	Y	Y	Y	N	N	Y
Restaurant of 2,500 sf or greater	N	Y	Y	N	Y	N	N	SP
Restaurant with drive-through	N	SP	SP	SP	N	N	N	N
Banquet Facilities less than or equal to 15,000 sf	N	Y	Y	N	Y	N	N	N
Banquet Facilities 15,000 sf or greater	N	SP	Y	N	SP	N	N	N
Theater, bowling alley or other commercial amusement provided all business is conducted within the structure	N	Y	SP	SP	N	N	N	N
Motor vehicle sales, rental, or repair shop	N	Y	Y	Y	SP	N	N	N
Veterinary office, animal hospital, kennel, or animals sales	N	SP	Y	Y	SP	N	N	N
Drive-through facilities associated with any commercial use (bank, drug store, etc.)	N	SP	SP	SP	N	N	N	N
Scrap or junk yards	N	N	Y	Y	SP	N	N	N
Earth removal for commercial purposes	<b>See: Protective By-laws, Article 6 Soil Removal</b>							
Bus or railroad terminal or passenger station	N	SP	SP	SP	SP	N	N	N
Hospital, convalescent or nursing home	N	SP	SP	N	SP	N	N	N

**ARTICLE 11 (11.18 cont.)**

<u>USE</u>	<u>DISTRICT</u>							
	<u>R</u>	<u>B</u>	<u>I</u>	<u>I/2</u>	<u>G</u>	<u>OSR</u>	<u>VR</u>	<u>VB</u>
Funeral parlor	N	Y	Y	Y	Y	N	N	N
Crematory	N	N	SP	SP	N	N	N	N
Cemetery	SP	N	N	N	Y	Y	SP	N
Golf Course	SP	SP	SP	SP	SP	N	N	N
Recreational or sports facilities including day or seasonal camp for children	SP	SP	SP	SP	SP	Y	N	N
Race track (outdoor)	N	N	N	N	N	N	N	N
Race track (indoor)	N	N	SP	N	N	N	N	N
Warehouse or facilities for distributing merchandise	N	Y	Y	Y	SP	N	N	N
Plant for manufacturing, processing, fabricating or assembly	N	SP	Y	Y	SP	N	N	N
Research Laboratory	N	SP	Y	Y	SP	N	N	N
Dry Cleaning plant	N	N	SP	SP	N	N	N	N
Retail or wholesale Fuel establishment involving storage and distribution	N	SP	SP	SP	SP	N	N	N
Hazardous waste facilities for the storage, treatment, dewatering, refining, incinerating, reclamation, stabilization, solidification, or disposal of hazardous wastes	N	N	N	N	N	N	N	N
Commercial tower and/or antenna *See also Article 11, Section 11.17 of the Freetown Protective By-Laws	N	Y	Y	Y	Y	N	N	N
Adult Entertainment Establishments	N	N	N	SP	N	N	N	N
Any proposed shopping centers, retail establishments, and/or wholesale establishments that exceed 25,000 square feet of floor area as described in Article 11.22	N	N	SP	SP	N	N	N	N

## ARTICLE 11 (11.18 cont.)

<u>USE</u>	<u>DISTRICT</u>							
	<u>R</u>	<u>B</u>	<u>I</u>	<u>I/2</u>	<u>G</u>	<u>OSR</u>	<u>VR</u>	<u>VB</u>
Adult Retirement Community Use	SP	N	N	N	SP	N	N	N
Continuing Care Retirement Community Use	SP	N	N	N	SP	N	N	N

### **I. Special Permits:** *STM 3/24/97, STM 10/27/08*

The Planning Board is designated as the Special Permit Granting Authority for the purpose of granting special permits as cited in the Table of Use Regulations. The SPGA shall follow the procedural requirements for special permits as set forth in Section 9 of M.G.L. Chapter 40A. After notice and public hearing and after due consideration of the reports and recommendations of other town boards, commissions and or departments, the SPGA may grant such a permit. The Special Permit Granting Authority shall have the power to impose reasonable conditions and modifications, including limitations of time and use, as a condition of a Special Permit, and may secure compliance of performance by requiring the posting of a bond or other safeguards. Such conditions shall be imposed in writing and the applicant may be required to post a bond or other surety for compliance with said conditions in an amount satisfactory to the SPGA.

- 1) **Application:** Application for Special Permits shall be on such forms or in such manner as the Special Permit Granting Authority may specify and in accordance with its Rules and Regulations, and shall be submitted together with all required exhibits and site plans.
- 2) **Special Permits -Table of Use Regulations:** All applications for Special Permits from the Planning Board shall be subject to the procedural requirements established by that Board. Special Permits shall only be issued for uses which are in harmony with the general purpose and intent of this By-Law and subject to its general or specific provisions and only if the Special Permit Granting Authority finds that the following conditions are met:
  - a.) **The use is not noxious,** harmful or hazardous, is socially and economically desirable and will meet an existing or potential need.
  - b.) The advantages of the proposed use outweigh any detrimental effects, and such detrimental effects on the neighborhood and the environment will not be greater than could be expected from development which could occur if the Special Permit were denied.
  - c.) The applicant has no reasonable alternative available to accomplish this purpose in a manner more compatible with the character of the immediate neighborhood.
  - d.) The design and layout of the proposal assures the protection of adjoining premises against detrimental or offensive uses on the site, including compliance with all dimensional requirements set forth in this bylaw and provisions of adequate landscaping, including the screening of adjacent residential uses, this includes provision of street trees, landscape islands in the parking lots and a landscaped buffer along the property lines.
  - e.) The requested use will not create un-mitigated traffic congestion or safety issues and provides enhanced pedestrian mobility.
  - f.) The design of the proposal provides an adequate amount of spaces and for the proper layout of parking and loading areas.
  - g.) The proposal provides suitable methods of disposal for sewage, refuse and other wastes.
  - h.) The proposal provides an onsite drainage system that protects adjoining properties, wetlands, water courses and water bodies.
  - i.) The proposal provides and follows a soil erosion plan that addresses the re-grading of the site, stabilization of slopes during and after construction and the protection of adjoining properties, wetlands, water courses and water bodies.
  - j.) The proposal provides adequate lighting within the site while protecting adjoining properties from glare and light pollution.
  - k.) The requested use will not impair the integrity or character of the district or adjoining properties, nor be detrimental to the health, morals, or welfare of the town's residents.

## ARTICLE 11 (11.18I cont.)

All special permit applications shall be reviewed by the Special Permit Granting Authority for conformance with the Special Permit Rules and Regulations. The Special Permit Granting Authority shall determine that the proposal generally conforms to the principals of good engineering, sound planning, and correct land use, and that the applicant has the means to implement the proposal if a Special Permit is granted.

### **J. Special Permits for Adult Entertainment Establishments:** *STM 3/24/97, STM 10/27/08*

1. **Authority:** This by-law is enacted pursuant to M.G.L. Chapter 40A and pursuant to the Town's authority under the Home Rule Amendment to the Massachusetts Constitution to serve the compelling Town interests of limiting the location of and preventing the clustering and concentration of certain adult entertainment enterprises, as defined and designated herein, because of their deleterious effect in generating crime and blight. The Board of Selectmen is the Special Permit Granting Authority for adult entertainment establishment special permits.

2. **Purpose:** It is the purpose of the Industrial/2 District to address and mitigate the secondary effects of the adult entertainment establishments and sexually oriented businesses that are referenced and defined herein. Secondary effects have been shown in numerous studies to include increased crime, adverse impacts on the property values of residential and commercial properties, and adverse impacts on the quality of life in the Town. All of said secondary impacts are adverse to the health, safety and general welfare of the Town of Freetown and its inhabitants.

3. **Minimum Provisions:** The provisions of this by-law have neither the purpose nor intent of imposing a limitation on the content of any communicative matter or materials, including sexually oriented matter or materials. Similarly, it is not the purpose or intent of this by-law to restrict or deny access by adults to adult entertainment establishments or to sexually oriented matter or materials that are protected by the Constitutions of the United States of America or of the Commonwealth of Massachusetts, nor to restrict or deny rights that distributors or exhibitors of such matter or materials may have to sell, rent, distribute or exhibit such matter or materials. Neither is it the purpose or intent of this by-law to legalize the sale, rental, distribution or exhibition of obscene or other illegal matter or materials. In addition an application for a special permit for Adult Entertainment shall conform to the following conditions:

- a.) **May not locate within five hundred feet of each other:** Special permits for Adult Entertainment Establishments may not be located within Five Hundred (500) feet of each other and of any residential zone, single or multiple dwelling, church, park, school, day care facility, or any establishment licensed under the provisions of M.G.L. Chapter 138, §12.
- b.) **Shall not be granted to persons convicted of violating provisions:** Special permits for Adult Entertainment Establishments shall not be granted to any person convicted of violating the provisions of M.G.L. Chapter 119, § 63 or Chapter 272, § 28.
- c.) **Issued after a public hearing:** Special permits for Adult Entertainment Establishments shall only be issued following public hearings held within 65 days after filing an applications with the Special Permit Granting Authority, a copy of which the applicant shall give to the Town Clerk simultaneously.
- d.) **Shall lapse within one year:** A Special permit for Adult Entertainment Establishments shall lapse within one year, including the time required to pursue or await the determination of an appeal filed pursuant to M.G.L. Chapter 40A§17, from the grant thereof, if a substantial use thereof has not sooner commenced except for good cause or, in the case of permit for construction, if construction has not begun by such date except for good cause.
- e.) **Existing Adult Entertainment Establishments:** Any existing Adult Entertainment Establishments shall apply for such permit within ninety days following the adoption of said zoning by-law or by-law by a municipality.

## ARTICLE 11 (11.18J cont.)

### 4. **COMPLIANCE:**

- a) No building permit shall be issued by the Building Department for any development subject to this section and no construction or installation of utilities or infrastructure shall be started, until a decision of the SPGA approving the plan has been filed with the Town Clerk.
- b) An as-built plan, as specified under the Rules and Regulations of the Planning Board Governing the Subdivision of Land, certified by a registered professional land surveyor and/or engineer shall be submitted to the SPGA and Building Inspector before the issuance of an occupancy permit. The as-built plan shall attest to a development's conformity to its approved plans and conditions.
- c) No occupancy permit shall be issued for any building subject to this section unless such building and all its related facilities have been completed according to the special permit decision.
- d) Any changes in the approved plan or in the activity to be conducted on the site shall be submitted to the SPGA for review and approval.

5. **APPEALS:** Any person aggrieved by a decision of the SPGA under Section 15 may appeal to the Superior Court, the Land Court or the District Court pursuant to Chapter 40A of the Massachusetts General Laws.

6. **INVALIDITY:** The invalidity of any section, sentence or provision of this By-Law shall not affect the validity of any other section, sentence, or provision thereof.

### **11.19 Accessory Apartment By-Law:** *ATM 5/1/99, STM 10/27/2008*

**A. Purpose:** It is the intent of this by-law to create additional living space to a single-family dwelling. Proposed expansion must maintain the appearance of the structure as a single-family home. It must not be detrimental to the surrounding neighborhood. The additional living space shall not be used as an apartment for rental, but only as a convenience for members of the owner's family.

**B. Residential District/ Village Residential:** The Zoning Board of Appeals, as a Special Permit Granting Authority, may issue a Special Permit authorizing the conversion and use of a portion of a single-family dwelling into a separate living area with cooking facilities for a family member of the owner or owners. Said permit shall be valid only for the occupancy of said premises of the person for whom it is issued. For a Residential Zone, not more than 1,000 square feet of additional living space may be added to the existing single-family dwelling, must be subordinate in size to the principal dwelling unit in a manner that maintains the appearance of the structure as a detached single-family home, must provide two off-street parking spaces per unit, only one accessory apartment shall be allowed per single-family dwelling unit, and one of the two living units shall be owner occupied. Permit, if granted, is valid for five (5) years. Five years from date of issue a public hearing will be held to ensure use is the same. *STM 10/27/08*

**C. General District:** The Zoning Board of Appeals, as a Special Permit Granting Authority, may issue a Special Permit authorizing the conversion and use of a portion of a single-family dwelling into a separate living area with cooking facilities for a family member of the owner or owners. Said Permit shall be valid only for the occupancy of said premises by the person for whom it is issued. For a General Use Zone, not more than 1000 square feet of additional living space may be added to the existing single-family dwelling, must be subordinate in size to the principal dwelling unit in a manner that maintains the appearance of the structure as a detached single-family home, must provide two off-street parking spaces per unit, only one accessory apartment shall be allowed per single-family dwelling unit, and one of the two living units shall be owner occupied. Permit, if granted, is good for five (5) years. Five years from date of issue a public hearing will be held to ensure use is the same.

## ARTICLE 11

### 11.20 **Signs:** *ATM 5/7/01, STM 10/22/01, ATM 5/6/02, STM 10/27/08*

**A. Authority:** This by-law is adopted pursuant to the authority conferred upon the town by MGL C. 40A, MGL C. 93, § 29, and MGL C 143, § 3. Nothing in this chapter shall be construed to abrogate the town's control under MGL C. 87 § 9, governing signs placed on shade trees enforceable by the Tree Warden or the town's control under MGL C. 85, § 8, governing signs placed within a public way enforceable by the Selectmen or under the Building Code.

**B. Purpose And Scope:** The sign by-law is designed to provide standards for the installation of signs so as to reduce traffic safety hazards, protect property values, promote economic development, and encourage the creation of an aesthetic appearance along the street frontages in the Town of Freetown. The sign bylaw, as set forth in this section, is designed to be both logical and equitable for the various uses and identification needs. These sign standards help to effectuate an aesthetic and safe street environment. Restrictions on type, location, and size of signs protect the public from hazardous and distracting devices.

### **C. Administration & Enforcement:**

1. **Applicability:** All outdoor signs, banners, posters and window signs are subject to the regulations of this By-Law unless specifically excluded in Section 11.20D (13).
2. **Building Inspector:** The Building Inspector shall administer and enforce all regulations contained in this By-Law. The Building Inspector shall give a written notice to any person or persons erecting new signs in violation of these regulations, to render compliance therewith within ten days or remove the sign by reason of failure to do so.
3. **Special Permit Granting Authority:** The Special Permit Granting Authority (SPGA) shall be the Planning Board for the purposes of this by-law.
4. **Application:** All persons desiring to erect a sign shall apply to the Building Inspector for a building permit, except that persons desiring to erect a sign in accordance with Sections 11.20D(2), 11.20D (4), 11.20D (5) with the exception of real estate signs, or 11.20D (2) need not apply for a permit. All applications for permits shall include, at least, a drawing showing the following:
  - a.) The proposed sign with dimensions.
  - b.) Sign specifications. The application shall also contain the following specific information on each proposed sign:
    - 1.) Construction of the proposed sign and supporting structure, indication dimensions and materials.
    - 2.) Color scheme.
    - 3.) Lettering or graphic style.
    - 4.) Illumination specifications.
    - 5.) Sign proportions.
    - 6.) Location of any proposed signs on a building.
    - 7.) The areas of any windows to be covered by window signs but need not specify the exact dimension or nature of every window sign.
    - 8.) Detail of all lighting and wiring.
    - 9.) All existing signs maintained on the premises.
    - 10.) Plot Plan. An accurate plot plan of the zoning lot, at such scale as the Building Inspector may reasonably require, illustrating the location of the proposed and any existing signs, buildings, parking lots, driveways, and landscaped areas on such zoning lot.
    - 11.) A sketch of the building façade indicating the location of each sign.
5. **Building Inspector Action:** The Building Inspector shall issue a building permit provided the proposed sign complies with this By-Law, the State Building Code, requirements of the Historic Commission (where applicable) and any applicable laws, by-laws, or regulations.

## ARTICLE 11 (11.20C cont.)

6. **Special Permits:** In particular instances the SPGA may issue Special Permits for more or larger signs than are provided herein or for signs of types or for purposes not provided herein and not specifically prohibited herein, including temporary signs, if it is determined that the architecture of the building, the location of the building with reference to the street or the nature of the establishment is such that the sign should be permitted in the public interest. In granting such permission, the SPGA shall specify the size and location of the sign or signs and impose such other terms and restrictions as it may be deemed to be in the public interest. Any applicant under this provision shall provide the information required in Section 11.20C (6) above and specific information in the form of perspectives, renderings, photographs or other representations sufficient to show the nature of the proposed sign, its effect on the immediate surroundings and the reasons for allowing it.
7. **Fees:** Each application for an individual sign permit or for approval of a common signage plan shall be accompanied by the applicable fees, which shall be established by the Board of Selectmen.

**D. General Regulations:** The provisions of Section 11.20D shall apply to signs in all zoning districts. Additional specific regulations for Residential, General Use, Business & Industrial districts are set forth in Sections 11.20C and 11.20D respectively.

1. **General Guidelines:** No sign shall be erected or maintained unless its subject matter relates exclusively to the premises on which it is located, or to products, accommodations, services, or activities on those premises.
2. **Permitted Government or Special Signs:** Any sign owned and installed by a governmental agency, or required by any law, governmental order or regulation is not subject to this By-Law. Signs mounted on registered motor vehicles or carried by hand and not subject to this By-Law.
3. **Residences:** Two signs, up to four (4) square feet in area each, are permitted per residential building indicating the name and address of the occupants therein.
4. **Religious Institutions:** Two signs identifying churches, synagogues, and other similar religious uses are permitted on each street frontage, one of which may not exceed 20 square feet in area and the other of which may not exceed 10 square feet in area. One sign may be a standing sign used for notices and announcements of events at the religious institution.
5. **Temporary Signs:**
  - a.) **Permitted Temporary Signs:** The following types of temporary signs are permitted: Signs banners, and posters covering social and holiday events as well as signs pertaining to a candidate for an elected local, county, state or national government office or a ballot question that will appear on the ballot at any local, county, state or national election. Signs pertaining to yard sales and fundraising events are permitted. A Real Estate sign advertising the sale or rental of the premises on which it is located is permitted. Real estate development signs may be erected on subdivisions of land solely to advertise the selling of land or buildings in said subdivision, but not more than one sign shall face the same street.
  - b.) **Temporary Sign Limitations:** Signs shall not be erected sooner than Thirty (30) days before the event to which they pertain (i.e., the offering for sale or lease of the premises, the commencement of construction or the election) and shall be removed within seven (7) days after the conclusion of the event to which they pertain.
    - (A.) No signs shall be lighted.
    - (B.) All signs shall meet the standards as set forth in 11.20D.
    - (C.) With the exception of Real Estate Development Signs, no sign shall exceed six (6) square feet in area, and shall not exceed forty (40) inches in length or thirty-six (36) inches in width, excluding supporting materials. Real Estate Development signs shall not exceed twenty (20) square feet in area and not more than 10 feet in any dimension.
    - (D.) No mechanical or electrically powered signs or signs with moving parts shall be permitted.

## ARTICLE 11 (11.20D cont.)

- (E.) No more than Three (3) temporary signs per dwelling unit or per lot, whichever is greater, shall be erected at the same time.
- (F.) Signs must be firmly attached to a supporting device and present no undue hazard to the public.
6. **Directional Signs:** Directional signs not exceeding three square feet in area may be used without limitation where needed on private property.
7. **Illumination:**
- a.) No sign shall be illuminated between the hours of 11:00 p.m. and 6:00 a.m., except signs on premises open for business and then only upon issuance of a special permit by the SPGA.
  - b.) Exterior illumination of signs shall be shielded, directed solely at the sign, and be steady and stationary.
  - c.) No internal illumination of a sign is permitted except upon issuance of a special permit by the SPGA.
  - d.) The illumination of any sign shall not exceed 150-foot lamberts.
  - e.) Any sign which is externally illuminated shall be a minimum distance of 100 feet between the leading edge of the illuminated sign and the adjoining residential property line.
8. **Height:** No ground sign shall exceed 20 feet in height as measured from the ground level to the top of the sign.
9. **Signs Cannot Interfere with Traffic:** No sign, including window displays, or their illuminators shall by reason of its location, shape, size or color interfere with traffic or be confused with or obstruct the view or the effectiveness of any official traffic sign, traffic signal or traffic marking. No red or green lights shall be used on any sign if, in the opinion of the Building Inspector with the advice of the Chief of Police, such lights would create a driving hazard.
8. **Construction:** No sign shall be painted or posed directly on the exterior surface of any wall. All exterior, attached signs, except awning signs, shall be painted, posted or otherwise securely affixed to the wall of the building. The foregoing, however, shall not prevent installation of a sign by individual letters or devices cut into or securely affixed to the exterior wall of a building, provided that such letters or devices have a minimum depth of projection of one fourth (1/4) of an inch. The construction of the sign shall comply with the State Building Code.
9. **Maintenance:** Every sign shall be maintained in good condition. If a sign shows corrosion or deteriorated paint over 25% of the area of one side or if damage to the sign causes the loss of 10% of its substance or if the sign suffers damage or deterioration which creates a risk of harm to the person or property of another, it shall be repaired or removed.
10. **Prohibited Signs:** The following types of signs are prohibited.
- A.) Neon, gas-filled tube type illuminated signs are not permitted. No sign shall produce glare or incorporate in any manner flashing, moving or intermittent lighting, excluding public service signs showing time and temperature.
  - B.) Wind signs, including banners, pennants, spinners, streamers, and other wind activated components. However a single flag or banner, such as one containing advertising matter, for each establishment or business on the lot, may be allowed in a commercial zoning district provided that the flag or banner not exceed 3 x 5 feet. As provided in subparagraph 11.20D (1), a government flag is not subject to this provision.
  - C.) String lights used in connection with commercial premises with the exception of temporary lighting for holiday decoration.
  - D.) Signs erected so as to obstruct any door, open-able window or fire escape on a building.
  - E.) Billboards or non-accessory signs.
  - F.) Portable, platform-mounted, frame mounted or trailer-mounted signs.
  - G.) Any sign emitting sound shall be prohibited. (Exception: Menu boards in conjunction with restaurant drive-through pick up are allowed a speaker through which orders may be placed and confirmed subject to the restrictions noted in this by-law.

## ARTICLE 11 (11.20D cont.)

- H.) Signs on Natural Features and Utility Poles are prohibited. No sign shall be permitted to be painted on, attached to, or maintained upon utility poles, trees, shrubs, rocks or other natural features, except that historical or commemorative plaques may be mounted in rocks and that “No Trespassing”, “No Hunting”, “Property Boundary”, or “Ownership” signs may be mounted on trees, rocks, shrubs or other natural features.
- I.) Obscene Signs Prohibited. No sign shall contain words, statements, or graphic descriptions of an obscene or indecent nature.
- J.) Signs which interfere with official signs and traffic control devices.
- K.) Signs which prevent the driver of a vehicle from having a clear and unobstructed view, from an adequate safe distance, of any official sign or approaching or merging traffic.
- L.) Signs which when located in such a manner as to materially impede the view of any street or intersection.

### 13. Signs Exempt from Permit and License Requirements:

- a. Bulletin Board. A freestanding bulletin board or similar sign used for occasional commercial purposes, not exceeding 32 square feet in display area in connection with any church, museum, library, school or similar public structure is allowed without a permit.
- b. Balloon less than twenty-four (24) inches in diameter.
- c. Holiday decorations, including lighting, are exempt from the provisions of this by-law and may be displayed without a permit.
- d. Decals used to reference authorized services (e.g. credit or bank cards) when not exceeding 144 square inches in total display area per business.
- e. Incidental sign – a sign that has a purpose secondary to the use of the lot on which it is located, such as “telephone”, “drive-up window”, “cash machine” and other similar directives.
- f. Open Flags. One non-illuminated “OPEN” flag may be displayed for each separate business unit in connection with commercial promotion. No name, logo or lettering other than the word “OPEN” may be displayed on such signs. OPEN flags may be displayed at the building during business hours and must be displayed at the building entrance.
- g. Building markers and historic or commemorative plaques are exempt from a permit and a license.
- h. Construction Signs – One (1) temporary freestanding construction sign or wall sign per project construction site is exempt from obtaining a permit and a license on each street frontage of the project, subject to the following conditions:
  - (1) The construction sign shall not exceed thirty-two (32) square feet.
  - (2) The construction sign shall be a maximum of six (6) feet in height for residential districts or 15 feet in height for other districts.
- i. Flags, noncommercial.
- j. Garage sale signs.
- k. Home improvement/home construction/home remodeling signs are exempt from obtaining a permit and license provided:
  - i. There shall be only one such sign not exceeding thirty-two (32) square feet in total surface area and four (4) feet in height for each lot.
- l. Interior signs.
- m. Murals.
- n. Official signs and notices
- o. Political Signs.
- p. Public Utility Signs.
- q. Real Estate signs are exempt from obtaining a permit and license, provided:
  - ii. Real Estate Signs for Single or two-family Residential Dwellings or lots.
  - iii. There shall be one (1) sign per street frontage up to a maximum of two (2) signs per lot.
  - iv. Such sign shall be located on the lot for sale or lease.
  - v. Such sign shall not exceed six (6) square feet.

## ARTICLE 11 (11.20D cont.)

### **Real Estate Signs for other uses:**

**General Provisions:** The real estate sign shall be located on the site for sale or lease. The site may elect one (1) of the following options, subject to other provisions within this bylaw:

- (i) Incorporate the real estate sign into the permanent identification sign; or
  - (ii) One real estate sign, not exceeding six (6) square feet, shall be permitted per street frontage up to a maximum of two (2) signs per site. The maximum height shall be six (6) feet.
  - (iii) Real Estate signs shall be included as part of the square footage calculations for permanent signs.
- r. Residential nameplates are exempt from obtaining a permit.
  - s. Warning signs. Signs warning of construction, excavation, underground utility pipes, or similar hazards, so long as the hazard exists, including any public notice or warning required by a valid and applicable federal, state, or local law, regulation, or ordinance.
  - t. "No Trespassing", "No Parking", and other similar signs are also exempt.

### **E. Residential Districts:** *STM 10/27/08*

1. **Multi-Family Dwelling Developments:** A sign not exceeding 12 square feet in area is permitted identifying developments in an R, VR or G district.

**F. Village Business, General, Business & Industrial Districts:** Accessory signs on business establishments in Village Business, General, Business & Industrial districts that comply with the following provisions are permitted.

- 1) **Wall Signs:**
  - a. One principal wall sign is permitted on the front of the establishment to which it relates. The width of such a sign above the first floor of a building shall not exceed fifteen (15) feet.
  - b. A secondary wall sign may be installed marking a direct entrance on a parking lot or another street in addition to the front wall sign. There shall be not more than two such secondary wall signs. Said sign shall have a width no greater than 50% of the maximum permissible width for the principal wall sign.
  - c. No wall sign shall be more than three feet in overall height.
  - d. In buildings where the first story is substantially above grade and the basement is only partially below street grade, one sign for each level is allowed if each sign has only one half of the area that would be permitted for a single sign.
  - e. In addition to the above signs each building may have one directory sign affixed to the exterior wall, window, or door of the building. Such directory sign shall provide not more than one square foot for each occupant of the building.
  - f. Wall signs shall either be affixed to a wall and parallel to it or affixed to the roof above a wall and be parallel to the wall. They shall not project more than twelve (12) inches from the face of such wall.
  - g. No wall sign shall project above the highest line of the main roof or parapet on the wall to which it is attached whichever is higher.
- 2) **Window Signs:** Removable signs on the inside of windows or transparent doors are permitted.
- 3) **Projecting Signs or Hanging Signs:** In particular instances the SPGA may issue Special Permits for projecting signs in accordance with Section 11.20C (8), if it is determined that the architecture of the building, the location of the building with reference to the street or the nature of the establishment is such that the sign should be permitted in the public interest. No establishment shall be permitted more than one projecting sign.
- 4) **Standing Signs:** The following standing signs are permitted:
  - a. Standing signs permitted under Sections 11.20D (2), 11.20D (3), and 11.20D (4).
  - b. During the construction of a building a standing sign may be erected on the premises identifying the building, the owner, the contractors, the architects and the engineers. Such a sign shall not exceed twenty (20) square feet in area or 10 feet in any direction. Such sign shall be removed promptly after the completion of the building.
  - c. In particular instances the SPGA may issue Special Permits for standing signs in accordance with Section 11.20C (8), if it is determined that the architecture of the building, the location of the building with reference to the street or the nature of the establishment is such that the sign should be permitted in the public interest. No establishment shall be permitted more than one standing sign other than signs directing traffic flow.

## ARTICLE 11 (11.20F cont.)

5) **Signs at Gasoline Filling Stations and Garages:** Gasoline filling stations and garages may divide the one wall sign affixed to the front wall of the building to which they are entitled as hereinabove provided, into separate wall signs indicating the separate operations or departments of the business, provided however, that the total of the widths of the separate signs shall not exceed the maximum width permitted under this By-Law for a single wall sign on such wall. In addition, one sign indicating the brand of gasoline being sold may be erected of such type, in such location, and in such manner as the SPGA may allow by special permit. The standard type of gasoline pump bearing thereon in usual size and form, the name or type of gasoline and the price thereof shall not be deemed to be a sign within the meaning of this By-Law.

In addition to the above signs the following standards shall apply to Gasoline Filling Stations and Garages.

- a.) **Service Area Canopy Sign** – Maximum Size and Number of signs. Service area canopy signs are considered wall signs.
- b.) **Spandrel Sign** – Maximum Size and Number of signs. The maximum sign surface shall not exceed two (2) square feet per dispensing station regardless of the number of hoses. The signage allowed per dispensing station may be combined into one (1) sign on the spandrel. Signage is permitted on only two sides of the spandrel.
- c.) **Pump Island Signs.** In lieu of the spandrel sign, the gasoline services station may elect pump island signs or “pump toppers”. Pump Island Signs of two (2) square feet or less are allowed without permits. Pump Island signs greater than two (2) square feet are not allowed. Signage is permitted on only two sides of the pump island sign.
- d.) **No pennants** or other similar attracting or advertising devices shall be permitted except as noted in Section 11.20D (5), Temporary Signs.
- e.) **Signs on Perimeter Poles.** Signs placed on perimeter poles or other structures or those that are not expressly permitted in this Section shall be strictly prohibited.
- f.) **Operator Identification.** Operator Identification signs shall be located on the building only with a maximum dimension of six (6) square feet.
- g.) **Other Signs.** All other signs shall be located on the site of the use unless specified otherwise.

6) **Off Premises Signs:** Only signs pertaining to the premises on which they are located or to products, accommodations, services or activities on the premises shall be allowed, except that an off-premises directional sign designating the route to an establishment not on the street to which the sign is oriented may be erected and maintained at any intersection on private property. Such signs shall be authorized only upon the Building Inspector’s determination that such sign will not endanger the public safety. At locations where directions to more than one (1) establishment are to be provided, all such directional information shall be incorporated into a single structure.

7) **Menu Boards:** Menu Boards in conjunction with restaurant drive through pick up activities may be allowed under the following restrictions:

- a. Not more than one (1) such sign.
- b. Twenty-five foot (25’) setback from property lines.
- c. Thirty (30) square foot maximum area. Menu size sign shall not count against the freestanding identification sign area for a property.
- d. Six foot (6’) maximum height.
- e. May be freestanding or wall mounted.
- f. Shall be facing away from a public street
- g. Shall be screened from view from the public street.

G. **Nonconformance of Signs:** Signs legally existing on the effective date of this section may continue to be maintained, provided however, that no such sign shall be enlarged, have the principal wording changed or have a change in shape.

H. **Violations:** Any of the following shall be a violation of this zoning bylaw shall be subject to the enforcement remedies and penalties provided by this zoning by-law:

- (1) Inconsistent with Plan or Permit. To install, create, erect, or maintain any sign in a way that is inconsistent with any plan or permit governing such sign or the zoning lot on which the sign is located.
- (2) Failure to Obtain Permit. To install, create, erect, or maintain any sign requiring a permit without such a permit.
- (3) Failure to Remove Sign. To fail to remove any sign that is installed, created, erected, or maintained in violation of this zoning code, or for which the sign permit has lapsed.

## ARTICLE 11 (11.20H cont.)

- (4) Separate Violation Each Day. Each such day of a continued violation shall be considered a separate violation when applying the penalty portions of this zoning code.
- (5) Separate Violations. Each sign installed, created, erected, or maintained in violation of this zoning code shall be considered a separate violation when applying the penalty portions of this zoning code.

I. **Invalidity:** The invalidity of any section, sentence or provision of this by-law shall not affect the validity of any other section, sentence or provision thereof.

### 11.21 Drive Thru By-Law: *ATM 5/7/01, STM10/22/01*

A. **Purpose:** The drive-thru by-law is intended to reduce the negative impacts of drive-through facilities. These standards attempt to reduce the noise, lighting, and visual impacts of idling cars, voice amplification equipment, and queuing traffic on abutting uses, particularly on nearby residential uses. The standards are also intended to promote safe and efficient on-site vehicle and pedestrian circulation, and reduce conflicts between queuing traffic and traffic on adjacent streets.

#### B. **All Drive-thru Facilities Shall Comply with the Following Standards:**

- (a) All drive-thru facilities shall require a use permit approved by the Special Permit Granting Authority (SPGA). The SPGA for the purposes of this by-law shall be the Planning Board. Drive-thru facilities may be allowed as conditional uses, subject to the provisions of this section, in those planned development zones adopted by individual by-law, if office, retail or industrial uses are permitted in the zone district. However, at no time, are drive-thru's allowed in Residential or General Use Zones.
- (b) Drive-thru facilities may be approved only as accessory uses to a permitted use or facility. For example, a drive-thru window for a restaurant may be approved only as an accessory to a sit-down restaurant.
- (c) Locations at or near major intersections with traffic congestion may be approved only if it is demonstrated that the drive-thru will not significantly contribute to carbon monoxide "hot spots". For the purposes of this document, "hot spots" are defined as areas having relatively high concentrations of carbon monoxide.
- (d) Entries and/or exits to drive-thru facilities shall be a minimum of one hundred feet from any intersection, or from another drive-thru facility on the same side of the street, except within a shopping center. Shorter distances from road intersections may be approved if the SPGA determines that public safety and/or the efficiency of traffic circulation are not being compromised.
- (e) Drive-thru stacking lanes shall be a minimum one hundred feet from any residential zone. The SPGA may modify or waive this if it determines that the impacts to nearby residences will be minimal.
- (f) Speakers at drive-thru shall not be audible from adjacent residential uses or zones. Sound attenuation walls, landscaping or other mitigation measures may be required as necessary.
- (g) Pedestrian walkways shall not intersect the drive-thru aisles, but where they do, they shall have clear visibility and safe access and egress with a review by the SPGA.
- (h) Drive-thru aisles shall have a minimum twelve-foot width on curves and a minimum eleven-foot width on straight sections.
- (i) Drive-aisles shall provide sufficient stacking area behind the menu board to accommodate a minimum six cars (approximately one hundred fourteen feet) and will not interfere with parking, parking access aisles or any public or private ways.
- (j) No drive-thru aisles shall exit directly into a public right-of-way. Aisles shall be integrated with the on-site circulation and shall merge with the driveway.
- (k) Drive-aisles shall be delineated by a minimum six-inch high concrete or granite curbs or other suitable protective devices meeting SPGA approval.
- (l) All service areas, restrooms, and ground mounted mechanical equipment shall be screened from public view. Landscaping shall screen drive-thru aisles from the public right-of-way and shall be used to minimize the visual impacts of reader board signs and directional signs.
- (m) Menu board shall be a maximum of thirty square feet, with a maximum height of six feet, and shall face away from the street. Menu boards shall be screened from view from the public street.
- (n) Drive-thru's shall be architecturally compatible with nearby structures and complement existing or planned streetscape elements such as light poles and fixtures, sidewalk pavers, street trees and benches. Additionally, drive-thru shall provide landscaping to buffer adjacent uses, and provide adequate lighting, which is shielded from adjacent properties.

#### C. **Invalidity**

The invalidity of any section, sentence or provision of this by-law shall not affect the validity of any other section, sentence or provision thereof.

## ARTICLE 11

### 11.22 Retail and Wholesale Establishments *ATM 6/4/2007*

- A. **Purpose:** The retail and wholesale establishment by-law is intended to preserve the small-town character of the town of Freetown by limiting the sizes of retail establishments, wholesale establishments, and shopping centers. These standards attempt to reduce the noise, lighting, and visual impact of vehicles, structures, queuing traffic, potentially-necessary traffic signal lighting, and limited access traffic signaling on abutting uses; particularly, on nearby residential and environmental areas. It is also intended to reduce conflicts between queuing traffic and traffic on adjacent streets.
- B. **Definitions: (continued)**
- a. **Retail establishment or retail business:** A business establishment engaged in the sale, rental, or lease of goods or services to the ultimate consumer for direct use or consumption.
  - b. **Wholesale business or wholesale establishment:** A business establishment engaged in the sale, rental, or lease of goods and services to the ultimate consumer for direct use or consumption, as well as indirect use or consumption.
  - c. **Shopping center:** Any concentration of two or more retail and/or wholesale stores or service establishments containing 25,000 square feet or more of gross floor space.
- C. **All Retail and Wholesale Establishments Shall Comply with the Following Standards:**
- a. Notwithstanding any other provision of this by-law, no single retail business, whether located in a single structure, a combination of structures, single tenant space, or aggregate of structures or tenant spaces in an aggregate of structures, shall exceed 25,000 square feet of floor area. All adjacent retail or service establishments which share a common check stand, management, controlling ownership, or storage areas shall be considered a “single retail business” and their aggregate square footage of floor area shall be used to determine compliance with the standards of this by-law. This maximum floor area restriction shall apply to all new retail businesses and to all expansions of existing retail businesses.
  - b. Notwithstanding any other provision of this by-law, no single wholesale business, whether located in a single structure, a combination of structures, single tenant space, or aggregate of structures, shall exceed 25,000 square feet of floor area. All adjacent wholesale or service establishments which share a common check stand, management, controlling ownership, or storage areas shall be considered a “single wholesale business” and their aggregate square footage of floor area shall be used to determine compliance with the standards of this by-law. This maximum floor area restriction shall apply to all new wholesale businesses and to all expansions of existing wholesale businesses.
  - c. Notwithstanding any other provision of this by-law, no single shopping center that exceed 25,000 square feet of floor area, whether located in a single structure, a combination of structures, single tenant space, or aggregate of structures or tenant spaces in an aggregate of structures, shall exceed 25,000 square feet of floor area. All adjacent wholesale or service establishments which share a common check stand, management, controlling ownership, or storage areas shall be considered a “shopping center”, and their aggregate square footage of floor area shall be used to determine compliance with the standards of this by-law. This maximum floor area restriction shall apply to all new wholesale businesses and to all expansions of existing wholesale businesses.
  - d. All retail establishments, wholesale establishments and shopping centers constructed after July 1, 2007, shall be situated on a parcel no fewer than 70,000 square feet in area, of which such retail or wholesale establishment or shopping center shall occupy no more than eighty percent of the land area, including all impervious areas, for example but not limited to pavement, accessory structures, sidewalks, etc.

## ARTICLE 11 (11.22 cont.)

- e. Any proposed shopping centers, retail establishments, and/or wholesale establishments that exceed 25,000 square feet of floor area and are proposed to be located in either an Industrial (I) or Industrial /2 (I/2) zone may be permitted as an exception only if the Planning Board as Special Permit Granting Authority so determines and grants a Special Permit per Article 11.18, Section H. The Special Permit must be granted prior to the issuance of a building permit.

**D. Invalidity:** The invalidity of any section, sentence, or provision of this by-law shall not affect the validity of any other section, sentence, or provision thereof.

### **11.23 Site Plan Review By-Law ATM 5/7/2007**

#### **A. Findings:**

Projects that include buildings which exceed a combined gross of 10,000 square feet of floor area designed to be used for business and professional offices, commercial establishments, hotels, motels, industrial facilities, manufacturing facilities, medical-service facilities, public recreational facilities, warehouse facilities, and multiple family dwellings, together with their associated outdoor areas for vehicle movement and parking, invite and accommodate varying degrees of open and continuous use by the general public. Owing to their physical characteristic and the nature of their operations, such developments may affect neighboring properties and adjacent sidewalks and streets. It is in the interest of the community to promote functional and aesthetic design, construction, and maintenance of such developments and to minimize any harmful effects on surrounding areas.

#### **B. Powers and Administrative Procedures:**

The Planning Board is hereby designated the Site Plan Review Authority (SPRA) for Site Plan Approval. The SPRA shall adopt rules and regulations relative to the issuance of Site Plan Approval and file a copy with the town Clerk. Until such time that the SPRA adopts rules and regulations the Planning Board's Special Permit Regulations shall also be considered the Site Plan review Rules and Regulations. After notice and public hearing, if required, and after due consideration of the reports and recommendations of other town boards, commissions, and or departments, the SPRA may grant such approval. Site Plan approval must be received prior to the issuance of any required building permit.

#### **C. Purposes:**

The provisions of this section are designed to assure that all development activities regulated by this section will be carried out so as to provide for and maintain:

- a. Protection of neighboring properties against harmful effects of uses on the development site;
- b. Convenient and safe access for fire-fighting and all emergency rescue vehicles within the development site and in relation to adjacent streets;
- c. Convenience and safety of vehicular and pedestrian movement within the development site and in relation to adjacent streets, properties or improvements;
- d. Satisfactory methods for drainage of surface water to and from the development site;
- e. Satisfactory methods for storage, handling and disposal of sewage, refuse and other wastes resulting from the normal operations of the establishment(s) on the development site;
- f. Convenience and safety of off-street loading and unloading of vehicles, goods, products, materials, and equipment incidental to the normal operation of the establishment(s) on the development site; and
- g. Harmonious relationship to the terrain and to existing buildings in the vicinity of the development site.

## ARTICLE 11

### 11.24 Land-Based Wind Energy Facilities *ATM 06/07/2010*

- A. **Purpose:** The purpose of this bylaw is to provide standards for the placement, design, construction, operation, monitoring, modification and removal of wind facilities that address public safety, minimize impacts on scenic, natural and historic resources and to provide adequate financial assurance for the eventual decommissioning of such facilities.

The provisions set forth in this by-law shall take precedence over all other by-laws, when considering applications related to the construction, operation, and/or repair of land-based wind energy facilities.

- B. **Applicability:** This section applies to all utility-scale and on-site wind facilities proposed to be constructed after the effective date of this section. This section also pertains to physical modifications to existing wind facilities that materially alter the type, configuration, or size of such facilities or related equipment.

This section does not apply to offshore wind systems and private residential power systems.

- C. **Definitions**

**As-of-Right Siting:** As-of-Right Siting shall mean that development may proceed without the need for a special permit, variance, amendment, waiver, or other discretionary approval. As-of-right development shall be subject to site plan review to determine conformance with local zoning by-laws as well as state and federal law. As-of-right development projects that are consistent with zoning by-laws and with state and federal law cannot be prohibited.

**Building Inspector:** The inspector of buildings, building commissioner, or local inspector charged with the enforcement of the state building code.

**Building Permit:** The permit issued in accordance with all applicable requirements of the Massachusetts State Building Code (780 CMR).

**Height:** The height of a wind turbine measured from natural grade to the tip of the rotor blade at its highest point, or blade-tip height.

**Rated Nameplate Capacity:** The maximum rated output of electric power production equipment. This output is typically specified by the manufacturer with a “nameplate” on the equipment.

**Site Plan Review Authority:** The Planning Board is hereby designated as the Site Plan Review Authority to review site plans.

**Utility-Scale Wind Energy Facility:** A commercial wind energy facility, where the primary use of the facility is electrical generation to be sold to the wholesale electricity markets.

**Wind Energy Facility:** All of the equipment, machinery, and structures together utilized to convert wind to electricity. This includes, but is limited to, transmission, storage, collection and supply equipment, substations, transformers, service and access roads, and one or more wind turbines.

**Wind Monitoring or Meteorological Tower:** A temporary tower equipped with devices to measure wind speed and direction, to determine how much electricity a wind energy facility can be expected to generate.

**Wind Turbine:** A device that converts kinetic wind energy into rotational energy to drive an electrical generator. A wind turbine typically consists of a tower, nacelle body, and a rotor with two or more blades.

**Zoning Enforcement Authority:** The building commissioner is the person or board charged with enforcing the zoning by-laws within the Town of Freetown.

## ARTICLE 11 (11.24C cont.)

### D. General Requirements for all Wind Energy Facilities

The following requirements are common to all wind energy facilities to be sited in designated locations.

#### 1. Compliance with Laws, Ordinances and Regulations

The construction and operation of all such proposed wind energy facilities shall be consistent with all applicable local, state and federal requirements, including but not limited to all applicable safety, construction, environmental, electrical, communications and aviation requirements.

#### 2. Building Permit and Building Inspection

No wind energy system shall be erected, constructed, installed or modified as provided in this section without first obtaining a building permit.

#### 3. Fees

The application for a building permit for a wind energy system shall be accompanied by the fee required for a building permit.

### E. Site Plan Review

No wind energy facility shall be erected, constructed, installed or modified as provided in this section without first undergoing site plan review by the Site Plan Review Authority.

#### 1. General

All plans and maps shall be prepared, stamped and signed by a professional engineer licensed to practice in Massachusetts.

#### 2. Required Documents

Pursuant to the site plan review process, the project proponent shall provide the following documents:

- a. A site plan showing:
  - i. All property lines, physical features, existing and proposed topography at two (2) foot contour intervals of the site parcel;
  - ii. A site plan at a scale of not greater than 1" = 40' and to include a north arrow and locus on the plan;
  - iii. Outline of all existing buildings, including purpose (e.g. residence, garage, etc.) on site parcel and all adjacent parcels where practical, within 500 feet of the site parcel, including distances from the wind facility to each building shown;
  - iv. Location of the proposed tower, foundations, guy anchors, access roads, and associated equipment;
  - v. Location of all existing and proposed roads, both public and private, and including temporary roads or driveways, on the site parcel and adjacent parcels within 500 feet of the site parcel;
  - vi. Any existing overhead utility lines;
  - vii. Existing areas of tree cover, including average height of trees, on the site parcel and any adjacent parcels within a distance, measured from the wind turbine foundation, of 1.5 times the height of the wind turbine;
  - viii. Proposed changes to the landscape of the site, grading, vegetation clearing and planting, exterior lighting (other than FAA lights), screening vegetation or structures;
  - ix. Tower foundation blueprints or drawings signed by a Professional Engineer licensed to practice in the Commonwealth of Massachusetts;
  - x. Tower blueprints or drawings signed by a Professional Engineer licensed to practice in the Commonwealth of Massachusetts;
  - xi. One or three line electrical diagram detailing wind turbine, associated components, and electrical interconnection methods, with all National Electrical Code compliant disconnects and over-current devices;
  - xii. Documentation of the wind energy facility's manufacturer and model, rotor diameter, tower height, tower type (freestanding or guyed), and foundation type/dimensions;

## ARTICLE 11 (11.24E cont.)

- xiii. Name, address, phone number and signature of the applicant, as well as all co-applicants or property owners, if any;
  - xiv. The name, contact information and signature of any agents representing the applicant; and
  - xv. A maintenance plan for the wind energy facility;
- b. A locus map consisting of a copy of a portion of the most recent USGS Quadrangle Map, at a scale of 1:25,000, showing the proposed facility site, including turbine sites, and the area within at least two miles from the facility. Zoning district designation for the subject parcel should be included; submission of a copy of a zoning map with the parcel identified is suitable for this purpose;
  - c. Proof of liability insurance;
  - d. Certification of height approval from the FAA;
  - e. A statement that evidences the wind energy facility's conformance with Section 11.24, K, 6 listing ambient sound levels at the site and maximum projected sound levels from the wind energy facility; and
  - f. Description of financial surety that satisfies Section 11.24, M, 3

The Site Plan Review Authority may waive documentary requirements as it deems appropriate.

### F. Site Control

The applicant shall submit documentation of actual or prospective access and control of the project site sufficient to allow for installation and operation of the proposed wind energy facility. Control shall include the legal authority to prevent the use or construction of any structure for human habitation within the setback areas.

### G. Operation & Maintenance Plan

The applicant shall submit a plan for maintenance of access roads and storm water controls, as well as general procedures for operational maintenance of the wind facility.

### H. Utility Notification

No wind energy facility shall be installed until evidence has been given that the utility company that operates the electrical grid where the facility is to be located has been informed of the customer's intent to install an interconnected customer-owned generator. Off-grid systems shall be exempt from this requirement.

### I. Temporary Meteorological Towers (Met Towers)

A building permit shall be required for stand-alone temporary met towers. No site plan review shall be required for met towers.

### J. Design Standards

#### 1. Appearance, Color and Finish

Color and appearance shall comply with Federal Aviation Administration (FAA) safety requirements.

#### 2. Lighting

Wind turbines shall be lighted only if required by the FAA. Lighting of other parts of the wind energy facility, such as appurtenant structures, shall be limited to that required for safety and operational purposes, and shall be reasonably shielded from abutting properties. Except as required by the FAA, lighting of the wind energy facility shall be directed downward and shall incorporate full cut-off fixtures to reduce light pollution.

## ARTICLE 11 (11.24J cont.)

### 3. **Signage**

Signs on wind energy facilities shall comply with the Town's sign by-law. The following signs shall be required:

- a. Those necessary to identify the owner, provide a 24-hour emergency contact phone number, and warn of any danger.
- b. Educational signs providing information about the facility and the benefits of renewable energy.

Wind turbines shall not be used for displaying any advertising except for reasonable identification of the manufacturer or operator of the wind energy facility.

### 4. **Utility Connections**

Reasonable efforts, as determined by the Site Plan Review Authority, shall be made to place all utility connections from the wind energy facility underground, depending on appropriate soil conditions, shape, and topography of the site and any requirements of the utility provider.

Electrical transformers for utility interconnections may be above ground if required by the utility provider.

### 5. **Appurtenant Structures**

All appurtenant structures to wind energy facilities shall be subject to reasonable regulations concerning the bulk and height of structures, lot area, setbacks, open space, parking, and building coverage requirements. All such appurtenant structures, including but not limited to, equipment shelters, storage facilities, transformers, and substations, shall be architecturally compatible with each other and contained within the turbine tower whenever technically and economically feasible. Whenever reasonable, structures should be shaded from view by vegetation and/or located in an underground vault and joined or clustered to avoid adverse visual impacts.

### 6. **Height**

The height of wind energy facilities shall not exceed 450 feet in height.

## K. **Safety and Environmental Standards**

### 1. **Emergency Services**

The applicant shall provide a copy of the project summary, electrical schematic, and site plan to the police and fire departments, and/or the local emergency services entity designated by the local government. Upon request the applicant shall cooperate with local emergency services in developing an emergency response plan. All means of disconnecting the wind energy facility shall be clearly marked. The applicant or facility owner shall identify a responsible person for public inquires or complaints throughout the life of the project.

### 2. **Unauthorized Access**

Wind energy facilities shall be designed to prevent unauthorized access. For instance, the towers of wind turbines shall be designed and installed so that step bolts or other climbing features are not readily accessible to the public and so that step bolts or other climbing features are not installed below the level of 8 feet above the ground. Electrical equipment shall be locked where possible.

### 3. **Setbacks**

A wind turbine may not be sited within:

- a. A distance equal to three times (3x) the height of the wind turbine from buildings, critical infrastructure, or private or public ways that are not part of the wind energy facility;
- b. A distance equal to three times (3x) the height of the turbine from the nearest existing residential structure; or
- c. A distance equal to three times (3x) the height of the turbine from the nearest property line.

### 4. **Setback Waiver**

The Site Plan Review Authority may reduce the minimum setback distance as appropriate based on site-specific considerations, or written consent of the affected abutter(s), if the project satisfies all other criteria for the granting of a building permit under the provisions of this section.

## ARTICLE 11 (11.24K cont.)

### 5. **Shadow/Flicker**

Wind energy facilities shall be sited in a manner that minimizes shadowing or flicker impacts. The applicant has the burden of proving that this effect does not have significant adverse impact on neighboring or adjacent uses.

### 6. **Sound**

The operation of the wind energy facility shall conform with the provisions of the Department of Environmental Protection's, Division of Air Quality Noise Regulations (310 CMR 7.10).

### 7. **Land Clearing, Soil Erosion and Habitat Impacts**

Clearing of natural vegetation shall be limited to that which is necessary for the construction, operation and maintenance of the wind energy facility or otherwise prescribed by applicable laws, regulations, and by-laws.

## L. **Monitoring and Maintenance**

### 1. **Wind Energy Facility Conditions**

The applicant shall maintain the wind energy facility in good condition. Maintenance shall include, but not be limited to, painting, structural repairs, and integrity of security measures. Site access shall be maintained to a level acceptable to the local Fire Chief and Emergency Medical Services. The project owner shall be responsible for the cost of maintaining the wind energy facility and any access road(s), unless accepted as a public way.

### 2. **Modifications**

All material modifications to a wind energy facility made after issuance of the required building permit shall require approval by the Site Plan Review Authority.

## M. **Abandonment or Decommissioning**

### 1. **Removal Requirements**

Any wind energy facility which has reached the end of its useful life or has been abandoned shall be removed. The owner/operator shall physically remove the facility no more than 150 days after the date of discontinued operations. The applicant shall notify the Site Plan Review Authority by certified mail of the proposed date of discontinued operations and plans for removal.

Decommissioning shall consist of:

- a. Physical removal of all wind turbines, structures, equipment, security barriers and transmission lines from the site.
- b. Disposal of all solid and hazardous waste in accordance with local, state, and federal waste disposal regulations.
- c. Stabilization or re-vegetation of the site as necessary to minimize erosion. The Site Plan Review Authority may allow the owner to leave landscaping or designated below-grade foundations in order to minimize erosion and disruption of vegetation.

### 2. **Abandonment**

Absent notice of a proposed date of decommissioning or written not of extenuating circumstances, the wind energy facility shall be considered abandoned when the facility fails to operate for more than one year without the written consent of the Site Plan Review Authority. If the applicant fails to remove the facility in accordance with the requirements of this section within 150 days of abandonment or the proposed date of decommissioning, the town may enter the property and physically remove the facility.

### 3. **Financial Surety**

Applicants for utility-scale wind energy facilities shall provide a form of surety, either through escrow account, bond or otherwise, to cover the cost of removal in the event the town must remove the facility and remediate the landscape, in an amount and form determined to be reasonable by the Site Plan Review Authority, but in no event to exceed more than 125 percent of the cost of removal and compliance with the additional requirements set forth herein, as determined by the applicant. Such surety will not be required for municipally or state-owned facilities. The applicant shall submit a fully inclusive estimate of the costs associated with removal, prepared by a qualified engineer. The amount shall include a mechanism for calculating increased removal costs due to inflation.

## ARTICLE 11

### 11.25 South Main Street Corridor Overlay. *STM 2/25/2008*

#### A. Purposes.

This overlay district shall be called the South Main Street Corridor Overlay. The purpose of this overlay district is to maintain the integrity, viability, and safety of South Main Street, particularly as it relates to the Route 79/Exit 9 Highway corridor. As the town of Freetown grows and in order to protect the public interest, it is vital to ensure that the region encompassing the limited highway, public way, private way, and ancillary traffic resources adjacent to and contributing to traffic along South Main Street and the intersection of Rt. 24 and Rt. 79 is not over burdened, becoming an inoperable and unsafe “gateway” to our community and causing detriment to the public safety and harm to the existing businesses and residents currently within this district.

#### B. Special Permit Granting Authority.

The Planning Board of the Town of Freetown shall be the Special Permit Granting Authority (SPGA) for all approvals and special permits required under this Section.

#### C. Relationship to Other Districts.

1) This overlay district’s regulations supplement the zoning regulations of the underlying zoning district. The overlay district is an additional zoning requirement that does not change the underlying zoning.

2) When the overlay district standards conflict with applicable standards of the underlying zoning district or with other regulations of this by-Law, the regulations of the overlay district always govern. When no special overlay district standards are specified, the base district standards and all other applicable regulations of this By-Law will govern.

#### D. Requirements

1) Traffic Impact Study – A detailed traffic impact analysis shall be submitted to the Planning Board for any application for a new development whose principal use or an existing development whose change in use or anticipated change in traffic volume would have an anticipated average daily peak hour trip generation in excess of 100 vehicle trips. This traffic impact analysis shall analyze access and egress from South Main Street and Rt. 79 and their correlation to the Rt. 24 highway access ramps where applicable.

- a. Determination of Traffic impact. In determining traffic generation under this provision, the data contained in the most recent edition of The Institute of Transportation Engineers’ publication “Trip Generation” shall be used.

In the event that “Trip Generation” shall no longer be published, then its successor publication issued by the Institute of Transportation Engineers (or its successor organization) shall be used. In the event that there is no such successor publication, then the SPGA shall designate a successor publication or standard in its reasonable judgment, provided that such successor publication or standard is generally accepted by professional transportation engineers and the SPGA has made such determination in consultation with State and Federal transportation authorities.

- b. The traffic impact analysis shall be prepared by a registered professional engineer experienced and qualified in traffic engineering. Such engineer shall be acceptable to the SPGA. The SPGA may require a second study to be performed by a registered professional engineer identified by the SPGA acting in its sole discretion. All costs of any such second study shall be borne by the applicant.
- c. The traffic impact analysis shall be approved or disapproved by the SPGA by Special Permit. The SPGA must find that the traffic and any corresponding mitigation generated by the proposal will adequately protect the public interest and will not cause detriment to the public safety and harm to the existing businesses and residents within this district and the Town of Freetown.

2) Curb Cut Permit – All new curb cuts or proposed changes for existing curb cuts whose service use would have any anticipated average daily peak hour trip generation in excess of 100 vehicle trips shall require the receipt of a Special Permit from the Special Permit Granting Authority (SPGA).

- a. Performance Guidelines:

1. The SPGA shall base their decisions on the safety, design and expected performance of the proposed access/egress point as detailed in the aforementioned required traffic impact study.

## ARTICLE 11 (11.25D cont.)

2. Joint or shared curb cuts with adjoining parcels are encouraged. When it will facilitate such an arrangement the SPGA may reduce the required side yard setback on the parcel.
3. New curb cuts shall be no closer than 250 feet from a limited access highway ramp.
4. Existing curb cuts whose serviced use will be changed in a proposed development must demonstrate that this use will not cause undue traffic and safety concerns to other existing curb cuts, public ways, private ways, pedestrian access, highway, or otherwise.
5. Deleted (per AG 6/4/08 )

3) Multiple Parcel Regulation – Where a proposed development encompasses more than one parcel, and where said parcels are of differing zoning classifications and/or dimensional and site plan requirements (i.e. setbacks, building caps etc), the proposed development shall be governed by the strictest dimensional and site plan requirements contained therein.

**E. Description.** The South Main Street Corridor Overlay shall apply to all land abutting the South Main Street and Rte. 24 layouts from the Assonet Burial Ground to the Fall River City Line and consist of a fifty (50) foot setback area from the South Main Street and Rte. 24 layouts, as shown on the overlay plan attached hereto. The South Main Street Overlay shall apply to any curb cut onto a road or way whose sole access to any public way is South Main Street and provided that the service use of such curb cut would have any anticipated average daily peak hour trip generation in excess of 100 vehicle trips onto South Main Street.

### **11.26 ADULT RETIREMENT COMMUNITY** ATM 6/1/09, ATM 6/7/10

#### **A. PURPOSE and SCOPE**

This By-law is intended to allow an Adult Retirement Community (hereinafter ‘ARC’) use by Special Permit in order to encourage an alternative housing opportunity for persons aged fifty-five (55) years and older and to preserve common land for open space and recreation and provide an attractive residential environment suitable to the needs of people in their later years.

Notwithstanding any other provision of these By-laws, this provision, *Article 11.26*, shall apply to every ARC and shall supersede any requirements of this By-law which are inconsistent with them so that in the event of contradictory provisions within this By-law concerning ARC’s, the provisions of this *Article 11.26* shall prevail.

For the purposes of this By-law, the Planning Board shall be the Special Permit Granting Authority.

#### **B. DEFINITIONS**

**Adult Retirement Community (ARC):** A residential community consisting of detached single-family dwellings and/or duplex dwellings that shall be constructed on permanent foundations in accordance with Massachusetts Building Code 780 CMR as it pertains to “One and Two Family Dwelling Code” and “Foundations and Retaining Walls”. Each dwelling shall be shown on a site plan and shall be constructed expressly for and specifically limited to use and residency by persons who have met age requirement set forth in this By-law. Such developments shall comply in all respects with the requirements of M.G.L. Chapter 151B and the Federal Fair Housing Law.

**Common Facility:** A developed common area, constructed solely for the use of ARC residents and their guests. The Common Facility or Facilities may include, but shall not be limited to, parking lots, sidewalks and access roads, buildings, pools, spas, cabanas, accessory structures or rooms housing activities and amenities such as entertainment, recreation, education, physical activities, games, sewing, library, exercise, locker rooms, etc. Facilities may also include outdoor activities and amenities such as swimming, gardening, walking, putting greens, etc. All Common Facilities shall be designed and maintained in conformance with Massachusetts standards for handicapped accessibility. These facilities shall not be used for commercial purpose and shall be reserved to and for the use of the residents and their guests.

## ARTICLE 11 (11.26B cont.)

**Common Area:** An area that is intended to provide light and air, and is designed for environmental, scenic, or recreational purposes. Common Area may include, but is not limited to, lawns, decorative plantings, walkways, active and passive recreation areas, swimming pools, streets, wooded areas, and Common Facilities. The Common Area shall not be used for a commercial purpose and shall be reserved to and for the use of the residents and their guests.

### C. RESTRICTIONS

**Special Permit:** The Planning Board shall have jurisdiction to grant a special permit to allow an ARC use upon submission of a plan that is in conformance with the Town and Special Permit Granting Authority rules and regulations for special permits. The applicant shall also comply with the provisions set forth in *Article 11.6 (C), (I), (K), (L) and (M)*.

**Zoning:** A special permit shall be available in the General Use (G) and Residential (R) zoning districts, but shall be prohibited in Business (B), Industrial (I), Industrial 2 (I2), Open Space and Recreation (OSR), Village Business (VB) and Village Residential (VR) zoning districts.

**Age Limitation:** Occupancy of any unit in an ARC development shall be limited to one (1) or two (2) primary resident(s) at least one of whom has reached the age of fifty-five (55) years. There shall be no more than two (2) primary residents in an ARC Unit. In the event the primary resident(s) needs a full or part-time primary caregiver, then said caregiver may also reside in the unit. In the event the parents of the primary residents need to reside with a primary resident, then there may be more than two (2) residents in a unit, up to a maximum of two (2) residents per bedroom.

**Lot Size Area:** The minimum acreage for an ARC development shall be not less than ten (10) acres, a minimum two-thirds (2/3) of the overall acreage shall not consist of resource areas as defined under *Article 7.2* ("Freetown Wetlands Protection Bylaw").

**Frontage:** Every ARC project shall have a minimum of one hundred fifty (150) feet of frontage.

**Setback Requirements:** Every non-accessory building within the ARC shall be setback at least seventy-five (75) feet from all perimeter lot lines. The distance between proposed buildings shall be no less than forty (40) feet. Any and all perimeter setback areas may be required to contain densely planted evergreen screen plants and such additional requirements as the Special Permit Granting Authority may deem necessary to protect the privacy of abutting properties. Every accessory use building shall be setback at least thirty (30) feet from all perimeter lot lines.

**Density:** At least twenty (20%) percent of the total lot area shall be set aside as Common Land for use by the ARC residents and their guests. Not more than thirty (30%) percent of the required Common Land shall consist of resource area as defined in *Article 7.2* ("Freetown Wetlands Protection Bylaw"). No more than fifty percent (50%) of the total dwellings shall be duplex structures.

**Dwelling Construction Type:** Prohibited from being located or occupied within an ARC are trailers, mobile homes, and manufactured homes or other temporary dwellings or structures.

**Height:** The maximum height of any dwelling shall be the same height as a single family dwelling as set forth in *Article 11.17*.

**Parking:** The off-street parking space requirement for an ARC shall be a minimum of one (1) parking space for each unit contained therein. No other parking spaces shall be required as a result of other uses permitted to an ARC. No parking area or vehicular circulation space shall be nearer than thirty (30) feet to any lot line. If the ARC has a clubhouse or similar facility, clubhouse parking shall count toward the minimum parking requirement.

**Accessory Uses:** Accessory uses which are consistent with and supportive of the ARC and incidental to the principal uses indicated herein shall include, but not be limited to, administrative and professional offices required for operation of principal or accessory uses; swimming pool, exercise and locker facilities, lounge; snack bar and related facilities; adult and/or child day care facilities; places of public assembly, including auditorium and chapel facilities and a post office.

Any plans for the expansion or alteration of a building or use approved under an existing special permit shall require a filing for a modification of the special permit with a new public hearing with the SPGA and approval.

## ARTICLE 11 (11.26 cont.)

### D. OPERATION

The ARC must have an entity, corporation or trust controlled by the owners of the ARC Units through a Homeowners Association Trust that consists of all the owners in the development. Every ARC shall establish by-laws or policies which describe the organization of the Homeowners Association, and establish authority and responsibility. Said bylaws must contain language which enforces the 55 and over age restrictions, together with other rules and regulations. If this requirement is deleted, then the special permit shall become null and void and the project shall come immediately into compliance with applicable zoning requirements.

The Common Area shall be conveyed at no cost to the Homeowners Association and shall be subject to a permanent conservation restriction. The developer shall be responsible for the maintenance of the Common Land and Common Facilities until such time as the Homeowners Association assumes responsibility, pursuant to the by-laws. Thereafter, the Association shall share the cost of maintaining the Common Land and the Common Facilities. The Association By-laws shall provide for adequate funding of the responsibilities. Before the special permit is granted, the Planning Board, with the advice and counsel of Town Counsel, shall approve the form of ownership and original documentation creating the Homeowners Association prior to issuance of a Special Permit. Evidence of the recording of the Homeowners Association Trust and all related instruments and restrictive covenants shall be recorded prior to issuance of any building permit or occupancy for the project.

## 11.27 CONTINUING CARE RETIREMENT COMMUNITY ATM 6/1/09

### A. PURPOSE and SCOPE

This By-law is intended to allow a Continuing Care Retirement Community (hereinafter "CCRC") use by Special Permit in order to allow a greater flexibility in development from the guidelines otherwise permitted in the General Use (G) and Residential (R) zoning districts and to encourage the preservation of open spaces, while at the same time allowing a greater mixture of buildings, structures and uses, with special attention given to the concerns of the elderly and the ill in a campus-like setting.

Notwithstanding any other provision of these By-laws, this provision, *Article 11.27*, shall apply to every CCRC and shall supersede any requirements of this By-law which are inconsistent with them so that in the event of contradictory provisions within this By-law concerning CCRC's, the provisions of this *Article 11.27* shall prevail.

For the purposes of this By-law, the Planning Board shall be the Special Permit Granting Authority.

### B. DEFINITIONS

**Assisted Living Residence:** Housing and support services operated by a legal entity, however organized, whether conducted for profit or non-profit, which meets all of the following criteria:

- a. provides room and board;
- b. provides, directly by employees of the entity or through arrangements with another organization which the entity may or may not control, Personal Care Services for three or more adults who are not related by consanguinity or affinity to their care provider; and,
- c. collects payments or third-party reimbursements from or on behalf of residents to pay for the provision of assistance with Daily Living Activities.

**Bed Capacity:** The capacity of a building to accommodate a bed and the necessary physical appurtenances in accordance with the applicable standards imposed as a condition of operation under state law.

**Bedroom:** An interior sleeping room within a living unit, assisted living unit or long term care facility having an area of at least one hundred (100) square feet and a window directly to the exterior.

**Construction:** The construction of a new health care facility; the alteration of, expansion of, making of major repairs to, remodeling of, renovation of, or replacement of an existing health care facility.

**Continuing Care Retirement Community:** A planned development containing a minimum of three (3) of the following four (4) uses: independent living residences, assisted living residences, long-term care facilities (i.e. nursing homes), and elderly housing, but not necessarily limited to those uses.

## ARTICLE 11 (11.27B cont.)

**Daily Living Activities:** Those tasks related to bathing, dressing/grooming, ambulation, eating, toileting, and other similar tasks related to personal care needs.

**Determination of Need:** The formal decision of the Department of Public Health as set forth in 105 C.M.R. 100.000 et seq., as from time to time amended, to determine need in every instance where, under statutory authority, the Department of Public Health has jurisdiction to determine the need for any facility or any part or service of any such facility.

**Elderly Housing:** As defined in 651 C.M.R. 12.02 by the Department of Elder Affairs, as any residential premises available for lease by elderly or disabled individuals which is financed or subsidized in whole or in part by state or federal housing programs established primarily to furnish housing rather than housing and personal services, as set forth in a listing established by the Secretary of Elder Affairs, and which was never licensed under M.G.L. Chapter 111, as from time to time amended.

**Independent Living Residence:** Any residential premises available for lease by approved individuals, comprised of efficiency, single bedroom, double bedroom or triple bedroom living unit for which no assistance is required.

**Long-Term Care Facility:** Any institution which is maintained for the express or implied purpose of providing three or more individuals admitted thereto with long-term resident, nursing, convalescent or rehabilitative care; supervision and care incident to old age for ambulatory persons; or retirement home care for elderly persons, as more particularly set forth in 105 C.M.R. 150.000 et seq., as from time to time amended.

**Manager:** The individual or entity responsible for general administrative charge of the facility.

**Owner:** The individual or entity who owns the CCRC. Prior to construction, unless otherwise set forth, the owner shall be the record title-holder of the land upon which the proposed CCRC is to be built.

**Personal Care Service:** The assistance with one or more of the Daily Living Activities, either through physical support or supervision. Supervision shall include reminding and/or observing Residents while they perform activities.

**Residency Agreement:** The contract between the CCRC and a Resident or adult who seeks to reside in such CCRC on either a temporary or more permanent basis, which clearly describes the rights and responsibilities of the CCRC

**Resident:** An adult who resides in a CCRC and who receives housing and/or Resident Services.

**Resident Services:** Assistance with Daily Living Activities or other similar services, but not including concierge services, recreational or leisure services. Assistance is through either physical assistance or supervision.

**Transfer of Ownership:** Transfer of a majority interest in the Owner of a CCRC. In the case of an individual, transfer of ownership; in the case of a corporation, transfer of a majority of the stock thereof; in the case of a partnership, transfer of majority of the partnership interest; in the case of a trust, change of trustee or majority of trustees; and in the case of a non-profit corporation, transfer of a majority of corporate membership and/or directors. A transfer of ownership shall also be deemed to have occurred where foreclosure proceedings have been consummated by a mortgagee in possession of the premises.

**Unit:** A portion of an Independent Living Residence, Elderly Housing or an Assisted Living Residence designed for and occupied pursuant to Residency Agreements by approved individuals as the private living quarters of such individuals with a locking entry and bathing capacity (room equipped with a showerhead and/or bathtub to enable one person to take a shower or bath) and cooking capacity (refrigerator, sink and heating element) or the availability of a common dining facility.

## ARTICLE 11 (11.27 cont.)

### C. RESTRICTIONS

**Special Permit:** Application for a CCRC shall require submission of a plan to the Special Permit Granting Authority, in conformance with the Town Rules and Regulations for Special Permits. Applicant shall also comply with the provisions set forth in *Article 11.6 (C), (I), (K), (L) and (M)*.

**Zoning:** A “Continuing Care Retirement Community” shall be allowed by Special Permit (SP) within the General Use (G) and Residential (R) zoning districts, but shall be prohibited in Business (B), Industrial (I), Industrial 2 (I2), Open Space and Recreation (OSR), Village Business (VB) and Village Residential (VR) zoning districts.

**Age Limitation:** Occupancy of Independent Living Units shall be limited to one (1) or two (2) primary residents, at least one of whom has reached the age of fifty-five (55) years. Additional individual(s) may reside with the primary resident(s) upon approval by the management. Nothing in this provision shall prevent management from determining that a disabled person of any age is appropriate and suitable for the CCRC.

**Lot Size Area:** The minimum acreage required for a special permit shall be thirty (30) acres, of which a minimum two-thirds (2/3) of the total acreage shall not include a resource area as defined in *Article 7.2* (“Freetown Wetlands Protection Bylaw”).

**Frontage:** Every CCRC project must have at least seventy-five (75) feet of frontage.

**Setback Requirements:** Every non-accessory building within the CCRC shall meet the following setbacks: front setback of two hundred (200) feet from street; side and rear setback of one hundred (100) feet from property lines. Every accessory use building within the CCRC shall have a thirty (30) foot setback from all property lines. The distance between proposed buildings shall be no less than thirty (30) feet. Notwithstanding the foregoing, all buildings may be connected by a covered or enclosed walkway, whether or not elevated, within the areas separating buildings. Every accessory use building shall be setback at least thirty (30) feet from all perimeter lot lines.

Any and all such setbacks may be required to contain densely planted evergreen screen plants and such additional requirements as the Special Permit Granting Authority may deem necessary to protect the privacy of abutting properties.

**Density:** The maximum bed capacity shall be twenty (20) independent living units per acre on average, and the calculation of maximum density shall not include any assisted living units, nursing home units or medical beds, or any other uses that may be contained within the CCRC.

**Height:** The maximum height of any non-accessory building within the CCRC shall be determined according to its distance from the nearest lot line. The maximum height shall be thirty-five (35) feet at one hundred (100) feet of setback. For every additional thirty (30) feet of setback, the allowed height shall increase ten (10) feet, to a maximum height of seventy-five (75) feet.

**Parking:** The parking space requirement for a CCRC must be adequate for its intended uses according to generally accepted industry standards and as the Special Permit Granting Authority shall deem necessary. No parking area or vehicular circulation space shall be nearer than thirty (30) feet to any lot line.

**Accessory Uses:** Accessory uses which are consistent with and supportive of the CCRC and incidental to the principal uses indicated herein shall include, but not be limited to, administrative and professional offices required for operation of principal or accessory uses; lounge; snack bar and related facilities; beauty parlor; barber shop; pharmacy; laundry services; transportation; adult and/or child day care facilities; facilities for the sale of services and merchandise; places of public assembly, including auditorium and chapel facilities. Nothing in this Article shall prevent the inclusion of a religious or educational use on the CCRC campus, provided said use(s) does not comprise more than twenty-five percent (25%) of the lot area.

Any plans for the expansion or alteration of a building or use approved under an existing special permit shall require a modification of the special permit with a new public hearing by the SPGA and approval.

**Authority:** The Owner, or its representative, shall comply with all requisite federal and state laws. The Owner may not commence construction unless and until a favorable Determination of Need, as required, is issued from the Department of Public Health.

## ARTICLE 11 (11.27 cont.)

### D. OPERATION

Every CCRC shall designate a qualified manager and shall establish by-laws or policies which describe the organization of the facility, establish authority and responsibility, and identify programs and goals. The CCRC shall comply with all applicable state and federal guidelines.

Assisted living units shall include private bathroom facilities and common dining facility services shall be available to their occupants.

The CCRC shall provide for its residents, and may make available to its staff, a comprehensive system of outdoor recreational facilities such as gardens, seating areas, path networks, and game areas, which shall not exceed more than twenty-five (25%) percent of the lot area.

Upon transfer of ownership, written notice of said transfer, identifying the subsequent owner and contact information, shall be filed with the Special Permit Granting Authority within thirty (30) days thereof.

### **11.28 Large-Scale Ground-Mounted Solar Photovoltaic Installations** *ATM 06/07/2010*

#### A. Purpose

The purpose of this by-law is to promote the creation of new large-scale ground-mounted solar photovoltaic installations by providing standards for the placement, design, construction, operation, monitoring, modification and removal of such installations that address public safety, minimize impacts on scenic, natural and historic resources and to provide adequate financial assurance for the eventual decommissioning of such installations.

The provisions set forth in this section shall apply to the construction, operation, and/or repair of large-scale ground-mounted solar photovoltaic installations.

#### B. Applicability

This section applies to large-scale ground-mounted solar photovoltaic installations proposed to be constructed after the effective date of this section. This section also pertains to physical modifications that materially alter the type, configuration, or size of these installations or related equipment.

#### C. Definitions

**As-of-Right Siting:** As-of-Right Siting shall mean that development may proceed without the need for a special permit, variance, amendment, waiver, or other discretionary approval. As-of-right development shall be subject to site plan review to determine conformance with local zoning ordinances or by-laws. Projects cannot be prohibited, but can be reasonably regulated by the building inspector, or if there is none in a town, the board of selectmen, or person or board designated by local ordinance or by-law.

**Building Inspector:** The inspector of buildings, building commissioner, or local inspector, or person or board designated by local ordinance or by-law charged with the enforcement of the zoning ordinance.

**Building Permit:** A construction permit issued by an authorized building inspector; the building permit evidences that the project is consistent with the state and federal building codes as well as local zoning by-laws, including those governing ground-mounted large-scale solar photovoltaic installations.

**Large-Scale Ground-Mounted Solar Photovoltaic Installation:** A solar photovoltaic system that is structurally mounted on the ground and is not roof-mounted, and has a minimum nameplate capacity of 250kW DC.

**On-Site Solar Photovoltaic Installation:** A solar photovoltaic installation that is constructed at a location where other uses of the underlying property occur.

**Rated Nameplate Capacity:** The maximum rated output of electric power production of the Photovoltaic system in Direct Current (DC).

## ARTICLE 11 (11.28C cont.)

**Site Plan Review:** Review by the Site Plan Review Authority to determine conformance with local zoning ordinances or by-laws.

**Site Plan Review Authority:** For purposes of this by-law, Site Plan Review Authority refers to the Town of Freetown Planning Board.

**Zoning Enforcement Authority:** The person or board charged with enforcing the zoning ordinances or by-laws.

### D. General Requirements for all Large-Scale Solar Power Generation Installations

The following requirements are common to all solar photovoltaic installations to be sited in designated locations.

#### 1. Compliance with Laws, Ordinances and Regulations

The construction and operation of all large scale solar photovoltaic installations shall be consistent with all applicable local, state and federal requirements, including but not limited to all applicable safety, construction, electrical, and communications requirements. All buildings and fixtures forming part of a solar photovoltaic installation shall be constructed in accordance with the State Building Code.

#### 2. Building Permit and Building Inspection

No large scale solar photovoltaic installation shall be constructed, installed or modified as provided in this section without first obtaining a building permit.

#### 3. Fees

The application for a building permit for a large scale solar photovoltaic installation must be accompanied by the fee required for a building permit.

### E. Site Plan Review

Ground-mounted large scale solar photovoltaic installations with 250 kW or larger of rated nameplate capacity shall undergo site plan review by the Site Plan Review Authority prior to construction, installation or modification as provided in this section.

#### 1. General

All plans and maps shall be prepared, stamped and signed by a Professional Engineer licensed to practice in Massachusetts.

#### 2. Required Documents

Pursuant to the site plan review process, the project proponent shall provide the following documents:

##### a. A site plan showing:

- i. Property lines, access roads, site features and existing and proposed topography at two (2) foot contour intervals, for the project site;
- ii. A site plan at a scale not greater than 1" = 40';
- iii. Proposed changes to the landscape of the site, grading, vegetation clearing and planting, exterior lighting, screening vegetation or structures;
- iv. Blueprints or drawings of the solar photovoltaic installation signed by a Professional Engineer licensed to practice in the Commonwealth of Massachusetts showing the proposed layout of the system and any potential shading from nearby structures;
- v. One or three line electrical diagram detailing the solar photovoltaic installation, associated components, and electrical interconnection methods, with all National Electrical Code compliant disconnects and over-current devices;
- vi. Documentation of the major system components to be used, including the PV panels, mounting system, and inverter;
- vii. Name, address, and contact information for proposed system installer;
- viii. Name, address, phone number and signature of the project proponent, as well as all co-proponents or property owners, if any;
- ix. The name, contact information and signature of any agents representing the project proponent; and

b. Zoning district designation for the parcel(s) of land comprising the project site (submission of a copy of a zoning map with the parcel(s) identified is suitable for this purpose);

c. Proof of liability insurance; and

## ARTICLE 11 (11.28E cont.)

- d. Description of financial surety that satisfies Section 11.28,M, 3.

The Site Plan Review Authority may waive documentary requirements as it deems appropriate.

### F. Site Control

The project proponent shall submit documentation of actual or prospective access and control of the project site sufficient to allow for construction and operation of the proposed solar photovoltaic installation.

### G. Operation & Maintenance Plan

The project proponent shall submit a plan for the operation and maintenance of the large-scale ground-mounted solar photovoltaic installation, which shall include measures for maintaining safe access to the installation, storm water controls, as well as general procedures for operational maintenance of the installation.

### H. Utility Notification

No large-scale ground-mounted solar photovoltaic installation shall be constructed until evidence has been given to the Site Plan Review Authority that the utility company that operates the electrical grid where the installation is to be located has been informed of the solar photovoltaic installation owner or operator's intent to install an interconnected customer-owned generator. Off-grid systems shall be exempt from this requirement.

### I. Dimension and Density Requirements

#### 1. Setbacks

For large-scale ground-mounted solar photovoltaic installations, front, side and rear setbacks shall be as follows:

- a. **Front yard:** The front yard depth shall be at least fifty (50) feet.
- b. **Side yard:** Each side yard shall have a depth at least twenty (20) feet; provided, however, that where the lot abuts a Conservation-Recreation or Residential district, the side yard shall not be less than fifty (50) feet.
- c. **Rear yard:** The rear yard depth shall be at least twenty-five (25) feet; provided, however, that where the lot abuts a Conservation-Recreation or Residential district, the rear yard setback shall not be less than fifty (50) feet.

#### 2. Appurtenant Structures

All appurtenant structures to large-scale ground-mounted solar photovoltaic installations shall be subject to reasonable regulations concerning the bulk and height of structures, lot area, setbacks, open space, parking and building coverage requirements. All such appurtenant structures, including but not limited to, equipment shelters, storage facilities, transformers, and substations, shall be architecturally compatible with each other. Whenever reasonable, structures should be shaded from view by vegetation and/or joined or clustered to avoid adverse visual impacts.

### J. Design Standards

#### 1. Lighting

Lighting of solar photovoltaic installations shall be consistent with local, state and federal law. Lighting of other parts of the installation, such as appurtenant structures, shall be limited to that required for safety and operational purposes, and shall be reasonably shielded from abutting properties. Where feasible, lighting of the solar photovoltaic installation shall be directed downward and shall incorporate full cut-off fixtures to reduce light pollution.

#### 2. Signage

Signs on large-scale ground-mounted solar photovoltaic installations shall comply with a municipality's sign by-law. A sign consistent with a municipality's sign by-law shall be required to identify the owner and provide a 24-hour emergency contact phone number.

#### 3. Utility Connections

Reasonable efforts, as determined by the Site Plan Review Authority, shall be made to place all utility connections from the solar photovoltaic installation underground, depending on appropriate soil conditions, shape, and topography of the site and any requirements of the utility provider. Electrical transformers for utility interconnections may be above ground if required by the utility provider.

## ARTICLE 11 (11.28 cont.)

### K. Safety and Environmental Standards

#### 1. Emergency Services

The large-scale solar photovoltaic installation owner or operator shall provide a copy of the project summary, electrical schematic, and site plan to the local Fire Chief. Upon request the owner or operator shall cooperate with local emergency services in developing an emergency response plan. All means of shutting down the solar photovoltaic installation shall be clearly marked. The owner or operator shall identify a responsible person for public inquires throughout the life of the installation.

#### 2. Land Clearing, Soil Erosion and Habitat Impacts

Clearing of natural vegetation shall be limited to what is necessary for the construction, operation and maintenance of the large-scale ground-mounted solar photovoltaic installation or otherwise prescribed by applicable laws, regulations, and by-laws.

### L. Monitoring and Maintenance

#### 1. Solar Photovoltaic Installation Conditions

The large-scale ground-mounted solar photovoltaic installation owner or operator shall maintain the facility in good condition. Maintenance should include, but not be limited to, painting, structural repairs, and integrity of security measures. Site access shall be maintained to a level acceptable to the local Fire Chief and Emergency Medical Services. The owner or operator shall be responsible for the cost of maintaining the solar photovoltaic installation and any access road(s), unless accepted as a public way.

#### 2. Modifications

All material modifications to a solar photovoltaic installation made after the issuance of the required building permit shall require approval by the Site Plan Review Authority.

### M. Abandonment or Decommissioning

#### 1. Removal Requirements

Any large-scale ground-mounted solar photovoltaic installation which has reached the end of its useful life or has been abandoned consistent with Section 11.28, M, 2 of this by-law shall be removed. The owner or operator shall physically remove the installation no more than 150 days after the date of discontinued operations. The owner or operator shall notify the Site Plan Review Authority by certified mail of the proposed date of discontinued operations and plans for removal. Decommissioning shall consist of:

- a. Physical removal of all large-scale ground-mounted solar photovoltaic installations, structures, equipment, security barriers and transmission lines from the site.
- b. Disposal of all solid and hazardous waste in accordance with local, state, and federal waste disposal regulations.
- c. Stabilization or re-vegetation of the site as necessary to minimize erosion. The Site Plan Review Authority may allow the owner or operator to leave landscaping or designated below-grade foundations in order to minimize erosion and disruption to vegetation.

#### 2. Abandonment

Absent notice of a proposed date of decommissioning or written notice of extenuating circumstances, the solar photovoltaic installation shall be considered abandoned when it fails to operate for more than one year without the written consent of the Site Plan Review Authority. If the owner or operator of the large-scale ground-mounted solar photovoltaic installation fails to remove the installation in accordance with the requirements of this section within 150 days of abandonment or the proposed date of decommissioning, the town may enter the property and physically remove the installation.

## ARTICLE 11 (11.28M cont.)

### 3. Financial Surety

Proponents of large-scale ground-mounted solar photovoltaic projects shall provide a form of surety, either through escrow account, bond or otherwise, to cover the cost of removal in the event the town must remove the installation and remediate the landscape, in an amount and form determined to be reasonable by the Site Plan Review Authority, but in no event to exceed more than 125percent of the cost of removal and compliance with the additional requirements set forth herein, as determined by the project proponent. Such surety will not be required for municipally – or state-owned facilities. The project proponent shall submit a fully inclusive estimate of the costs associated with removal, prepared by a qualified engineer. The amount shall include a mechanism for calculating increased removal costs due to inflation.

## ARTICLE 12

### DEMOLITION DELAY BY-LAW *ATM 5/5/03, STM 10/27/03*

**12.0 Freetown Historical Commission** The purpose of Freetown’s Demolition Delay By-law is to preserve and protect significant buildings and structures within the Town which constitute or reflect distinctive features of the architectural, cultural, political, economic, or social history of the town and to encourage owners of such buildings to seek out persons who might be willing to purchase, preserve, rehabilitate, or restore such buildings rather than demolish or relocate them. To achieve these purposes the Freetown Historical Commission is empowered to advise the Building Commissioner with respect to the issuance of permits for demolition of significant buildings and to delay demolition of such buildings and structures for 12 months. Generally, significant buildings and structures are those which are:

1. Importantly associated with one or more historic persons or events, or with the architectural, cultural, political, economic or social history of the Town, the Commonwealth of Massachusetts or the United States of America; or
2. Historically or architecturally important by reason of period, age, style, method of building construction or association with a particular architect or builder, either by itself or in the context of a group of buildings or structures.

For the purposes of the by-law, this includes:

1. Properties listed on the State or National Register of Historic Places and the Inventory of Historic Assets of the Commonwealth for the Town of Freetown,
2. Properties in existence in or before 1903 (e.g. current date less 100 years)

#### **Demolition Delay By-law Contents**

- 12.1 [Intent and Purpose](#)
- 12.2 [Definitions](#)
- 12.3 [Regulated Buildings and Structures](#)
- 12.4 [Procedure](#)
- 12.5 [Determination of Applicability](#)
- 12.6 [Emergency Demolition](#)
- 12.7 [Non-Compliance](#)
- 12.8 [Severability](#)

## ARTICLE 12 (cont.)

### 12.1 Intent and Purpose

This by-law is adopted for the purpose of preserving and protecting significant buildings within the Town, which constitute or reflect distinctive features of the architectural, cultural, political, economic, or social history of the town; to encourage owners of such buildings to seek out persons who might be willing to purchase, preserve, rehabilitate, relocate or restore such buildings rather than demolish them. To achieve these purposes the Freetown Historical Commission (herein after the "Commission") is empowered to advise the Building Inspector with respect to the issuance of permits for demolition of significant buildings.

### 12.2 Definitions

1. **Building** – Any combination of materials capable of being used as a shelter for persons, animals or property.
2. **Commission** – The Freetown Historical Commission.
3. **Building Inspector** – The Freetown Inspector of Buildings.
4. **Demolition Permit** – The permit issued by the Building Inspector as required by the state building code for the demolition or removal of a building or structure.
5. **Historically Significant Building or Structure** – Any building or structure which is (1) importantly associated with one or more historic persons or events, or with the architectural, cultural, political, economic or social history of the Town, the Commonwealth of Massachusetts or the United States of America; or (2) is historically or architecturally important by reason of period, age, style, method of building construction or association with a particular architect or builder, either by itself or in the context of a group of buildings or structures.

### 12.3 Regulated Buildings and Structures

1. A building or structure listed on, or is within an area listed on, the National Register of Historic Places or the State Register of Historic Places, or the subject of a pending application for listing on either of said Registers; or
2. A building or structure located within 200 feet of the boundary line of any federal, state or local historic district; or
3. A building or structure included in the Inventory of the Historic Assets of the Commonwealth, or designated by the Commission for inclusion in said inventory including those buildings listed for which complete surveys may be pending; or
4. A building or structure determined by vote of the Commission to be historically or architecturally significant in terms of period, style, and method of building construction based on the following criteria:
  - Properties listed on the National or State Register of Historic Places and the Inventory of Historic Assets of the Commonwealth for the Town of Freetown.
  - Properties in existence on or before 1903.
  - Properties that appear on the **1871 Map of Freetown**.
5. No demolition permit shall be issued for a regulated building or structure without full compliance with the provisions of this by-law.

### 12.4 Procedure

1. The Building Inspector shall forward a copy of each demolition permit application for all regulated buildings or structures identified in section 12.3 of this section to the Commission within *thirty (30) days* after the filing of such application. No demolition permit shall be issued at that time.

## ARTICLE 12.4 (cont.)

2. Within *sixty (60) days* after the receipt of such application, the Commission shall determine whether the building or structure is historically significant.
3. **A.** If the Commission determines that the building or structure is not historically significant, it shall so notify the Building Inspector and the applicant in writing and the Building Inspector may issue a demolition permit. If the Commission fails to notify the Building Inspector and the applicant of its determination within the *sixty (60) days* after its receipt of the application, then the building or structure shall be deemed not historically significant and the Building Inspector may issue a demolition permit.  
**B.** If the Commission determines that the building or structure is historically significant, it shall notify the Building Inspector and the applicant in writing that a demolition plan review must be made prior to the issuance of a demolition permit.
4. Within *forty-five (45) days* after the applicant is notified that the Commission has determined that a building or structure is historically significant, the applicant for the permit shall submit to the Commission seven (7) copies of a demolition plan which shall include the following information: (i) a map showing the location of the building or structure to be demolished with reference to lot lines and to neighboring buildings and structures; (ii) photographs of all street façade elevations; (iii) a description of the building or structure to be demolished; (iv) the reason for the proposed demolition and data supporting said reasons, including, where applicable, data sufficient to establish any economic justification for demolition; and (v) a brief description of the proposed reuse of the parcel on which the building or structure to be demolished is located.
5. The Commission (in conjunction with Planning Board) shall hold a public hearing, within *forty-five (45) days* of receipt of the demolition plan referenced in paragraph four, with respect to the application for a demolition permit, and shall give public notice of the time, place, and purposes thereof at least *fourteen (14) days* before said hearing in such manner as it may determine, and by mailing, postage prepaid, a copy of said notice to the applicant, to the owners of all adjoining property and other property deemed by the Commission to be materially affected thereby as they appear on the most recent real estate tax list of the Board of Assessors, to the Planning Board, to any person filing written request for notice of hearings, such request to be renewed yearly in December, and to such other persons as the Commission shall deem entitled to notice. Within *forty-five (45) days* after public hearing, the Commission shall file a written report with the Building Inspector on the demolition plan which shall include the following: (i) a description of age, architectural style, historic association and importance of the building or structure to be demolished (ii) a determination as to whether or not the building or structure should preferably be preserved. The Commission shall determine that a building or structure should preferably be preserved only if it finds that the building or structure is an historically significant building or structure which, because of the important contribution made by such building or structure to the Town's historical and/or architectural resources, it is in the public interest to preserve, rehabilitate, relocate or restore.
6. If, following the demolition plan review, the Commission does not determine that the building or structure should preferably be preserved, or if the Commission fails to file a report with the Building Commissioner within the time limit set out in subparagraph (5) next above, then the Building Inspector may issue a demolition permit.
7. If, following the demolition plan review, the Commission determines that the building or structure should preferably be preserved, then the Building Inspector shall not issue a demolition permit for a period of *twelve (12) months* from the date of the filing of the initial request for a demolition permit unless the Commission informs the Building Inspector prior to the expiration of such *twelve (12) month* period that it is satisfied that the applicant for the demolition permit has made a bona fide, reasonable and unsuccessful effort to locate a purchaser for the building or structure who is willing to preserve, rehabilitate, relocate or restore the building or structure, or has agreed to accept a demolition permit on specific conditions approved by the Commission. During *the twelve (12) month* review period, the Commission shall invite the Applicant to participate in an investigation of alternatives to demolition.

## ARTICLE 12 (cont.)

### 12.5 Determination of Applicability

An owner of a regulated building or structure may petition the Commission for a determination of applicability of the bylaw. Within *sixty (60) days* after the receipt of such application, the Commission shall determine whether the building or structure is historically significant. The applicant for the permit shall be entitled to make a presentation to the Commission if he or she makes a timely request in writing to the Commission. The determination by the Commission of whether a regulated building or structure is historically significant shall be made in writing signed by the Commission and shall be binding on the Commission for a period of *five (5) years* from the date thereof.

### 12.6 Emergency Demolition

If the condition of a building or structure poses a serious and imminent threat to public health or safety due to its deteriorated condition, the owner of such building or structure may request the issuance of an emergency demolition permit from the Building Inspector. If possible and as soon as practical after the receipt of such a request, the Building Inspector shall arrange to have the property inspected by a board consisting of himself, the Chairman of the Commission and the Chairman of the Board of Health, and the Chief of the Fire Department, or their respective designees. After inspection of the building or structure and, to the extent possible, consultation with this Board, the Building Inspector shall determine whether the condition of the building or structure represents a serious and imminent threat to public health or safety and whether there is any reasonable alternative to immediate demolition of the building or structure which would protect the public health or safety. If the Building Inspector finds that the condition of the building or structure poses a serious and imminent threat to public health or safety, and that there is no reasonable alternative to the immediate demolition permit under the provision of this paragraph (12.5), they shall prepare a written report describing the condition of the building or structure and the basis for his decision to issue an emergency demolition permit with the Commission. Nothing in this paragraph (12.5) shall be inconsistent with the procedures for the demolition and/or securing of building and structures established by Chapter 143, section 6-10, of the Massachusetts General Laws. In the event that a Board of Survey is convened under the provisions of Section 8 of said Chapter 143 with regard to any building or structure identified in paragraph (12.3) of this section, the Building Inspector shall request the Chairman of the Commission or his designee to accompany that Board of Survey during its inspection. A copy of the written report prepared as a result of such inspection shall be filed with the Commission.

### 12.7 Non-Compliance

1. The Commission and the Building Inspector are each authorized to institute any and all proceedings in law or equity, as they deem necessary and appropriate to obtain compliance with the requirements of this bylaw, or to prevent a violation thereof.
2. No building permit shall be issued with respect to any premises upon which a significant building has been voluntarily demolished in violation of this bylaw for a period of twenty-two months after the date of the completion of such demolition. As used herein "premises" includes the parcel of land upon which the demolished significant building is located.
3. Upon a determination of the Commission that a building is a preferably preserved significant building, the owner shall be responsible for properly securing the building, if vacant, to the satisfaction of the Building Inspector. Should the owner fail to secure the building, the loss of such building through fire or other cause shall be considered voluntary demolition for the purposes of section 12.7 (2).
4. Anyone who demolished a building or structure identified in paragraph 12.3 of this section without first obtaining, and complying fully with the provisions of, a demolition permit, shall be subject to a fine of **two hundred (200) dollars**.


### 12.8 Severability

If any section, paragraph or part of this bylaw be for any reason declared invalid or unconstitutional by a court authority, every other section, paragraph and part shall continue in full force and effect.

(Planning Board Approves)

### 12.9 Demolition Delay Bylaw Flowchart

<http://www.assonetriver.com/sites/freetown/fhc/demodelay.asp>



## **ARTICLE 13**

### **USE OF STREETS, SIDEWALKS, AND PUBLIC PLACES**

*ATM 5/6/00, STM 10/27/03*

#### **13.1 Use of Streets, Sidewalks, and Public Places** *STM 7/15/76, STM 5/1/89, STM 1/25/93, ATM 5/6/96*

These rules are adopted with the intent to promote the safe passage of vehicles and pedestrians along the public ways within the Town of Freetown.

Each rule shall have force and effect separately and independently of every other insofar as by express reference or necessary implication, any rule or any part of a rule is made dependent upon another rule or part thereof.

#### **13.2 Definitions**

For the purpose of Article 13 the words and phrases used herein shall have the following meanings, except in those instances where the context clearly indicates a different meaning:

**Bicycle.** Any wheeled vehicle propelled by pedals and operated by one or more persons.

**Bus.** Every vehicle designed for carrying more than eight passengers and used primarily for the transportation of persons either for compensation, as a service, or as an adjunct to a school program.

**Bus Stop.** An area in a roadway set aside for the boarding of or alighting from buses.

**Caution Signal.** A flashing yellow signal having the same general function as a warning sign.

**Chief of Police.** The appointed Police Chief of the Town of Freetown, or, in his absence, the designated acting Police Chief of the Town of Freetown, or, an officer designated by such chief or acting chief to act on their behalf.

**Channelizing Island.** A traffic island located to guide traffic streams along certain definite paths and to prevent the promiscuous movement of vehicles in what would otherwise be a widely extended roadway area.

**Commercial Vehicle.** Any vehicle registered for commercial purposes and designed and used primarily for the transportation of goods, wares or merchandise.

**Construction Material.** Material including, but not limited to gravel, sand, stone, asphalt, loam, wire, utility poles, pipes, conduits, tree limbs, tree trunks, and mulch, dumpsters or any other material deemed to be construction material by the Chief of Police.

**Construction Vehicle.** Any vehicle and/or trailer, whether attached or unattached to any construction vehicle, used in conjunction with, and engaged in, the loading, unloading, excavating, grading or spreading of construction material; the trimming or cutting of trees along a roadway; installation, maintenance or repair of driveways, sidewalks, asphalt, lighting, wires, cables equipment pipes and conduits.

**Container.** Any drum, barrel, cylinder, bag, carboy or other shipping vessel (other than a tank vehicle) used for the transportation of dangerous articles.

**Crossover.** An opening in a channelizing island that connects both sides of a divided roadway.

**Crosswalk.** That portion of a roadway ordinarily included within the extensions of the sidewalk lines, or, if none then the footpath lines, and, at any place in a roadway, clearly indicated for pedestrian crossing by lines or markers upon the roadway surface.

**Curb Marking.** That portion of a curbing which has been painted by the Department.

**Department.** The Town of Freetown Department of Highways.

## ARTICLE 13 (13.2 cont.)

**Divided Way.** A public way with separated roadways for traffic in opposite directions.

**Emergency Vehicle.** Vehicles of the Fire Department (Fire Patrol), police vehicles and such ambulances and emergency vehicles of federal, state or municipal departments or public service corporations as are commonly recognized as such.

**Flag Man.** Person or person(s), privately employed, who have received training in the direction of motor vehicles and pedestrian traffic upon ways, and who are equipped with such equipment as to adequately warn and direct such traffic.

**Intersection.** The area embraced within the extensions of lateral curb lines, or, if none, then the lateral boundary lines, of intersection ways as defined in M.G.L. c. 90, §1, including divided ways.

13.1 herein contained governing and restricting the movement of vehicles on public ways at and near intersecting ways shall apply at any place along any way at which drivers are to be controlled by traffic control signals whether or not such place is an intersection as herein defined.

**Lane.** A longitudinal division of a roadway of sufficient width to accommodate the passage of a single line of vehicles, whether or not such lane is indicated by pavement markings or longitudinal construction joints.

**Limited Access Highway.** An express state highway with full control of access.

**Officer.** Any Freetown police officer, or any police officer authorized to direct or regulate traffic or to make arrests for violations of traffic regulations.

**Official Signs.** Signals, markings and devices. All signs, signals, markings and devices installed or maintained by the Department.

**One-Way Roadways.** Roadways, designated by the Department as one-way and upon which vehicular traffic may move only in the direction indicated by signs.

**Parking.** The stopping or standing of a vehicle whether occupied or not, otherwise than temporarily, except that a vehicle shall not be deemed parked when stopped or standing for the purpose of and while actually engaged in loading or unloading or in obedience to an officer or traffic control signs or signals, or while making emergency repairs or, if disabled, while arrangements are being made to move such vehicle forthwith.

**Pedestrian.** Any person afoot or riding on a conveyance moved by human power, except bicycles or tricycles.

**Public Way.** The entire width between property lines of any town way or lawful throughway designated by the Town.

**Roadway.** That portion of a public way between regularly established curb lines or that part, exclusive of shoulders, improved and intended to be used for vehicular traffic.

**Rotary Traffic.** The counter-clockwise operation of a vehicle around an island or other structure in the roadway.

**Sidewalk.** That portion of a public way set aside for pedestrian travel.

**Stop Signal.** A Flashing Red Signal having the same function as a stop sign and erected by or under the control of the Department.

**Street Marking.** Any painted line, legend, marking or marker of any description painted or placed on any public way by the Department and which purports to direct or regulate traffic.

**Tank Vehicle.** Any tank type motor vehicle with cargo tank, portable tank or bulk pyramided cylinders, used for the transportation of liquids or gases.

**Town.** The Town of Freetown.

## ARTICLE 13 (13.2 cont.)

**Traffic.** Pedestrians, ridden or herded animals, vehicles, street cars or other conveyances either singly or together while using any public way for the purpose of travel.

**Traffic Control Signal.** A roadway traffic signal which, through its indications, alternately directs traffic to stop and permits it to proceed and which has been erected by or is under the control of the Department.

**Traffic Island.** Any area or space set aside, within a roadway, which is not intended for use by vehicular traffic.

**Traffic Signals.** Any power-operated traffic control device, except a sign, by which traffic is warned or is directed to take some specific action, and which has been erected by or is under the control of the Department.

**U Turn.** The turning of a vehicle by means of a continuous left turn whereby the direction of such vehicle is reversed.

**Urban Area.** The territory contiguous to and including any street which is built up with structures devoted to business, industry or dwelling houses situated at intervals of less than 100 feet for a distance of a quarter of a mile or more.

**Vehicle.** Every device in, upon or by which any person or property is or may be transported or drawn upon a highway, including bicycles, mopeds and scooters, when the provisions of these rules are applicable to them, except other devices moved by human power or used exclusively upon stationary rails or tracks and devices which derive their power for operation from stationary overhead wires.

### 13.3 Parking *ATM 5/5/80, STM 10/24/11*

(1) **Restricted Places.** No person shall stand or park any vehicle in any public parking area, way or roadway under control of the Town and no person or entity shall allow, permit, or suffer any vehicle registered in his or her name to stand or park in any public parking area, way or roadway under the control of the Town in violation of any rule, regulation, or bylaw and in particular in any of the following places except in compliance with the direction or supervision of an officer or official traffic control sign or signal:

- (A) Within an intersection.
- (B) Upon a sidewalk.
- (C) Upon a crosswalk.
- (D) Upon any roadway where the parking or standing of a vehicle will obstruct the normal movement of traffic.
- (E) Upon any public way or roadway within ten (10) feet of a fire hydrant.
- (F) Upon any roadway within twenty (20) feet of an intersection.
- (G) Upon any public way or roadway in front of any private road or driveway, blocking or limiting access to such private road or driveway, without the consent of the owner of such road or driveway.
- (H) Upon any public way or roadway where the parking or standing of a vehicle will obstruct or hide from view any official traffic control sign or signal.
- (I) Upon any bridge under the control of the Town.
- (J) Upon the roadway side ("double parking") of any vehicle stopped or parked at the edge or curb of the roadway.
- (K) Upon any roadway unless the right wheels of the vehicle are within twelve (12) inches of edge or curb of the roadway.
- (L) Upon any public way or roadway in such a manner as to impede or obstruct the removal or plowing of snow or ice.
- (M) Upon any public parking area, way, roadway, or part thereof, where the parking or standing of such vehicle has been prohibited by the board or officer in charge of such public parking area, way or roadway, provided that such public parking area, way, roadway, or portion thereof, has been marked or signed so as to acquaint a driver of such prohibition.

## ARTICLE 13 (13.3 cont.)

(2) **Emergency Repair.** No person shall park a vehicle in any public way except upon the shoulder for the purpose of changing a tire or making emergency repairs, unless such vehicle is so damaged or disabled that it cannot be moved safely under its own power.

(3) **Exemptions.** The provisions of Section 13.3: Parking, shall not apply to emergency vehicles, vehicles owned by the Town, and vehicles owned by the commonwealth of Massachusetts.

### **13.4 Police May Prohibit Parking Temporarily**

The Chief of Police is hereby authorized to prohibit parking, temporarily, on any public way, roadway, or part thereof, in an impending or existing emergency, or for a lawful assemblage, demonstration, procession, provided there is reasonable justification for such prohibitions. Vehicles parked in places where parking is prohibited temporarily may be removed by or under the direction of a Sergeant or police officer of higher rank.

### **13.5 Towing**

(1) **Authorization of Police.** Sergeants, or police officers of higher rank within the Freetown Police Department, are authorized, with such limitations as are, or may hereinafter set forth, to remove or cause to be removed to some convenient place any vehicle parked in violation of the provisions set forth in Section 13.3: Parking.

### **13.6 Construction Vehicles; Construction Materials; Construction in Public Ways**

(1) **Permit Required.** No person, unless he is the holder of a permit issued by the Board of Selectmen, and is acting in accordance with the terms and conditions of that permit, shall construct, reconstruct, install or repair anything that is on, over or under any public way. Nothing in this section shall be construed as to prohibit the Board of Selectmen from placing a moratorium on the breaking of any roadway surface or sidewalk.

(2) **Men and Construction Vehicles.** Before undertaking any of the foregoing, including persons operating or working in conjunction with a construction vehicle or construction material that is on, over or under any public way, the person responsible for such work or in charge of those performing such work, shall review such work with the Chief of Police to determine whether or not such work will disrupt the normal flow of vehicular traffic or cause a safety hazard to pedestrian or vehicular traffic.

(3) **Duties of the Chief of Police.** The Chief of Police may, in his discretion, order that an officer or officers, as may be required and at no cost to the Town, accompany construction vehicles engaged in work or construction materials placed on public ways, or men working on, over or under public ways, for the purpose of ensuring the safe passage of vehicles and pedestrians in such work area or storage sites. In the event that the Chief is unable to assign an officer to accompany such construction vehicles or materials the Chief may, in his sole discretion, may authorize the use one or more constables or flag men in place of an officer or officers. Provided, however, that the Chief may waive the requirement to assign an officer if the owner, operator, or persons working in conjunction with construction vehicles, men, or temporarily depositing construction materials can demonstrate to the satisfaction of the Chief, that their activities will not cause an unnecessary impediment to the normal flow of traffic or be detrimental to the safety of vehicles or pedestrians.

The Chief may suspend such activities when, in his discretion, the activities violate 13.6, or cause an unnecessary impediment to the normal flow of traffic, or may be detrimental to the safety of vehicles or pedestrians.

### **13.7 One-way Traffic**

**One-Way.** Upon those roadways designated for one-way traffic, and sign posted for same, no driver shall proceed except in the direction indicated by such sign(s).

### **13.8 Operation of Vehicles**

(1) **Drive Within Marked Lanes.** When any roadway is divided into lanes, the driver of a vehicle shall so drive that the vehicle shall be entirely within a single lane, and he shall not move from the lane in which he is driving until he has first ascertained if such movement can be made with safety.

## ARTICLE 13 (13.8 cont.)

- (2) **Use Right Lane.** Upon all roadways the driver of a vehicle shall drive in the lane nearest the right side of the roadway when said lane is available for travel, except when overtaking another vehicle or when preparing for a left turn.
- (3) **Overtaking Other Vehicles.** The driver of any vehicle overtaking another vehicle proceeding in the same direction shall pass at a safe distance to the left thereof, and shall not cut in ahead of such other vehicle until safely clear of it.
- (4) **Overtake Only When There is a Space Ahead.** The driver of a vehicle shall not overtake and pass a vehicle proceeding in the same direction unless there is sufficient clear space ahead on the right side of the roadway to permit the overtaking to be completed without impeding the safe operation of any vehicle ahead or without causing the driver of any such vehicle to change his speed or alter his course, except as provided in 13.8(5).
- (5) **Vehicle Being Passed.** Subject to the provisions of M.G.L. c. 89, § 2, the driver of a vehicle when about to be overtaken and passed by another vehicle approaching from the rear shall give way to the right when practicable in favor of the overtaking vehicle, on suitable and visible signal being given by the driver of the overtaking vehicle, and shall not increase the speed of his vehicle until completely passed by the overtaking vehicle.
- (6) **Obstructing Traffic.**
- (a) No person shall drive in such a manner as to obstruct unnecessarily the normal movement of traffic upon any roadway. Officers are hereby authorized to require any driver who fails to comply with 13.8(6) to drive to the side of the roadway and wait until such traffic as has been delayed has passed.
- (b) Subject to the provisions of M.G.L. c. 89, § 11, no driver shall enter an intersection or a marked crosswalk unless there is sufficient space on the other side of the intersection or crosswalk and on the right half of the roadway to accommodate the vehicle he is operating without obstructing the passage of other vehicles or pedestrians, notwithstanding any traffic control signal indication to proceed.
- (7) **Following Too Closely.** The driver of a vehicle shall not follow another vehicle more closely than is reasonable and prudent, having due regard to the speed of such vehicle and the traffic upon and condition of the roadway.
- (8) **Slow Vehicles to Stay 200 Feet Apart.** Upon roadways less than 27 feet wide and upon which vehicular traffic is permitted to operate in both directions, the driver of any slow-moving commercial vehicle when traveling outside of a business or residential district shall not follow another slow-moving commercial vehicle within 200 feet, but this shall not be construed to prevent such slow-moving commercial vehicle from overtaking and passing another slow-moving commercial vehicle. 13.8(8) shall not apply to funerals or other lawful processions.
- (9) **Care in Starting, Stopping, Turning or Backing.** The driver of any vehicle before starting, stopping, turning from a direct line, or backing shall first see that such movement can be made in safety. If such movement cannot be made in safety or if it interferes unduly with the normal movement or other traffic, said driver shall wait for a more favorable opportunity to make such a movement. If the operation of another vehicle should be affected by a stopping or turning movement, the driver of such other vehicle shall be given a plainly visible signal, as required by M.G.L. c. 90, § 14B.
- (10) **Obedience to Traffic Control Signals.** Colors and arrow indications in traffic control signals shall have the commands ascribed to them in 13.8(10), and no other meanings, and every driver of a vehicle, railway car or other conveyance shall comply therewith, except when otherwise directed by an officer or by a lawful traffic regulating sign (other than a "stop" sign), signal or device or except as provided in 13.8 (24)(b).

In no case shall a driver enter or proceed through an intersection without due regard to the safety of other persons within the intersection, regardless of what indications may be given by traffic control signals.

- (a) **Green.** While the green lens is illuminated, drivers facing the signal may proceed through the intersection, but shall yield the right of way to pedestrians and vehicles lawfully within a crosswalk or the intersection at the time such a signal was exhibited. Drivers of vehicles making a right or left turn shall yield the right of way to pedestrians crossing with the flow of traffic.

## ARTICLE 13 (13.8 (10) cont.)

- (b) **Right, Left and Vertical Green Arrows.** When a right green arrow is illuminated, drivers facing said signal may turn right. When a left green arrow is illuminated, drivers facing said signal may turn left. When a vertical green arrow is illuminated, drivers facing said signal may go straight ahead. When a green arrow is exhibited together with a red or yellow lens, drivers may enter the intersection to make the movement permitted by the arrow, but shall yield the right of way to vehicles proceeding from another direction on a green indication, and to pedestrians legally within a marked crosswalk.
- (c) **Yellow.** While the yellow lens is illuminated, waiting drivers shall not proceed, and any driver approaching the intersection or a marked stop line shall stop at such point unless so close to the intersection that a stop cannot be made in safety; provided, however, that if a green arrow is illuminated at the same time drivers may enter the intersection to make the movement permitted by such arrow.
- (d) **Right and Left Yellow Arrows.** When yellow arrows are illuminated, drivers are warned that the related green movement is being terminated or that a red indication will be exhibited immediately thereafter when vehicular traffic shall not enter the intersection.
- (e) **Red.** While the red lens is illuminated, drivers facing the signal shall stop outside of the intersection or at such point as may be clearly marked by a sign or line; provided, however, that if a green arrow is illuminated at the same time drivers may enter the intersection to make the movement permitted by such arrow.
- (f) **Right and Left Red Arrows.** Vehicular traffic facing a steady red arrow signal shall not enter the intersection to make the movement indicated by the arrow and, unless entering the intersection to make a movement permitted by another signal, shall stop at a clearly marked stop line, but if none, before entering the crosswalk on the near side of the intersection, or if none, then before entering the intersection, and shall remain standing until an indication permitting the movement indicated by such red arrow shown. Except when a sign is in place prohibiting a turn, vehicular traffic facing any steady red signal may cautiously enter the intersection to turn right, or to turn left from a one-way street into a one-way street, after stopping.

Such vehicular traffic shall yield the right of way to pedestrians lawfully within an adjacent crosswalk and to other traffic lawfully using the intersection.

- (g) **Flashing Red (Stop Signal).** When a red lens is illuminated by rapid intermittent flashes, drivers of vehicles shall stop before entering the nearest crosswalk at an intersection or at a Stop line when marked, and the right to proceed shall be subject to provisions of M.G.L. c. 89, § 8.
  - (h) **Flashing Yellow (Caution Signal).** When a yellow lens is illuminated with rapid intermittent flashes, drivers of vehicles may proceed through the intersection or past such signal only with caution.
- (11) Lane - Direction - Control Signals.**
- (a) When lane-direction-control signals are placed over the individual lanes of a street or roadway, vehicular traffic may travel in any lane over which a green signal is shown, but shall not enter or travel in any lane over which a red signal is shown.
  - (b) **Meaning of Indications.** Lane direction control signal indications shall have the following meanings:
    1. **Downward-pointing illuminated green arrow.** A driver may operate a vehicle in the lane over which the arrow signal is located and illuminated.
    2. **Red illuminated symbol "x".** A driver shall not operate a vehicle in the lane over which the signal is located and illuminated, and that this indication shall modify accordingly the meaning of all other traffic controls present. The driver shall obey all other traffic controls and follow normal safe driving practices.
    3. **Steady Yellow illuminated symbol "x".** A driver should prepare to vacate, in a safe manner, the lane over which the signal is located because a lane control change is being made, and to avoid occupying that lane when a steady red x is displayed.
    4. **Flashing Yellow illuminated symbol "x".** A driver is permitted to use a lane over which the signal is located for a left turn. The driver is cautioned that he may be sharing that lane with opposite flow-left-turn vehicles.

## ARTICLE 13 (13.8 cont.)

**(12) Lane Control Signals.** When Traffic Control Signals are located and operated over or adjacent to the individual lanes of a street or roadway within an area designated as a Lane Traffic Control Area, vehicles shall be operated in obedience to the command given by the signal indication shown over or adjacent to the lane in which the vehicle is being operated.

A Lane Traffic Control Area is that portion of a roadway designated by Official Traffic Signs installed not less than 1000 feet in advance of Lane Traffic Control Signal installations.

**(13) Obedience to Isolated Stop Signs.** Except when directed to proceed by a police officer, authorized constable or flagman, every driver of a vehicle approaching a stop sign or a flashing red signal indication shall stop at a clearly marked stop line, but if none, before entering the crosswalk on the near side of the intersection, or, if none, then at the point nearest the intersecting roadway where the driver has a view of approaching traffic on the intersecting roadway before entering it. After having stopped, the driver shall yield the right of way to any vehicle in the intersection or approaching on another roadway so closely as to constitute an immediate hazard during the time when such driver is moving across or within the intersection or junction of roadways. 13.8 (13) shall not apply when the traffic is otherwise directed by an officer or by a lawful traffic-regulating sign, signal or device or as provided in 13.8 (24)(c).

**(14) Obedience to "Yield" Signs.** Every driver of a vehicle or other conveyance approaching an intersection of ways, where there exists facing him an official sign bearing the word "Yield", said sign having been erected in accordance with the written approval of the Department and such approval being in effect, shall surrender to oncoming traffic his right to enter the intersection until such time as he has brought his vehicle or other conveyance to a complete stop at a point between the said "Yield" sign and the nearer line of the street intersection, provided, however, that this requirement to stop before entering the intersection shall not apply when a driver approaching a "Yield" sign can enter the intersection in safety without causing interference to approaching traffic. 13.8 (14) shall not apply when the traffic is otherwise directed by an officer or by a lawful traffic regulating sign, signal or device or as provided in 13.8 (24)(c).

**(15) Sound Horn When Necessary.** The driver of a vehicle shall give an audible warning with his horn or other suitable warning device whenever necessary to insure safe operation.

**(16) Keep to the Right of Roadway Division.** Upon such public ways and roadways as are divided by a parkway, grass plot, reservation, viaduct, subway or by any structure or areas, drivers shall keep to the right of such division, and shall cross such parkway, grass plot or reservation only at a crossover. In the case of a roadway which has no crossovers, access to the adjoining roadway shall be gained only by the proper use of under or overpasses and ramps. The foregoing provisions shall not apply when drivers are otherwise directed by an officer, authorized constable or flagman, or official signs, signals or markings.

**(17) Operation at Under or Over Passes and at Intersections With Islands.** At any junction or crossing of ways where the roadway grades have been separated and where the ways are connected by ramps, and at any intersection of ways in which there are channelizing islands, drivers of vehicles shall proceed only as indicated by signs, signals or markings.

**(18) Driving on Road Surface Under Construction or Repair.** No operator shall enter upon the road surface of any roadway or section thereof when, by reason of construction, surface treatment, maintenance or the like, or because of some unprotected hazard, such road surface is closed to travel, and one or more signs, lights or signals have been erected to indicate that all or part of the road surface of the roadway is not to be used, or when so advised by an officer, authorized constable, flagman, watchman, member of a highway department crew or employee of the Department, either audibly or by signals.

**(19) No Driving on Sidewalks.** The driver of a vehicle shall not drive upon any sidewalk except at a permanent or temporary driveway.

**(20) Emerging from Alley or Private Driveway.** The driver of a vehicle emerging from a private road, parking lot, driveway or garage shall stop such vehicle immediately prior to driving upon the sidewalk area extending across such private road, parking lot, driveway or garage, and where no such sidewalk exists the stop shall be made at the building or property line as the case may be and upon entering the roadway shall yield the right of way to vehicles approaching on the roadway.

## ARTICLE 13 (13.8 cont.)

**(21) Certain Turns Prohibited.** The driver of a vehicle or other conveyance shall not make a turn from the way in which he is driving into another way or driveway, at any point in the roadway, where such a movement is prohibited by signs.

**(22) Driving or Parking on Channelizing Island.** No person shall drive over or park a motor vehicle upon any traffic island or channelizing island unless directed to do so by a police officer.

**(23) Obedience to Traffic Signs, Signals and Markings.** The driver of any vehicle or of any street car shall obey the instructions of any official traffic control sign, signal, device, marking or legend unless otherwise directed by a police officer.

**(24) Rights and Duties of Drivers in Funerals or Other Processions.**

- (a) It shall be the duty of each driver in a funeral or other procession to keep as near to the right edge of the roadway as is feasible and to follow the vehicle ahead as closely as practicable and safe.
- (b) At an intersection where a traffic control signal is operating the driver of the first vehicle in a funeral or other procession shall be the only one required to stop for a red or red and yellow indication.
- (c) At an intersection where a lawful isolated stop sign or signal exists, the driver of the first vehicle in a funeral or other procession shall be the only one required to stop before proceeding through the intersection.

**(25) Men and Equipment in Roadway.** Whenever traffic signs are erected or warning lights are displayed in or adjacent to a roadway to notify of the presence of men and equipment, in such roadway every motorist shall regulate the speed of his vehicle in a manner and to a degree consistent with the particular condition.

**(26) U Turns Prohibited.** No operator shall back or turn a vehicle so as to proceed in a direction opposite to that in which said vehicle is headed or traveling wherever signs notifying of such a restriction have been erected.

**(27) Vehicle Operation at Crosswalks.**

- (a) Subject to the provisions of M.G.L. c. 89, § 11, when traffic control signals are not in place or not in operation the driver of a vehicle, which for the purposes of 13.8 shall include bicycles, mopeds and scooters, shall yield the right of way, slowing down or stopping if need be so to yield, to a pedestrian crossing the roadway within a marked crosswalk when the pedestrian is upon the half of the roadway upon which the vehicle is traveling or when the pedestrian approaches from the opposite half of the roadway to within five feet of that half of the roadway upon which the vehicle is traveling.
- (b) Subject to the provisions of M.G.L. c. 89, § 11, no operator of a vehicle shall pass any other vehicle which has been stopped at a marked crosswalk to permit a pedestrian to cross a way, nor shall any operator enter a marked crosswalk until there is sufficient space on the other side of the crosswalk to accommodate the vehicle he is operating notwithstanding any traffic control signal indication to proceed.

**(28) Operators to Exercise Due Care.** The provisions of 13.8 shall in no way abrogate the provisions of M.G.L. c 90, § 14 and 14A which provide: "Precautions for Safety of Other Travelers" and for the "Protection of Blind Persons Crossing Ways", Furthermore, notwithstanding the provisions of Article 13 every operator of a vehicle shall exercise due care to avoid colliding with any pedestrian upon the roadway and shall give warning by sounding the horn when necessary and shall exercise proper precautions which may become necessary for safe operation.

### **13.9 Exemptions and Penalties**

- (1) **Exemptions.** The provisions of 13.8 shall not apply to persons acting in conformity with the direction of an officer or , to persons or drivers actually engaged in work upon a roadway closed to travel or under construction or repair, provided, however such work is in accordance with 13.5, when the nature of their work necessitates a departure from any part of Article 13, to officers when engaged in the performance of public duties which necessitates a departure from any part of Article 13, nor to drivers of emergency vehicles while operating in an emergency and in performance of public duties which necessitate a departure from any part of Article 13, or to drivers of emergency vehicles while operating in an emergency and in performance of public duties which necessitate a departure from any part of Article 13. These exemptions shall not, however, protect the driver of any vehicle from the consequence of a reckless disregard of the safety of others.

## ARTICLE 13 (13.9 cont.)

**(2) Owner Prima Facie Responsible for Violations.** If any vehicle is found upon any roadway in violation of any provision of Article 13 et seq. and orders and the identity of the driver cannot be determined, the owner or the person in whose name such a vehicle is registered shall be held prima facie responsible for such violations.

**(3) Obedience to Police.** No person shall willfully fail or refuse to comply with any lawful order or direction of a police officer, authorized constable or flagman, in regard to the direction, control or regulation of traffic. Any person acting in conformity with any such order or direction shall be relieved from the observance of any provision of Article 13 et seq. with which the order or direction may conflict.

**(4) Obedience to Signs, etc.** No person shall disobey the instructions of any official sign, signal, marking or marker.

**(5) Penalties.** Any person convicted of a parking violation of any provision of 13.3 or 13.4 shall be punished as provided in M.G.L. c. 90, § 20A. The Board of Selectmen, pursuant to said statute, shall from time to time, establish by rule or regulation a schedule of fines for violations subject to this by-law. Police officers or other persons so authorized by the Board of Selectmen may enforce said parking regulations.

Any person convicted of a violation of any provision of 13.6 shall be punished by a fine of two hundred dollars. Police officers are authorized to enforce said provisions and violations may be processed in accordance with M.G.L. c. 40, § 21D.

Any person convicted of a violation of any other rule made hereunder shall be punished by a fine of fifty dollars for each offense. A police officer may issue a citation in accordance with the provisions of M.G.L. c. 85, § 10.

### **13.10 Handicapped and Veteran Parking By-Law** STM-10/23/1995

Designated parking spaces for vehicles either owned and operated by disabled veterans or by handicapped persons and bearing the distinctive number plates authorized by section two of chapter ninety, or for vehicles transporting handicapped persons and displaying the special parking identification plate authorized by said section two of said chapter ninety, or for vehicles bearing the official identification of a handicapped person issued by any other state or any Canadian Province shall be provided in public and private off-street parking areas.

- (a) Any person or body that has lawful control of a public or private way or of improved or enclosed property used as off-street parking areas for businesses, shopping malls, theaters, auditoriums, sporting or recreational facilities, cultural centers, residential dwellings, or for any other place where the public has a right of access as invitees or licensees, shall reserve parking spaces in said off-street parking areas for any vehicle owned and operated by a disabled veteran or handicapped person whose vehicle bears the distinguishing license plate authorized by said section two of said chapter ninety or for any vehicle transporting a handicapped person and displaying the special identification plate authorized by section two of chapter ninety or for any vehicle bearing the official identification of a handicapped person issued by any other state or any Canadian Province, according to the following formula:

If the number of parking spaces in any such areas is more than fifteen but not more than twenty-five, one parking space; more than twenty-five but not more than forty, five percent of such spaces but not less than two; more than forty but not more than one hundred, four percent of such spaces but not less than three; more than one hundred but not more than two hundred, three percent of such spaces but not less than four; more than two hundred but not more than five hundred, two percent of such spaces but not less than six; more than five hundred but not more than one thousand, one and one-half percent of such spaces but not less than ten; more than one thousand but not more than two thousand, one percent of such spaces but not less than fifteen; more than two thousand but less than five thousand, three-fourths of one percent of such spaces but not less than twenty; and more than five thousand, one-half of one percent of such spaces but not less than thirty.

- (b) Parking spaces designated as reserved under the provisions of paragraph (a) shall be identified by the use of above grade signs with white lettering against a blue background and shall bear the words "Handicapped, Parking: Special Plate Required. Unauthorized Vehicles May be Removed at Owner's Expense"; shall be as near as possible to a building entrance or walkway; shall be adjacent to curb ramps or other unobstructed methods permitting sidewalk access to a handicapped person; and shall be twelve feet wide and two eight-foot wide areas with four feet of cross hatch between them.

## **ARTICLE 13 (13.10b cont.)**

The leaving of unauthorized vehicles within parking spaces designated for use by disabled veterans or handicapped persons or in such a manner as to obstruct a curb ramp designated for use by handicapped persons as a means of egress to a street or public way is hereby prohibited.

The penalty for any violation hereunder shall be fifty (\$50.00) dollars for the first offense, and one hundred (\$100.00) dollars for the second and any subsequent offense.

### **13.11 Possession of Open Containers of Alcohol** *ATM 05/01/1989, ATM 11/7/2005 re-codified*

No person shall drink any alcoholic beverages or possess any open container(s) thereof as defined in Chapter 138, Section 1 of the Mass. General Laws while in or upon any public way or any way to which the public has a right of access, or any park or playground, except any areas and functions duly authorized by the Board of Selectmen; nor shall any person so drink, or possess any open container(s) thereof, any alcoholic beverages while in or upon private land, without the consent of the owner or person or persons in control thereof. Any person violation this by-law shall be fined not more than Fifty (\$50.00) dollars for each offense.

### **13.12 Consumption of Alcoholic Beverages in Unlicensed Food Establishments**

*STM 01/25/1993, ATM 11/7/2005 re-codified*

Notwithstanding the above provisions of Section 13.11, no person shall drink any alcoholic beverages or possess any open containers thereof as defined in Mass. General Laws, Chapter 138, while in or upon any premises licensed by the Town as a common victualer for the sale or serving of non-alcoholic beverages and food unless the premises are also licensed by the Town to sell or dispense such alcoholic beverages under the provisions of Mass. General Laws, Chapter 138.

### **13.13 Public Consumption Or Use Of Marijuana Or Tetrahydrocannabinol** *STM 06/01/09*

**A.** No person, whether in or upon a vehicle, motor vehicle, conveyance, or on foot, shall burn, smoke, ingest, or otherwise use or consume marijuana or tetrahydrocannabinol (as defined in G.L. c. 94C, § 1, as amended) while in or upon any area owned by or under the control of the Town, including but not limited to, any street, sidewalk, public way, footway, passageway, stairs, bridge, park, playground, beach, recreation area, boat landing, public building, school, school grounds, cemetery, or parking lot; or in or upon any place to which the public has a right of access as invitees or licensees.

**B.** Any marijuana or tetrahydrocannabinol burned, smoked, ingested, or otherwise used or consumed in violation of this bylaw shall be seized, held, and disposed of in accordance with G.L. c. 94C, § 47A.

**C.** Whoever is found in violation of this bylaw shall, when requested by an official authorized to enforce this bylaw, state his true name and address to said official.

**D.** This bylaw may be enforced through any lawful means in law or in equity including, but not limited to, enforcement by criminal indictment or complaint pursuant to G.L. c. 40, § 21, or by non-criminal disposition pursuant to G.L. c. 40, § 21D, by the Board of Selectmen, the Town Administrator, or their duly authorized agents, or any police officer.

**E.** The fine for a violation of this bylaw shall be Three Hundred (\$300.00) Dollars for each offense. A penalty imposed under this bylaw shall be in addition to any civil penalty imposed under G.L. c. 94C, § 32L.

## **ARTICLE 14**

### **RECREATIONAL FACILITIES** *ATM 5/3/2004*

#### **14.1 Duties**

The Board of Park Commissioners (hereinafter referred to as "Board") shall have and exercise all the powers and duties conferred upon park commissioners in towns; the powers and duties of playground commissioners appointed under authority of M.G.L.A c.45, § 14; It shall be responsible for regulating the use of all Recreational Facilities located in the Town of Freetown and shall have the authority to promulgate rules and regulations with regard thereto. "Recreational Facilities" shall include parks, greens, playgrounds, ball fields, and beaches together with the improved and enclosed land, buildings, beach area, and parking lots owned or controlled by the Town. The Board is authorized to appoint such assistants as may be necessary to assist it in promoting recreational facilities and to perform such other duties that may be required.

## **ARTICLE 14 (cont.)**

### **14.2 Admittance**

Maximum limits as to the number of users of a Recreational Facility may be established by the Board. Admittance to given areas may be suspended temporarily and/or evacuation may be directed when these limits are reached, or exceeded, or when at the discretion of the Board, it is determined that further public use of the facility is hazardous due to weather, construction, crowds, water quality, or other situations involving public health, safety or welfare.

### **14.3 Hours of Operation**

Unless otherwise provided by the Board, and posted to the contrary, Recreational Facilities shall be closed to the public between the hours of 9:00 PM to 6:00AM. The Board may from time to time require users of recreational facilities to seek permits therefor, and may establish by regulation the fees, terms, and conditions for the issuance of such permits.

### **14.4 Violations/Enforcement**

- 1) Any person who by his or her actions violates any provision of this bylaw or the regulations adopted hereunder, or who fails to comply with any reasonable request of a duly authorized employee of the Town of Freetown to comply with such bylaw or regulations, may be punished by a fine of not more than Fifty (\$50.00) Dollars for each offense.
- 2) Any person who by his or her actions violates any provision of this By-Law or the regulations adopted hereunder, or who fails to comply with any reasonable request of a duly authorized employee of the Town of Freetown to comply with such By-Law or regulations may also be evicted forthwith from a Recreational Facility; or, for a period of time to be determined by the Board of Park Commissioners, denied admittance to, and/or suspended from use of, a Recreational Facility.
- 3) The provisions of this By-Law, and any regulations adopted hereunder may be enforced through any means available in law or in equity, including non-criminal disposition pursuant to G.L. c.40, s.21D, and Article 25, Section 25.3 of the General By-Laws. The enforcing person for purposes of non-criminal disposition shall be the Board of Park Commissioners or its designee, the Town Administrator, or any police officer of the Town of Freetown. Each day a violation exists shall constitute a separate violation. For the purposes of non-criminal disposition, the following fines shall apply:
  - First Offense: \$ 25.00;
  - Second Offense: \$ 50.00;
  - Third and Subsequent Offenses: \$ 75.00.

### **14.5 Severability**

If any provision of this By-law and rule or regulations promulgated in accordance with this by-law, or application thereof is held to be invalid, such invalidity shall not affect any provision of the rules and regulations not specifically held to be invalid.

## **ARTICLE 15**

### **PUBLIC PEACE AND SAFETY** *STM 10/26/00, ATM 5/6/02*

The purpose of this article is to prohibit certain conduct that is harmful to the health, safety, and welfare of the community. Nothing herein is meant to limit constitutional rights under the federal or state constitution.

#### **15.1 Public Indecency**

- 1) A person is guilty of indecency if, while in a public place where he or she may reasonably be expected to be viewed by others, he or she:
  - a) engages in sexual intercourse
  - b) engages in deviate sexual intercourse; or
  - c) fondles the genitals of himself, herself or another person commits Public Indecency.

## ARTICLE 15 (15.1 cont.)

- 2) “Nudity” means the showing of human male or female genital (sic), pubic area or buttocks with less than a fully opaque covering; the showing of the female breast with less than a fully opaque covering of any part of the nipple; the exposure of any device, costume, or covering which gives the appearance of or simulates the genitals, pubic hair, natal cleft, perineum anal region or pubic hair region; or the exposure of any device worn as a cover over the nipples and/or areola of the female breast, which device simulates and gives the realistic appearance of nipples and/or areola.
- 3) “Public Place” includes all outdoor places owned by or open to the general public, and all buildings and enclosed places owned by or open to the general public, including such places of entertainment, taverns, restaurants, clubs, theaters, dance halls, banquet halls, party rooms or halls limited to specific members, restricted to adults or to patrons invited to attend, whether or not an admission charge is levied.
- 4) Deleted *ATM 5/6/02*
- 5) Construction and Severability – It is the intention of the Town of Freetown that the provisions of this bylaw be construed, enforced and interpreted in such a manner as will cause the least possible infringement of the constitutional rights of free speech, free expression, due process, equal protection or other fundamental rights consistent with the purposes of this ordinance. Should a court of competent jurisdiction determine that any part of this bylaw, or any application or enforcement of its is excessively restrictive of such rights or liberties, then such portion of the bylaw, or specific application of the bylaw, shall be severed from the remainder, which shall continue in full force and effect.

## ARTICLE 16

### FALSE ALARM BY-LAW *ATM 5/4/92, STM 06/01/09*

#### 16.1 Intent

The intent and purpose of this by-law is to promote the health, safety, welfare, and convenience of the community by regulating the use of alarm systems in the Town and to further regulate and control the emanation of false alarms therefrom.

#### 16.2 Definitions

For the purposes of this section, the following terms, unless a different meaning is clearly apparent from the language or context, shall have the following meanings:

**Alarm** - An indication of danger emanating from an “alarm system”. The emanating signal may be audible, visual, or by electrical activation of remote devices.

**Alarm System** – Any configuration of electrical and/or mechanical or other devices and equipment designed and/or intended to detect hazardous conditions and to produce an “alarm”.

**Burglar Alarm** – An “alarm” which indicates an unlawful intrusion into a building or upon a property.

**False Alarm** – An alarm which is emitted from an “alarm system” and which results in the response of police and/or fire department personnel and equipment to the alarm location when there does not exist the hazardous condition which the alarm system is intended to detect and there is no valid cause or reason for the alarm to have been activated, and includes an alarm caused by equipment failure or malfunction, improper installation, negligent operation or intentional manual activation. No alarm shall be considered a false alarm if it were caused by an act of God, including, but not limited to, power failures, storms, earthquakes, or other uncontrollable circumstance.

**Fire Alarm** – An “alarm” which indicates the presence of uncontrolled fire within a building or upon a property.

## ARTICLE 16 (16.3 cont.)

- 16.3** Whenever three (3) or more false alarms from an alarm system are caused within a calendar year, the owner(s) or person(s) in control of said alarm system shall be subject to a fine for each and every occurrence starting with the third false alarm.
- 16.4** Every alarm system installed subsequent to the effective date of this By-law which is equipped with an audible signaling apparatus shall also be equipped with an automatic shut-off device which will de-activate audible component of the system within fifteen (15) minutes of activation. Every previously installed alarm system with audible signaling shall be modified by the addition of such an automatic shut-off device within one (1) year of the effective date of this By-law. Violation of these requirements shall subject the owner(s) of the property to a fine.
- Every false alarm which results in the activation of an audible signaling apparatus which fails to de-activate within fifteen (15) minutes shall subject the owner(s) of the offending alarm system to a fine.
- 16.5** The violation of any Rule or Regulation made by the Board of Selectmen relative to the installation, operation, or registration of "Alarm Systems" shall be subject to a fine.
- 16.6** For violations related to alarms originating from a residential property, the fine shall be twenty-five (\$25.00) Dollars for each offense, and for those originating from commercial or institutional property, the fine shall be Fifty (\$50.00) Dollars for each offense.

## ARTICLE 17

### DOG LICENSING, CONTROL AND REGULATIONS

*ATM- 6/21/93, ATM 5/06/04,  
STM 11/20/06*

#### **17.1 Definitions:**

As used in this section the following terms mean:

**At Large** - Any dog shall be deemed to be at large when he is off the property of his owner and not under control of a competent person.

**Dog Fund** – The fees, fines, and reimbursements collected in connection with the licensing of dogs and the enforcement of this by-law.

**Dog Officer** – Officer(s) annually appointed by the Selectmen on July first to enforce the laws relating to dogs.

**Dog Pound** – Any premises designated by the Selectmen of the Town for the purpose of impounding and caring for all animals found running at large in violation of this by-law.

**Kennel** – One pack or collection of dogs on a single premises, whether maintained for breeding, boarding, sale, training, hunting or other purposes and including any shop where dogs are on sale, and also including every pack or collection of more than three dogs six months old or over, owned or kept by a person on a single premises irrespective of the purposes for which they are maintained.

**Kennel Licenses**- Every person maintaining a kennel shall have a kennel license. Any owner or keeper of less than four dogs six months old or over who does not maintain a kennel may elect to secure a kennel license in lieu of licensing such dogs under Section 17.2A and during such time as he does not license such dogs there under shall have a kennel license and shall be subject to this section and all sections which shall apply to kennels as though he were maintaining a kennel. Kennel licenses under this section shall be issued by the Town Clerk.

## ARTICLE 17 (17.1 cont.)

**Licensing Period** – The time in between April first and the following March thirty-first, both dates inclusive.

**Live Stock or Fowls** – Animals or fowls kept or propagated by the owner for food or as a means of livelihood; also deer, elk, cottontail rabbits and northern hares, pheasants, quail, partridge and other birds and quadrupeds determined by the department of fisheries, wildlife and environmental law enforcement to be wild and kept by, or under a permit from, said department in proper houses or suitable closed yards. This shall not include dogs, cats and other pets.

**Owner**- Any person, group or persons, or corporation owning, keeping or harboring a dog or dogs.

**Restraint**- A dog shall be deemed under restraint within the meaning of these by-laws if it is on a leash or other type of permanent physical control or controlled by a competent person and obedient to that person's commands, on or within a vehicle being driven or parked on the streets, or within the property limits of its owner or keeper.

### 17.2 Licenses

- A. Any person who at the commencement of the license period, or who during any license period becomes, the owner or keeper of a dog six months old or over which is not duly licensed, shall cause it to be duly registered, numbered, described, and licensed until the end of such license period. In order to own or keep such dog after the beginning of the succeeding license period shall, before the beginning thereof, cause it to be registered, numbered, described, and licensed for such license period. Registration, numbering, description, and licensing shall be with the office of the Town Clerk.
- 1) Effective with the issuance of the 2007 Dog Licenses, no fee shall be charged for a Dog License to any resident who is 70 years of age or over. This exemption will be limited to one dog license and will exclude kennels.
- B. **Kennel Licenses**- Every person maintaining a kennel shall have a kennel license providing, however, it does not violate the provisions of any town by-laws. Kennel licenses under this section shall be issued by the Town Clerk. Such license shall be in lieu of any other license for any dog while kept at such kennel during any portion of the period for which such kennel license is issued. The holder of a license for a kennel shall cause each dog kept therein to wear, while it is at large, a collar or harness of leather or other suitable material, to which shall be securely attached a tag upon which shall appear the number of such kennel license and the year of issue. Such tags shall be furnished to such owner or keeper by the Town Clerk.
- C. **Kennel Licenses/Tags/Certificates**- Every holder of a kennel license, upon delivering an unlicensed dog to a purchaser or to any other person, shall attach to such dog a collar or harness which shall carry a tag marked with the name and address of such kennel licensee, and a number which shall be properly recorded on the records of such licensee, and shall also furnish to the persons to whom the dog is delivered a certificate bearing the same number and a description of the dog. Such certificate shall bear the date of purchase, exchange or gift and, with the tag, shall, for a period of two weeks following such date, be a legal substitute for a license. The purchaser or other recipient of a dog shall, within two weeks of the purchase or receipt of such dog, either return the same to the licensee from whom it was received, together with the collar or harness, tag and certificate, or return to such licensee said tag, and a certificate signed by the Town Clerk certifying that the dog has been licensed in the name of such purchaser or recipient or of some other person. If any such purchaser or recipient fails to comply with the preceding sentence, such licensee shall notify the Town Clerk of the purchase, exchange or gift of such dog, and shall furnish to such Town Clerk the date thereof, and the name and address of the purchaser or recipient.
- D. **Kennel Licenses – Inspection of Kennels** – The Freetown Dog Officer, the Assistant Dog Officer, the Police Chief, the Board of Selectmen, the Board of Health Agent or any Police Officer authorized by any of said officials may at any time inspect or cause to be inspected any kennel and if, in their or his judgment, the same is not being maintained in a sanitary and humane manner, or if records are not properly kept as required by law, the Freetown Dog Officer and the Board of Selectmen shall by order revoke or suspend, and in case of suspension, may reinstate such license. Upon the petition of twenty-five citizens,

## **ARTICLE 17 (17.2 cont.)**

filed with the Board of Selectmen, setting forth that they are aggrieved, or annoyed to any unreasonable extent, by one or more dogs at kennel because of the excessive barking or vicious disposition of said dogs or other conditions connected with such kennel constituting a public nuisance, said Board of Selectmen within seven days after the filing of such petition, shall give notice to all parties of interest of a public hearing to be held within fourteen days after the date of such notice. Within seven days after such public hearing, the Board of Selectmen shall make an order either revoking or suspending such kennel license or otherwise regulating said kennel, or dismissing said petition.

### **17.3 Rabies**

- A. Every license issued to the owner of a dog shall have a description of the symptoms of rabies printed thereon.
- B. Vaccination of Dogs Against Rabies – Whoever is the owner or keeper of a dog six months of age or older shall cause such dog to be vaccinated against rabies by a licensed veterinarian. Such owner or keeper shall procure a veterinarian's certificate that such dog has been so vaccinated and setting forth the date of such vaccination and the duration of immunity, or a notarized letter from a veterinarian that a certificate was used, or a metal rabies tag bearing an expiration date indicating that such certification is still in effect in order to obtain a license(s).

### **17.4 Fees**

The Board of Selectmen shall from time to time review and set any applicable fees for the registration, numbering, description, and licensing of dogs, demand fees for unregistered dogs, for loss due to damages by dogs, for expenses related to appraisal of such losses and for maintenance fees and reclaiming fees applicable to impounded dogs or any similar fee connected with these by-laws. Any fees or fines collected pursuant to this by-law shall be paid into the Town Treasury, along with any interest accrued. *STM 2/7/94, ATM 5/3/04*

### **17.5 Restraint**

No person owning or harboring a dog shall suffer or allow it to run at large in any of the streets or public places in the Town of Freetown or allow it upon the premises of anyone other than the owner or keeper of such dog without the permission of the owner or occupant of such premises. No dog shall be permitted in any street or public place within the Town of Freetown unless it is effectively restrained as above defined by a chain or leash not exceeding seven (7) feet.

### **17.6 Impoundment** *STM 2/7/94*

Any dog or dogs, found running at large if approachable and can be caught shall be taken up by the Dog Officer and impounded in the shelter designated as the Town Dog Pound, and there confined in a humane manner for a period of the number of days that the State mandates and may thereafter be disposed of in a humane manner if not claimed by their owners. Dogs not claimed by their owners before the expiration of the number of days that the State mandates may be disposed of at the discretion of the dog officer, except as hereinafter provided in the case of certain dogs.

- A. Immediately upon impounding dogs or other animals, the dog officer shall make every possible reasonable effort to identify the owners of such dogs or other animals, so impounded and shall notify such owners within 48 hours of the conditions whereby they may regain custody of such animals.
- B. Any dog determined by the dog officer to be fierce, dangerous, or vicious shall not be redeemed unless the owner thereof shall agree to confine the dog within a building or secure enclosure that is approved by the Dog Officer.

### **17.7 Redemption of Impounded Animals**

The owner shall be entitled to resume possession of any impounded dog except as hereinafter provided in the cases of certain dogs on payment of reclaiming fees and maintenance fees adopted by the Board of Selectmen for each day or part thereof, of the dog's impoundment, payment to the dog officer, which shall be paid into the Town Treasury.

Any animal impounded under the provisions of these regulations and not reclaimed by its owner within ten (10) days, may be humanely destroyed by the dog officer, or placed in custody of some person deemed to be a responsible and suitable owner, who will agree to comply with the provisions of these regulations and such other regulations as shall be fixed by the Town of Freetown.

## **ARTICLE 17 (cont.)**

### **17.8 Warrant – Unlicensed Dogs**

The Selectmen shall annually within ten days after July 1<sup>st</sup> issue a warrant to the Dog Officer or officers directing him or them to seek out, catch and confine all dogs within the town which then have not been licensed, collared or harnessed, and tagged as required by said by-law.

### **17.9 Emergency Treatment of Dogs and Cats on Public Ways**

Any registered veterinarian who renders emergency care of treatment to, or disposes of, a dog or cat that is injured on any way, shall receive payment from the owner of such dog or cat, if known, or if not known, from the Town of Freetown Dog Fund in an amount not to exceed twenty dollars for such care, treatment or disposal; provided, however, such emergency care, treatment or disposal shall be for the purpose of maintaining life, stabilizing the animal or alleviating suffering until the owner or keeper of such dog or cat is identified or for a period of twenty-four hours, whichever is sooner. Any veterinarian who renders such emergency care or treatment to, or disposes of, such dog or cat shall notify the Freetown dog officer and, upon notification, such dog officer shall assume control of such dog or cat.

### **17.10 Killing of Certain Dogs**

If the dog deemed to be at large is determined by the Dog Officer to be dangerous, or worrying persons, or worrying animals, or a treat to private property, or is otherwise unapproachable, it will be executed by the Dog Officer or a duly appointed Police Officer.

### **17.11 Damage to Live Stock and Fowls**

- A. The Board of Selectmen or their authorized agents thereto authorized in writing, may, after written notice to the owner or keeper, enter upon the premises of the owner or keeper of any dog known to them to have worried or killed live stock or fowls, and then and there kill such dog unless such owner or keeper whose premises are thus entered for the said purpose shall give a bond in the sum of two hundred dollars, with sufficient sureties, approved by the Board of Selectmen, conditioned that the dog shall be restrained for twelve months ensuing. And if the owner or keeper of the dog declares his intention to give such a bond, said Selectmen, Chief of Police or his or their agents, shall allow him seven days, exclusive of Sundays and holidays, in which to procure and prepare the same and to present it to them, or to file with the Freetown Town Clerk.
  
- B. Whoever suffers loss by the worrying, maiming or killing of his live stock or fowls by dogs, outside the premises of the owners or keepers of such dogs, may, inform the Freetown Police Department, who shall be designated by the Board of Selectmen to receive such information, and, if the damage is done in the Town, may notify the Chairman of the Board of Selectmen, or if he/she is absent or ill, any one of the Selectmen, who shall proceed to the premises where the damage was done and determine whether the same was inflicted by dogs, and if so, appraise the amount thereof if it does not exceed fifty (\$50.) dollars. If in the opinion of said police officer, Chairman or Selectman, the amount of said damage exceeds fifty dollars, the damage shall be appraised, on oath, by three persons, of whom one shall be such police officer, Chairman or Selectman, one shall be appointed by the person alleged to be damaged, and the third shall be appointed by the other two. The said appraisers shall consider and include in such damages the labor and time necessarily expended in the finding and collecting of the live stock or fowls injured or separated and the value of those lost or otherwise damaged by dogs. The police officer, Chairman or Selectman shall return a certificate of damages to the Town Treasurer within ten days after such appraisal is made. The Town Treasurer, within thirty days shall examine all bills for damages, and may upon request of an interested party, summon the appraisers and all parties interested and make such investigation as they may deem proper, and shall issue an order upon the Town Treasurer for such amounts, if any, as they decide to be just and shall notify all interested parties of their decision. The Town Treasurer shall pay all orders drawn upon him in full, for the above purpose, in accordance with the reimbursement schedule as determined by the Board of Selectmen from time to time, and for the expenses of appraisal out of the money in the Dog Fund. All appraisers shall receive from the Dog Fund a sum of money as provided under Section 17.4.

## ARTICLE 17 (17.11 cont.)

- C. No owner of live stock or fowls shall be reimbursed for damages, as provided under Section 17.4, inflicted by his own dog or dogs, nor shall he be reimbursed for any damage by any dog if, at the time such damage was inflicted, he was himself the owner or keeper of an unlicensed dog of the age of six months or older. No reimbursement shall be made on account of damages by a dog to deer, elk, cottontail rabbits, northern hares, pheasants, quail, partridge and other live stock or fowls determined by the Department of Fisheries, Wildlife and Environmental Law Enforcement to be wild unless they are kept by, or under permit from, said Department, nor unless they shall be kept in proper houses or in suitable enclosed yards. No reimbursement shall be made for damage by a dog to dogs, cats and other pets. Awards shall in no case exceed the fair cash market value of such live stock or fowls.

### **17.12 Hunting Dogs** STM 2/13/89

No leash or physical restraint shall be necessary if a dog is with his owner or keeper when said owner or keeper is hunting, providing that the dog is obedient to that person's commands. No person or persons may hunt game with more than six (6) dogs. The Board of Selectmen upon application may exempt sporting events from the provisions of this section.

### **17.13 Interference**

No person shall interfere with, hinder or molest the dog officer of this Town in the performance of his duties, or seek to release any animal in the custody of the dog officer, except as herein provided.

### **17.14 Records**

- A. It shall be the duty of the dog officer to keep, or cause to be kept, accurate and detailed records of the impoundment and disposition of all animals coming into his custody.
- B. It shall be the duty of the dog officer to keep, or cause to be kept accurate and detailed records of all bite cases reported to him and his investigation of the same.

### **17.15 Enforcement**

The provisions of this by-law shall be enforced by the Dog Officer of the Town of Freetown and may be enforced by any Police Officer of said Town.

### **17.16 Killing of Dogs for Humane Purposes**

When, in the judgement of the dog officer or any police officer, in this Town, an animal should be destroyed for humane reasons, such animal may not be reclaimed and may be destroyed by the Dog Officer or Police Officer.

### **17.17 Dogs on School Property: Complaints Made to Dog Officer**

No dogs are allowed in school yards or on school property when school is in session or being used for school activities, whether at large or under restraint, seeing-eye dogs, so-called excepted.

- A. Notwithstanding the provisions of Section 17.12, dogs under the control and restraint of any police or law enforcement officer or school authorities may be allowed on school property for official purposes such as, but not limited to, bomb or drug searches, lectures, animal studies, etc.
- B. All complaints made under the provisions of this Section shall be made to the Dog Officer. Complaints may be made orally, provided, however, that such complaint is within forty-eight hours, reduces to writing and shall be signed by the complainant showing his address and telephone number, if any.

### **17.18 Right of Entry**

In the discharge of the duties imposed by the by-laws, the Dog Officer or any Police Officer of this Town shall have the authority at all reasonable times to enter upon any premises, but such authority should not include the right to enter any residence on such premises to examine a dog or other animal which is allegedly in violation of a provision of these by-laws.

Such officer shall have the further authority to take possession of any such dog or other animal and remove it from such premises.

## ARTICLE 17 (17.18 cont.)

- A. Dogs on Beach and Recreation Areas: No dogs shall be allowed on Beach and Recreation Areas, owned or under the control of the Town of Freetown or any Boards or Commissions thereof, during the six months of May through October inclusive, whether at large or under restraint. Seeing-eye dogs and dogs owned or under the control of the Police or any Law Enforcement Officer shall be excepted from these provisions.

### **17.19 Abandonment of Dogs or Other Animals**

It shall be unlawful to abandon dogs or their animals within the Town Limits.

It shall be unlawful to allow or permit any dog to trespass on private or public property so as to damage or destroy any property or thing of value and the same is hereby declared to be a nuisance and any such dog may be impounded by any Police Officer. Whenever it shall be affirmed in writing by three or more persons residing in or regularly employed in the neighborhood that any dog is a habitual nuisance by reason of trespassing, howling, barking or other noise, or damage to property, being vicious or by its actions potentially vicious or in any other manner causing undue annoyance, any police officer, if he finds such nuisance to exist, shall serve notice upon the owner or custodian that such nuisance must be abated.

### **17.20 Penalty** *STM 2/13/89, ATM 5/1/89, ATM 6/21/93*

Except as otherwise provided herein, any person convicted of violating any provision of these by-laws may be punished by the payment of a fine of fifty (\$50.00) dollars to be recovered for the use of the Town and if such violation be continued, each day's violation may constitute a separate offense. The provisions and procedures in Mass. General Laws Chapter 140, §173A shall be followed and apply to violation of these by-laws.

## **ARTICLE 18**

### **CAT LICENSING, CONTROL AND REGULATIONS** *STM – 10/23/1995, ATM- 6/1/09*

#### **18.1 Licenses**

- A. Deleted
- B. **Cattery Licenses** – Every person maintaining a cattery shall have a cattery license providing, however, it does not violate the provisions of any town by-laws. Cattery licenses under this section shall be issued by the Town Clerk. Such license shall be in lieu of any other license for any cat while kept at such cattery during any portion of the period for which shall cat license is issued. The holder of a license for a cattery shall cause each cat kept therein to wear, while it is at large, a tag upon which shall appear the number of such cattery license and the year of issue. Such tags shall be furnished to such owner or keeper by the Town Clerk.
- C. **Cattery Licenses – Inspection of Cattery** – The Freetown Dog Officer, the Assistant Dog Officer, the Police Chief, the Board of Selectmen, the Board of Health Agent or any Police Officer authorized by any of said officials may at any time inspect or cause to be inspected any cattery and if, in their or his judgement, the same is not being maintained in a sanitary and humane manner, or if records are not properly kept as required by law, the Freetown Dog Officer and the Board of Selectmen shall by order revoke or suspend, and in case of suspension, may reinstate such license.

#### **18.2 Rabies**

- A. Deleted
- B. **Vaccination of Cats Against Rabies** – Whoever is the owner or keep of a cat six months of age or older shall cause such cat to be vaccinated against rabies by a licensed veterinarian. Such owner or keeper shall procure a veterinarian's certificate that such cat has been so vaccinated and setting for the date of such vaccination and the duration of immunity, or a notarized letter from a veterinarian that a certificate was used, or a rabies tag bearing an expiration date indicating that such certification is still in effect.

## ARTICLE 18 (cont.)

**18.3** Deleted

**18.4** Deleted

**18.5** Deleted

**18.6** Deleted

**18.7** Deleted

**18.8** Deleted

### **18.9 Enforcement**

The provisions of this by-law shall be enforced by the dog officer of the Town of Freetown and may be enforced by any police officer of said Town.

### **18.10 Killing of Cats for Humane Purposes**

When, in the judgement of the dog officer or any police officer, in this Town, an animal should be destroyed for humane reasons, such animal may not be reclaimed, and may be destroyed by the dog officer or police officer.

**18.11** Deleted

### **18.12 Right of Entry**

In the discharge of the duties imposed by the by-laws, the dog officer or any police officer of this Town shall have the authority at all reasonable times to enter upon any premises, but such authority should not include the right to enter any residence on such premises to examine a cat or other animal which is allegedly in violation of a provision of these by-laws. Such officer shall have the further authority to take possession of any such cat or other animal and remove it from such premises.

**18.13** Deleted

### **18.14 Penalty**

Except as otherwise provided herein, any person violating any provision of these by-laws may be punished by the payment of a penalty of fifty (\$50.00) dollars to be recovered for the use of the Town and if such violation be continued, each day's violation may constitute a separate offense. The provisions and procedures in Mass. General Laws Chapter 140, § 173A shall be followed and apply to violation of these by-laws.

The provisions of M.G.L., Chapter 140, §151 and 151A remain affect.

## **ARTICLE 19**

### **UNREGISTERED MOTOR VEHICLES** *STM 11/20/06, ATM 5/7/07, ATM 6/11/90, STM 06/01/09*

#### **UNREGISTERED VEHICLES –**

##### **19.1 Definitions:**

##### **A. Antique Motor Car**

Any motor vehicle over twenty-five years old which is maintained solely for use in exhibitions, club activities, parades or other functions of public interest and which is not used primarily for the transportation of passengers or goods over any way.

##### **B. Farmer**

A person substantially engaged in the occupation of farming as defined in M.G.L. chapter 90, section 1.

## **ARTICLE 19 (19.1 cont.)**

### **C. Junk Vehicle**

Shall be a vehicle which is abandoned, wrecked, or partially dismantled, discarded; and shall also include an unregistered vehicle, but excluding vehicles that are registered on a seasonal basis.

### **D. Motor Vehicle**

Shall mean a machine propelled by other than human power that is designed to travel on the ground by use of wheels, treads, runners or slides and transport persons, property or other machinery and shall include, without limitations, automobiles, buses, mobile homes, motor homes, trucks, trailers, motorcycles, tractors or recreational and snow vehicles. The definition of "motor vehicle" shall not include wheelchairs, lawn mowers, golf carts, and motorized bicycles.

### **E. Number Plate**

The sign or marker furnished by the registrar on which is displayed the register number or mark of a motor vehicle assigned to such motor vehicle by the registrar as defined in M.G.L. c.90, s.1.

### **F. Person**

Shall mean any person, corporation, partnership, or other legal entity.

### **G. Repairman**

Any person who is principally and substantially engaged in the business of repairing, altering, reconditioning, equipping, or towing motor vehicles or trailers for the public and who maintains an established place of business as defined in M.G. L. c.90, s.1, with the facilities for the repairing of such motor vehicles or trailers.

### **H. Registered Vehicle.**

A vehicle currently registered and bearing an unexpired registration plate pursuant to Massachusetts General Laws, Chapter 90 or comparable laws of other States and the United States of America.

### **I. Trailer.**

Any vehicle or object on wheels and having no motive power of its own, but which is drawn by, or used in combination with, a motor vehicle as defined in M.G.L. c.90, s.1.

## **19.2 General Information.**

Except as authorized by permit, no person shall park, store, keep, leave or allow that there be parked, stored, kept or left, more than two unregistered motor vehicle or trailer or registered motor vehicle(s) without a valid windshield inspection sticker as required by Massachusetts General Laws, Chapter 90 Section 7A, or by the laws of the state of registration, or any disassembled parts thereof, on any land within the Town of Freetown.

The absence of a valid and current number plate(s) affixed to a motor vehicle or trailer shall constitute prima facie evidence that such vehicle or trailer is unregistered.

Except as authorized by permit, no person shall park, store, keep, leave or allow that there be parked, stored, kept or left, any junk vehicle(s), or any disassembled parts thereof, on any land within the Town of Freetown.

## **19.3 Written Approval Required.**

Any person seeking a permit must make application to the Chief of Police. Permits shall not exceed one calendar year (365 days); however, upon re-application, the Chief of Police may re-issue said permit on an annual basis. The Board of Selectmen may establish an application fee.

## **19.4 Limitations.**

At no time will a permit for more than three vehicles be granted to a Licensed Repairer not operating under a motor vehicle sales business or junk business license in accordance with the provisions of Chapter 140 of Massachusetts General Laws.

## **19.5 Aggrieved Party.**

Any person aggrieved by a denial of the Chief of Police may seek approval from the Board of Selectmen by filing a written request for same in the Office of the Town Clerk.

## **ARTICLE 19 (cont.)**

### **19.6 Permit Criteria.**

The Chief of Police and /or the Board of Selectmen may use the following criteria as a means of determining whether or not to grant such a permit:

- A.** The condition of the vehicle or vehicles. Is it considered to be junk, inoperative, rusted, dismantled or abandoned, or in any way a visible nuisance?
- B.** Whether or not the vehicle or vehicles present a public health hazard, such as broken glass or jagged metal.
- C.** Whether or not the vehicle or vehicles present a public health hazard, such as oil or gas spillage, or other toxic fluids found in the engine or other vehicle parts. Does it serve as a harborage for diseased vermin?
- D.** Whether or not the vehicle or vehicles present a public safety hazard such as electrical shock or fire.
- E.** The proximity of the vehicle or vehicles to adjoining properties and the visibility of such vehicles from adjoining or nearby properties or public ways.
- F.** Whether or not the applicant has complied with the terms of an existing permit or previously issued permit.

### **19.7 Exclusions.**

This By-law shall not apply to:

- A.** Vehicles owned by the Commonwealth of Massachusetts, County of Bristol or the Town of Freetown;
- B.** To vehicles within a completely enclosed structure including side walls and roof in a lawful manner where they are not visible from the street or other public or private property;
- C.** Unlicensed, operable or inoperable antique motor cars or parts thereof stored by a collector on private property.
- D.** To registered trailers used for recreational purposes such as camping or boating or those trailers used for the conveyance of off road vehicles such as snowmobiles, motorcycles or other off road recreational vehicles not including automobiles or trucks. Or to registered trailers used for the conveyance of landscaping or other seasonal equipment.
- E.** To vehicles on property operating under a license in accordance with the provisions of Chapter 140 of Massachusetts General Laws for use in connection with a motor vehicle business or junk business;
- F.** To farm vehicles owned by a farmer on property where said vehicles are necessary in an agricultural use;
- G.** To vehicles stored on property on which industrial or commercial use is permitted under zoning which are not manufactured for use over the road and are not customarily registered. Provided that the vehicles and the outdoor storage areas are maintained in such a manner that they do not constitute a health hazard and are screened from ordinary public view by means of a fence, rapidly growing trees, shrubbery, or other appropriate means.

### **19.8 Penalties.**

The provisions of this By-law may be enforced by an available means in law or equity, including but not limited to enforcement by non-criminal disposition pursuant to G.L. c. 40, §21D and Article 25 of the Town's By-Laws. Each day a violation exists shall constitute a separate violation.

The provisions of this by-law may be enforced by police officers or other persons so authorized by the Board of Selectmen.

## ARTICLE 19 (cont.)

### **19.9 Severability.**

This by law shall be interpreted insofar as possible as consistent with state law. In the event of an inconsistency, however, state law shall control. This by-law shall be interpreted insofar as possible as consistent with existing by-laws. In the event of an inconsistency, however, this by-law shall control.

## **ARTICLE 20**

### **JUNK & USED AUTO DEALERS AND COLLECTORS** *ATM 5/9/77, ATM 3/11/67*

#### **20.1 Licensing Procedures**

The Selectmen may license such persons as they deem suitable to be dealers in and keepers of shops for the purchase, sale, or barter of junk, old metals or second hand articles, and the junking and disposing of automobiles, within the town; and as junk collectors, to collect, by purchase or otherwise, junk, old metals and second hand articles from place to place within the town, subject to the provisions of § 54 through 59 of Chapter 140 of the Generals Laws, provided, nevertheless, that all licenses thus granted shall contain a clause that the person thus licensed agrees to abide by and be subject to all the provisions of the by-law, or any by-laws, and all rules and regulations adopted by the Selectmen, which may be adopted by the Town Meeting to dealers in and keepers of shops licensed for the purpose and to junk collectors licensed as aforesaid. Before such licenses shall be granted all premises shall be inspected by the selectmen or their agent, making a written report of the same and due notice of hearing being given.

#### **20.2 Rules & Regulations**

The Board of Selectmen may make additional rules and regulations to supplement this article subject to § 54 of said Chapter 140.

#### **20.3 Third Class Licenses**

The Town shall limit the number of third class motor vehicles dealers' licenses, or junk licenses to a maximum of ten (10). *ATM 5/24/99*

#### **20.4 Second Class Licenses**

The Town shall limit the number of second class auto licenses for the sale of used automobiles to a maximum of twenty-seven (27). *STM-7/15/76, ATM-5/1/89*

## **ARTICLE 21**

### **TIRE STORAGE AND REGULATIONS**

#### **21.1 Tire Storage**

No person, owner, business or corporation shall establish, maintain or allow to exist on any property within the Town of Freetown, a tire storage yard or facility consisting of the open or outside storage of new rubber tires, tire casings, tire tubes, rubber scraps or any other by-product of rubber tires, and not more than one hundred (100) used tires. Any person who shall violate any of the provisions of this by-law shall be subject to a penalty of not less than \$20.00 or more than \$100.00 for each such offense. Each day the violation continues or its allowed to remain shall be considered a separate offense. *ATM 5/5/80*

#### **21.2 Tire Regulations**

Regulations governing the existing storage of new or used rubber tires, tire casings, tire tubes, rubber scraps, and/or any other by-product of rubber tires as on file in the office of the Town Clerk: *ATM 5/5/80*

The storage site shall be reasonably level, solid ground, preferably surfaced with fine gravel. Refuse or filled-land, swampy ground, or areas where the hazard of underground fire is present shall not be used.

All-weather roadways, alley-ways, and fire lanes capable of supporting fire department apparatus shall be provided to the plant and throughout the storage yard from town ways.

## ARTICLE 21 (21.2 cont.)

All sides of storage piles shall be accessible by means of alley-ways and fire lanes. An alley-way width of 1 ½ times pile-height, but not less than twenty feet is required with fire lanes between alternate rows of two pile groups, providing a clear space of at least 100 feet. The length of each pile shall not exceed 125 feet in length, 25 feet in width, or 15 feet in height. Fire lanes for access across each end providing a clear space of at least 100 feet to adjacent pile rows, or other exposed property shall be provided.

Where practical, greater widths are desirable to minimize the effects of radiated heat, particularly in high-piled yards. Fire lanes shall be kept unobstructed at all times to permit maneuvering of fire suppression equipment. For basic fire protection, a water supply shall be provided where practical. The supply should be large enough to provide 1,000 G.P.M. for a period of two hours, and shall be accessible to fire apparatus as directed by fire department personnel.

Weeds, grass, and similar vegetation shall be prevented throughout the yard, and should be sprayed as often as needed with a satisfactory herbicide or ground sterilizer or grubbed out. Dead vegetation shall be removed after destruction. Weed burners should not be used.

Good housekeeping should be maintained at all times, including regular and frequent cleaning of materials handling equipment.

Smoking shall be prohibited in tire storage yards. No Smoking signs shall be posted in storage yards.

Access into yard areas by unauthorized persons shall be prohibited. Where needed, storage areas should be enclosed with a suitable fence equipped with proper gates located as necessary, to permit entry of fire department apparatus.

Miscellaneous occupancy hazards such as vehicle storage and repair shops, cutting and welding operations, flammable liquid storage, liquefied petroleum gas storage and similar operations shall be safe-guarded in accordance with recognized good practice. Refer to various N.F.P.A. standards applicable to specific occupancy hazards.

Vehicles and other power devices should be of an approved type, safely maintained and operated. Vehicle fueling operations should be conducted in specified safe locations, isolated from storage areas and principal operating buildings. (Refer to standard for Powered Industrial Trucks, N.F.P.A., 505.)

All electrical equipment and installations shall conform to the provisions of the National Electrical Code, N.F.P.A., 70.

No cutting, welding, or other use of open flames or spark-producing equipment shall be permitted in the storage area.

The owner of the storage yard shall be responsible for the hiring of any heavy equipment to aid in the extinguishing of a fire, should it be deemed necessary

## **ARTICLE 22**

### **VOLATILE LIQUIDS**

#### **22.1 Disposal of Volatile Liquids**

No person shall dispose of, or cause to be disposed of, any volatile or nonvolatile inflammable liquids, in closed containers in any public dump, in or adjacent to any public way, or on any property belonging to or under the control of the town. *ATM 3/12/60*

#### **22.2 Disposal by Collection**

No person shall place any volatile or nonvolatile inflammable liquids for the purpose of being picked up by rubbish collectors employed by or under contract to the town. *ATM 3/12/60*

#### **22.3 Penalty**

Breaches of the foregoing sections may be punished by a penalty of not more than \$20.00 for each offense which may be recovered by indictment or on complaint before the District Court. *ATM 3/12/60*

## **ARTICLE 22 (cont.)**

### **22.4 Regulations**

By-Law to Prevent Leaking of Underground Fuel and Chemical Storage Systems *ATM 5/6/91, STM 9/22/86*

Pursuant to Chapter 40, § 21 and Chapter 148, §9 of the Massachusetts General Laws, the Town of Freetown hereby adopts the following by-law to protect the ground and surface waters from contamination with liquid fuel or toxic materials from leaking storage tanks. The following regulations apply to all underground fuel and chemical storage systems, tanks and piping:

1. The State Fire Prevention Regulations for underground storage tanks, 527C.M.R. 9 is hereby adopted as and included as part of this by-law.
2. All existing underground storage tanks for consumptive use must meet the following on or before the tank has been in the ground for twenty (20) years.
  - A. Leak detection
  - B. Cathodic protection
  - C. A spill containment manhole
  - D. Overfill protection

Any underground storage tank owner with a tank used for consumptive use must show a signed permit with date of issue to verify the age of said tank. If the owner of an existing underground storage tank cannot provide the Fire Chief or his designee with a dated permit, it will be assumed for these regulations that the underground storage tank is twenty (20) years old.

If the tank has been in the ground for twenty (20) years and is not equipped with A, B, C, and D from the above list, it must be tested annually or removed.

3. Non-compliance with this by-law will result in a fine of One hundred (\$100) dollars per day for each day the violation continues.

## **ARTICLE 23**

### **COAL ASH**

#### **23.1 Prohibition of Coal Ash**

Ash produced from the combustion of coal, including but not limited to fly ash and bottom ash, is prohibited from being disposed of, stored, stockpiled, or used as fill material for any and all purposes, within the Town of Freetown. *ATM 5/7/01, STM 10/22/01*

#### **23.2 Board of Health – Coal Ash Projects**

The Freetown Board of Health retains the right to examine engineer's plans or require engineer's plans for all coal ash projects which conform to Mass. General Laws, Chapter 111, § 150A, which do not need to proceed through the site assignment process. The Board of Health will determine if the project has the potential to jeopardize the water table, any aquifers present, or the health and welfare of the residents of Freetown, and establish conditions necessary to protect those concerns. *STM 9/14/92*

## **ARTICLE 24**

### **MISCELLANEOUS CONTROLS & REGULATIONS**

#### **24.1 Covering Wells**

Owners of land whereon is located an abandoned well or a well in use shall provide for and cover such well with a covering capable of sustaining a weight of 300 pounds or shall fill the same with earthen fill to the level of the ground.

The penalty for violation of this by-law shall be a fine of not less than One hundred (\$100.00) dollars nor more than Five hundred (\$500.00) dollars.

## **ARTICLE 24 (cont.)**

### **24.2 Substances Pumped on Street**

No person shall pump any water or other liquid substance under his control into or across any sidewalk or street and no person shall pump any water/or other substance onto land owned or occupied by him in such a manner as to allow or cause such water or substance to flow onto any such sidewalk or street. Penalties presently provided by Article 18, § 18.14 will apply to this section. *ATM 5/5/80*

### **24.3 Littering**

No person shall deposit papers, circulars or advertising matter of any kind in the public ways of the town or distribute the same through the town in such a manner as to create a disturbance or litter.

### **24.4 Video Game Rooms; Go Carts/All Terrain**

- A. It shall be unlawful for any person to operate or to permit to be operated on any premises in the town a video arcade without first securing a license issued by the Board of Selectmen as required by the provisions of chapter 140, sec. 177A of the General Laws of Massachusetts concerning automatic amusement devices.
- B. The provisions of Section A of this By-Law shall not be applicable to any person having in his private residence one or more automatic amusement devices for his own private use or for the use of his family and friends.
- C. No go-cart track or all terrain vehicle track shall be operated within the Town of Freetown without a license issued by the Board of Selectmen, after a hearing conducted in accordance with regulations adopted by the Board of Selectmen. *STM 8/23/82, STM 2/25/08*

### **24.5 By-Law for Open Burning and Burning Permit Fee** *STM 9/14/92*

- A. The Town of Freetown hereby adopts the following by-law for governing open burning or the burning of any material out-of-doors; Any person who violates any provisions of M.G.L. Chapter 48, §13, (setting fires in open air, etc.) or 310 C.M.R. 7.07 (Department of Environmental Protection Open Burning Regulations) shall be subject to a penalty of Fifty (\$50.00) dollars for each offense. This by-law may be enforced by the Fire Chief, any firefighter whom the Fire Chief has delegated written authority under the provisions of Chapter 148, any Police Officer, or the Building Inspector through non-criminal disposition, civil action or criminal penalty.
- B. The permit fee for open burning shall be Five (\$5.00) dollars for the burning season.

### **24.6 Pyrotechnics** *ATM 5/2/05, STM 11/7/05, STM 12/3/07*

- A. Notwithstanding the provisions of 527 CMR 2.09, the use of pyrotechnic devices, pyrotechnic materials, and pyrotechnic special effects, as defined in 527 CMR 2.03, in the interior of a structure or building is hereby prohibited.
- B. Compliance with this article shall be a condition of any license or permit issued by the Town of Freetown for on-premises consumption of alcoholic beverages and/or for entertainment.
- C. Any person violating any of the provisions of this article shall be punished by a fine of Three Hundred Dollars (\$300.00.) Each and every day shall be considered a separate and continuing offense subject to an individual fine. Any violation shall be sufficient grounds for revocation of any license referenced in Section 24.6B.

### **24.7 Depositing Snow on Roads and Sidewalks** *STM 06/01/09*

No person other than an employee in the service of the Town of Freetown or an employee in the service of an independent contractor acting for the Town, shall pile, push, plow, throw, shovel or by any other means cause snow or ice to be deposited or placed on any part of a public street or sidewalk or fire hydrant or other similar device in the Town so as to impede, obstruct or interrupt or otherwise adversely affect the unrestricted flow of traffic, or the safe travel of any pedestrian on such roadway or sidewalk, or conceal any fire hydrant or other similar device.

Violations of this bylaw section are punishable by a fine of \$100.00 for each violation.

## **ARTICLE 24 (24.7 cont.)**

The provisions of this By-law may be enforced by any available means in law or equity, including but not limited to enforcement by non-criminal disposition pursuant to G.L. c. 40, §21D.

The provisions of this by-law may be enforced by police officers or other persons so authorized by the Board of Selectmen.

## **ARTICLE 25**

### **PROSECUTIONS AND PENALTIES**

#### **25.1 Prosecutions for Offenses**

Except when otherwise provided by law, prosecutions for offenses under the by-laws of the Town may be made by any constable or police officer of the Town.

#### **25.2 Penalties**

Whoever violates any by-law of the Town whereby any act or thing is enjoined, required, or prohibited shall forfeit and pay for each offense a fine of Fifty (\$50) dollars for the first offense, One hundred (\$100) dollars for the second offense, and One hundred fifty (\$150) dollars for the third or subsequent offense. Each day such offense continues shall constitute a separate offense. These penalties may be enforced through the non-criminal procedure or the usual criminal procedure. Further enforcement may be made through Superior Court action for restraining orders or other appropriate remedies.

These penalties replace the penalties in Articles 13- Streets, Sidewalks and Public Places, 24.1- Covering Wells, 11- Protective by-laws and 22- Inflammable Liquids, 21-Tire Storage. *ATM 5/6/91*

#### **25.3 Non-Criminal Disposition**

Whoever violates any provision of these By-Laws, the violation of which is subject to a specific penalty, may be penalized by a non-criminal disposition as provided in General Laws, Chapter 40, § 21D. The non-criminal method of disposition may also be used for violations of any rule or regulation of any municipal officer, board of department which is subject to a specific penalty.

Any person taking cognizance of a violation of a specific By-Law, rule or regulation which he is empowered to enforce, hereinafter referred to as the enforcing person, as an alternative to initiating criminal proceedings may give to the offender a written notice to appear before the Clerk of the Fall River District Court at any time during office hours, not later than twenty-one (21) days after the date of such notice. Such notice shall be in triplicate and shall contain the name and address if known, of the offender, the specific offense charged, and the time and place of his required appearance. Such notice shall be signed by the enforcing person and shall be signed by the offender whenever practicable in acknowledgment that such notice has been received.

If the enforcing person is unable to deliver a copy of the notice to the offender at the time and place of the violation, said copy shall be mailed or delivered by the enforcing person or by his commanding officer or the head of his department or by any person authorized by such commanding officer, department or head to the offender's last known address, within fifteen (15) days after said violation. Such notice as so mailed shall be deemed a sufficient notice, and a certificate of the person so mailing such notice that it has been mailed in accordance with this section shall be prima facie evidence thereof.

At or before the completion of each tour of duty, or at the beginning of the first subsequent tour of duty, the enforcing person shall give to his commanding officer or department head those copies of each notice of such a violation he has taken cognizance of during such tour which have not already been delivered or mailed by him as aforesaid. Said commanding officer or department head shall retain and safely preserve one copy and shall, at a time not later than the next court day after such delivery or mailing, deliver the other copy to the Clerk of Court before which the offender has been notified to appear.

The disposition of such notices by the Clerk of the Fall River District Court shall be in accordance with § 21D of Chapter 40 of the General Laws, and/or take any other action relative thereto. *ATM 5/7/90*

## **ARTICLE 26**

### **APPROVAL, EFFECTIVE DATE OF BY LAWS**

#### **26.1 Approval of By-Laws**

These by-laws shall take effect upon approval and publication in the manner required by law and shall be in lieu of all by-laws heretofore enforced except for the Soil Removal By-Law passed at the annual town meeting of 1956 which by-law shall be incorporated therein.

#### **26.2 Provision of By-Laws**

If any provision of these by-laws be held unlawful or shall not be approved it shall not effect any other provision of these by-laws or the enforcement thereof.

## **ARTICLE 27**

### **NON-STORMWATER DISCHARGES TO THE MUNICIPAL STORM DRAINAGE SYSTEM OF THE TOWN OF FREETOWN** *STM 11/20/06, ATM 5/7/07*

#### **Section 27-1. Objective/Intent.**

The objective of this by-law is to prevent non-stormwater discharges to the Town of Freetown's municipal storm drain system through the regulation of non-stormwater discharges to the storm drain system to the maximum extent practicable as required by federal and state law. Non-stormwater discharges are a major concern because they can impair the water quality of fresh water bodies, including streams, rivers and wetlands; contaminate drinking water supplies; alter or destroy aquatic habitat; and increase flooding.

This by-law seeks to prevent the introduction of pollutants into the municipal storm drain system in order to comply with requirements of the National Pollutant Discharge Elimination System (NPDES) permit process by:

Regulating the contribution of pollutants to the municipal storm drainage system from stormwater discharges by any user;

Prohibiting illicit connections and discharges to the municipal storm drainage system;

Establishing legal authority to carry out all inspection, surveillance and monitoring procedures necessary to ensure compliance with this by-law.

Prohibiting discharges into the municipal storm drainage system that may or can create a condition that is harmful to public safety and welfare.

#### **Section 27-2. Definitions.**

For the purposes of this by-law the following shall mean:

- 1. Authorized Enforcement Agency.** The Building Commissioner and the employees and designees of the Town's Building Department are the Authorized Enforcement Agency designated to enforce this by-law.
- 2. Best Management Practices(BMPS).** Schedules of activities, prohibitions of practices, general good house keeping practices, pollution prevention and educational practices, maintenance procedures, and other management practices to prevent or reduce the discharge of pollutants directly or indirectly to stormwater, receiving waters, or stormwater conveyance systems. BMPs also include treatment practices, operating procedures, and practices to control site runoff, spillage or leaks, sludge or water disposal, or drainage from raw materials storage.
- 3. Clean Water Act.** The Federal Water Pollution Control Act (33 U.S.C. § 1251 et seq.), and any subsequent amendments thereto.
- 4. Construction Activity.** Activities subject to NPDES Construction Permits. These include construction projects resulting in land disturbance of five (5) acres or more. Such activities include, but are not limited to, clearing and grubbing, grading, excavating, and demolition.

## ARTICLE 27 (27-2 cont.)

5. **Hazardous Materials.** Any material, including any substance, waste, or combination thereof, which because of its quantity, concentration, or physical, chemical, or infectious characteristics may cause, or significantly contribute to, a substantial present or potential hazard to human health, safety, property, or the environment when improperly treated, stored, transported, disposed of, or otherwise managed.
6. **Illicit Connections.** Any surface or subsurface drain or conveyance which allows an illegal discharge to enter the municipal storm drain system including, but not limited to, any conveyances which allow any non-storm water discharge including sewage, process wastewater, and wash water to enter the storm drain system and any connections to the storm drain system from indoor drains, sinks or toilets, regardless of whether said drain or connection had been previously allowed, permitted, or approved by an authorized enforcement agency.
7. **Illegal Discharge.** Any direct or indirect non-storm water discharge to the storm drain system, except as exempted in Section 7 of this by-law.
8. **Industrial Activity.** Activities subject to NPDES Industrial Permits as defined in 40 CFR 122.26 (b)(14).
9. **National Pollutant Discharge Elimination System (NPDES) Storm Water Discharge Permit.**  
A permit issued by EPA (or by the Commonwealth of Massachusetts under authority delegated pursuant to 33 USC § 1342(b) that authorizes the discharge of pollutants to waters of the United States, whether the permit is applicable on an individual, group, or general area-wide basis.
10. **Non-Storm Water Discharge.** Any discharge to the municipal storm drain system that is not composed entirely of storm water.
11. **Person.** Any individual, partnership, association, firm, company, trust, corporation, agency, authority, department or political subdivision of the Commonwealth or the federal government, to the extent permitted by law, and any officer, employee or agent of such person.
12. **Pollutant.** Any element or property of sewage, agricultural, industrial, or commercial waste, runoff, leachate, heated effluent or other matter whether originating at a point or non-point source that is or may be introduced into any storm drain system, waters of the Commonwealth and/or waters of the United States. Pollutants may include, but are not limited to: paints, varnishes, and solvents; oil and other automotive fluids; non-hazardous liquid and solid wastes and yard wastes; refuse, rubbish, garbage, litter, or other discarded or abandoned objects, by-laws, and accumulations, so that same may cause or contribute to pollution; floatables; pesticides, herbicides, and fertilizers; hazardous substances and wastes; sewage, fecal coliform and pathogens; dissolved and particulate metals; animal wastes; rock, sand, salt and soils; wastes and residues that result from constructing a building or structure; and noxious or offensive matter of any kind.
13. **Premises.** Any building, lot, parcel of land, or portion of land whether improved or unimproved including adjacent sidewalks and parking strips.
14. **Storm Drainage System.** A system used to collect and/or convey stormwater including, but not limited to, any roads with drainage systems, municipal streets, gutters, curbs, inlets, piped storm drains, pumping facilities, retention and detention basins, natural and human-made or altered drainage channels, reservoirs, and other drainage structures owned or operated by the Town of Freetown.
15. **Storm Water.** Any surface flow, runoff, and drainage consisting entirely of water from any form of natural precipitation, and resulting from such precipitation.
16. **Watercourse.** A natural or man-made channel through which water flows or a stream of water, including a brook or underground stream.
17. **Waters of The Commonwealth.** All waters within the jurisdiction of the Commonwealth of Massachusetts, including, without limitation, rivers, streams, lakes, ponds, springs, impoundments, estuaries, wetlands, coastal waters and groundwater.
18. **Wastewater.** Any sanitary waste, sludge, septic tank or cesspool overflow, and water that during manufacturing, cleaning or processing comes in direct contact with or results from the production or use of any raw material, intermediate product, by-product or waste product

## **ARTICLE 27 (cont.)**

### **Section 27-3. Applicability.**

This by-law shall apply to all water entering the Storm Drainage System owned or operated by the Town of Freetown unless explicitly exempted by the Building Commissioner.

### **Section 27-4. Authority.**

This by-law is adopted under the authority granted by the Home Rule Amendment of the Massachusetts Constitution and the Home Rule Procedures Act, and G.L. c.83, §1 and §10, as amended by St. 2004, c.149, §§135-140, and the Federal Clean Water Act, 40 CFR 122.34.

### **Section 27-5. Responsibility for Administration.**

The Building Commissioner as the Authorized Enforcement Agency shall administer, implement, and enforce the provisions of this by-law. Any powers granted or duties imposed upon the Building Commissioner may be delegated in writing by the Building Commissioner to persons or entities acting in the beneficial interest of or in the employ of the Town under the Building Commissioner.

### **Section 27-6. Severability.**

The provisions of this by-law are hereby declared to be severable. If any provision, clause, sentence, or paragraph of this by-law or the application thereof to any person, establishment, or circumstances shall be held invalid, such invalidity shall not affect the other provisions or application of this by-law.

### **Section 27-7. Prohibited Activities.**

#### **A. Prohibition of Illegal Discharges.**

No person shall discharge or cause to be discharged into the municipal Storm Drainage System or watercourses any materials including, but not limited to, pollutants or waters containing any pollutants that cause or contribute to a violation of applicable water quality standards, other than storm water.

The commencement, conduct or continuance of any Illegal Discharge to the Storm Drainage System is prohibited except as provided as follows, and further provided that the exempt source is not a significant contributor of a Pollutant to the Storm Drainage System; notwithstanding the last previous phrase, all fire fighting activities are exempt:

The following discharges are exempt from discharge prohibitions established by this by-law: water line flushing or other potable water sources, landscape irrigation or lawn watering, diverted stream flows, rising ground water, ground water infiltration to storm drains, uncontaminated pumped ground water, foundation or footing drains (not including active groundwater dewatering systems), crawl space pumps, air conditioning condensation, springs, non-commercial washing of vehicles, natural riparian habitat or wetland flows, swimming pools (if de-chlorinated), fire fighting activities, and any other water source not containing Pollutants.

Discharges specified in writing by the Building Commissioner, as the Authorized Enforcement Agency, as being necessary to protect public health, safety, welfare or the environment.

Dye testing is an allowable discharge, but requires a written notification to the Building Commissioner prior to the time of the test.

The prohibition shall not apply to any non-storm water discharge permitted under an NPDES permit, waiver, or waste discharge order issued to the discharger and administered under the authority of the Federal Environmental Protection Agency, provided that the discharger is in full compliance with all requirements of the permit, waiver, or order and other applicable laws and regulations, and provided that written approval has been granted for any discharge to the Storm Drainage System.

#### **B. Prohibition of Illicit Connections.**

1. The construction, use, maintenance or continued existence of illicit Connections to the Storm Drainage System is prohibited.

## **ARTICLE 27 (27-7 cont.)**

2. This prohibition expressly includes, without limitation, illicit connections made in the past, regardless of whether the connection was permissible under law or practices applicable or prevailing at the time of connection.

A person is considered to be in violation of this by-law if the person connects a line conveying sewage to the Storm Drainage System, or allows such a connection to continue.

### **C. Time for Compliance**

Residential property owners shall have 90 days from the effective date of this by-law to comply with its provisions, provided good cause is shown for the failure to comply with the by-law during that period.

## **Section 27-8. Suspension of Municipal Storm Drainage System Access.**

### **Suspension due to Illegal Discharges in Emergency Situations.**

The Building Commissioner, as the Authorized Enforcement Agency, may, without prior notice, suspend municipal Storm Drainage System discharge access to any person or property when such suspension is necessary to stop an actual or threatened discharge which presents or may present an imminent risk of harm to public health, safety or welfare; to the environment; to the municipal Storm Drainage System or Waters of the Commonwealth or the United States. If the violator fails to comply with an emergency suspension order, the Authorized Enforcement Agency may take such steps as deemed necessary to prevent or minimize damage to the municipal Storm Drainage System or Waters of the Commonwealth or the United States, and/or to minimize risk of harm to public health, safety or welfare or to the environment.

### **Suspension due to the Detection of Illegal Discharge.**

Any person discharging to the Town's Storm Drainage System in violation of this by-law may have their access terminated if such termination would abate or reduce an Illegal discharge. The Building Commissioner, as the Authorized Enforcement Agency, shall notify a violator of the proposed termination of its Storm Drainage System access. The violator may petition the Building Commissioner for reconsideration and a hearing regarding such notice of termination.

A person commits an offense if the person reinstates municipal Storm Drainage System access to premises terminated pursuant to this Section, without the prior approval of the Building Commissioner.

## **Section 27-9. Industrial or Construction Activity Discharges.**

Any person subject to an industrial or construction activity NPDES storm water discharge permit shall comply with all provisions of such permit. Proof of compliance with said permit may be required in a form acceptable to the Building Commissioner prior to the allowing of discharges to the municipal Storm Drainage System.

## **Section 27-10. Monitoring of Discharges.**

### **A. Applicability.**

This Section applies to all facilities that have storm water discharges associated with industrial activity, including construction activity.

### **B. Access to Facilities.**

1. The Building Commissioner, as the Authorized Enforcement Agency, shall be permitted to enter and inspect facilities subject to regulation under this by-law as often as may be necessary to determine compliance with this by-law. If a discharger has security measures in force that require proper identification and clearance before entry into its premises, the discharger shall make the necessary arrangements to allow access to the Building Commissioner or his/her authorized representatives.
2. Facility operators shall allow the Building Commissioner ready access to all parts of the premises for the purposes of inspection, sampling, examination and copying of records that must be kept under the conditions of an NPDES permit to discharge storm water, and the performance of any additional duties as defined by state and federal law.
3. The Building Commissioner shall have the right to set up on any permitted facility such devices as are necessary in the opinion of the Building Commissioner to conduct monitoring and/or sampling of the facility's storm water discharge.

## **ARTICLE 27 (27-10 cont.)**

4. The Building Commissioner has the right to require the discharger to install monitoring equipment as determined by the Building Commissioner. The facility's sampling and monitoring equipment shall be maintained at all times in a safe and proper operating condition by the discharger at its own expense. All devices used to measure stormwater flow and quality shall be calibrated to ensure their accuracy.

Any temporary or permanent obstruction to safe and easy access to the facility to be inspected and/or sampled shall be promptly removed by the operator at the written or oral request of the Building Commissioner and shall not be replaced. The costs of clearing such access shall be borne by the operator.

Unreasonable delays in allowing the Building Commissioner access to a permitted facility is a violation of a storm water discharge permit and of this by-law. A person who is the operator of a facility with a NPDES permit to discharge storm water associated with industrial activity commits an offense if the person denies the Building Commissioner reasonable access to the permitted facility for the purpose of conducting any activity authorized or required by this by-law.

If the Building Commissioner has been refused access to any part of the premises from which stormwater is discharged, and he/she is able to demonstrate probable cause to believe that there may be a violation of this by-law, or that there is a need to inspect and/or sample as part of a routine inspection and sampling program designed to verify compliance with this by-law or any order issued hereunder, or to protect the overall public health, safety, and welfare of the community, then the Building Commissioner may seek issuance of a search warrant from any court of competent jurisdiction.

### **Section 27-11. Requirement to Prevent, Control, and Reduce Storm Water Pollutants by the Use of Best Management Practices.**

The Building Commissioner, as the Authorized Enforcement Agency, shall adopt requirements identifying Best Management Practices (BMPs) for any activity, operation or facility which may cause or contribute to pollution or contamination of Storm Water, the Storm Drainage System, or Waters of the Commonwealth or the United States. The owner or operator of a commercial or industrial establishment shall provide, at their own expense, reasonable protection from accidental discharge of prohibited materials or other wastes into the municipal Storm Drainage System or Watercourses through the use of these structural and non-structural BMPs.

Further, any person responsible for Premises, which is, or may be, the source of an Illicit Discharge, may be required to implement, at said Person's expense, additional structural and non-structural BMPs to prevent the further discharge of pollutants to the municipal Storm Drainage System. Compliance with all terms and conditions of a valid NPDES permit authorizing the discharge of Storm Water associated with industrial activity, to the extent practicable, shall be deemed compliant with the provisions of this section. These BMPs shall be part of a Stormwater Pollution Prevention Plan (SWPP) as necessary for compliance with requirements of the NPDES permit.

### **Section 27-12. Watercourse Protection.**

Every person owning Premises through which a Watercourse passes, or such person's lessee, shall keep and maintain that part of the Watercourse within the Premises free of trash, debris, excessive vegetation, and other obstacles that would pollute, contaminate, or significantly retard the flow of water through the Watercourse. In addition, the owner or lessee shall maintain existing privately owned structures within or adjacent to a Watercourse, so that such structures will not become a hazard to the use, function, or physical integrity of the Watercourse.

### **Section 27-13. Notification of Spills.**

Notwithstanding other requirements of local, state or federal law, as soon as any person responsible for a facility or operation, or responsible for emergency response for a facility or operation has information of any known or suspected release of materials which are resulting or may result in illegal discharges or pollutants discharging into Storm Water, the Storm Drainage System, or Waters of the Commonwealth and United States, said person shall take all necessary steps to ensure containment and cleanup of such release. In the event of such a release of oil or hazardous materials, said person shall immediately notify emergency response agencies of the occurrence via emergency dispatch services. In the event of a release of non-hazardous materials, said person shall notify the Building Commissioner, as the Authorized Enforcement Agency, in person or by telephone or facsimile no later than the next business day. Notifications in person or by telephone shall be confirmed by written notice addressed and mailed to the Building Commissioner within three business (3) days of the telephone notice. If the discharge of prohibited materials emanates from a commercial or industrial establishment, the owner or operator of such

## **ARTICLE 27 (27-13 cont.)**

establishment shall also retain an on-site written record of the discharge and the actions taken to prevent its recurrence. Such records shall be retained for at least three (3) years.

### **Section 27-14. Enforcement.**

The Building Commissioner, as the Authorized Enforcement Agency shall enforce this by-law, regulations, order, violation notices, and may pursue all criminal and civil remedies for such violations.

#### **A. Civil Relief.**

If a person violates the provisions of the by-law, regulations, permit, notice or order issued hereunder, the Building Commissioner may seek injunctive relief in a court of competent jurisdiction restraining the person from activities which would create further violations or compelling the person to perform abatement or remediation of the violation. Civil penalties may be imposed to the maximum permitted by law, including up to \$5,000 a day under Mass. G.L. c. 83, §10.

#### **B. Orders.**

The Building Commissioner may issue a written order to enforce provisions of this by-law or regulations thereunder, which may include (a) elimination of Illicit Connections or Illegal Discharges to the Storm Drainage System; (b) performance of monitoring, analyses and reporting; (c) an order to cease and desist Illicit Connections and/or Illegal Discharges, practices or operations; and (d) remediation of contamination in connection therewith. If the Building Commissioner determines that abatement or remediation of contamination is required, the order shall set forth a deadline by which such abatement or remediation must be completed. Said order shall further advise that should the violator or property owner fail to abate or perform remediation within the specified deadline, the work may be done by a governmental agency or contractor, in which event such work and expenses thereof shall be charged to the violator.

#### **C. Criminal Penalty.**

Any person who violates any provision of this by-law, regulation, order or permit issued hereunder shall be punished by a fine of not more than \$300.00 per day. Each day or part thereof that such violation occurs or continues shall constitute a separate offense.

#### **D. Non-Criminal Disposition.**

Whoever violates any provision of this by-law may be penalized by a non-criminal disposition as provided in Mass. G.L. Chapter 40, Section 21D and Article 25 of the Town's General By-Laws. The non-criminal method of disposition may also be used for violations of any rule or regulation of any municipal officer, board or department, which is subject to a specific penalty. Without intending to limit the foregoing, it is the intention of this section that the following by-laws and regulations be included within the scope of this subsection, that the specific penalties, as listed herein, shall apply in such cases and that, in addition to police officers, who shall in all cases be considered enforcing persons for the purpose of this section, the municipal personnel listed for each section, if any, shall also be enforcing persons for such section. The Building Commissioner, Town of Freetown Police Department, or any designated Agent of the Building Commissioner shall be considered an enforcing person for the purpose of this section.

A violation of the by-law and regulatory provisions may be dealt with in a non-criminal manner as provided by section (a) above. Each day on which any violations exist shall be deemed to be a separate offense.

The fine schedule is: First offense, \$100.00, second offense, \$200.00, third and subsequent offenses, \$300.00.

#### **E. Appeals.**

The decision or order of the Building Commissioner, as the Authorized Enforcement Agency, may be appealed to the Planning Board within 20 days of the date of the decision or order. The Planning Board shall consider the request at a meeting after written notice is given to abutters, paid for by the Person appealing, at least seven (7) calendar days prior to the said meeting.

#### **F. Remedies Not Exclusive.**

The remedies listed in this by-law are not exclusive of any other remedies available under applicable federal, state or local law.

## **ARTICLE 28**

### **TAX INCREMENT FINANCING BOARD (TIFB) *ATM 6/11/08***

#### **Organization**

There is hereby established within the municipal government an unpaid Tax Increment Financing Board (TIFB) consisting of the following officials: Chairman of the Board of Assessors or his/her designee, Chairman of the Planning Board or his/her designee, Chairman of the Board of Selectman or his/her designee, Chairman of the Finance Committee or his/her designee, Town Treasurer or his/her designee, Town Administrator or his/her designee and one citizen appointed annually by the Board of Selectmen. Each member who is a designee shall be appointed annually for a period to serve May 1 through April 30.

#### **Powers and Duties**

- (1.) The TIFB shall negotiate agreements between the Town of Freetown and businesses designated as “certified Projects” for Special Tax Assessment or Tax Increment Financing in accordance with General Laws Chapter 23A and Chapter 40, Section 59, as amended. Agreements as negotiated by the TIFB shall be legally binding only after ratification by Town Meeting. The Town’s designation of specific job creation projects as “Certified Projects” shall be subject to final approval from the Massachusetts Economic Assistance Coordinating Council (EACC). The TIFB does not have the authority to negotiate a TIF for any Water District.
- (2.) The TIFB shall direct the development of a Tax Increment Financing Plan and submit said plan to Town Meeting and EACC as required by state law.
- (3.) Subject to Town Meeting ratification, the TIFB shall determine, on a case-by-case basis, the need for local property tax incentives based upon the General Policy Statement as most recently amended by the TIFB.
- (4.) The TIFB shall forward to the Board of Assessors a copy of each executed agreement to provide tax incentives to an approved “Certified Project” together with a list of parcels to be included therein.
- (5.) The TIFB shall annually review the status of the executed agreement with each “Certified Project” to determine compliance with the terms and conditions of local project certification. The TIFB shall require corrective action to remedy any identified area of non-compliance, and shall initiate revocation when it determines that there has been failure by the “Certified Project” to make a reasonable effort to remedy the deficiency.

#### **Tax Increment Financing Parcels**

Subject only to the approval of the EACC, the TIFB shall establish Tax Increment Financing parcels on a project-by-project basis. The TIFB reserves the right to establish Tax Increment Financing Zones.

#### **Exemptions from Property Tax**

Each property tax exemption provided under this chapter shall become effective per the individual Tax Increment Financing Agreement negotiated. Under no circumstances shall the term of any specific exemption agreement exceed 20 years in duration. NO exemption shall exceed the incremental increase in assessed valuation of the property that is associated with the approved “Certified Project”.

Agreements to provide property tax incentives to “Certified Projects” shall be negotiated and executed in accordance with General Guidelines as most recently amended:

#### **Reporting**

Each “Certified Project” shall submit an annual report to the TIFB no later than June 30 of each calendar year. The TIFB shall thereupon review the status of each “Certified Project” to determine compliance with the terms and conditions included in each executed agreement and submit its annual report to the TIFB and EACC no later than July 31 of each calendar year.

#### **Revocation**

All executed agreements to provide Special Tax Assessment or Tax Increment Financing (including betterment, special assessment and/or exemption from property tax) shall be binding on each party and enforceable by the Town in accordance with General Laws Chapter 23A and Chapter 40, Section 59, as amended. Should the TIFB determine, after reasonable efforts to remedy an identified area of non-compliance, that a “Certified Project” has not met its obligation under the executed agreement, the TIFB with the approval of the Board of Selectmen may petition the EACC to revoke the certification in accordance with appropriate procedures. Upon final action by the EACC,

**ARTICLE 28 (cont.)**

the TIFB shall forward to the Board of Assessors a copy of the revocation of certification and all incentives pursuant thereto. (Submitted by the Tax Increment Financing Board)

**Approval by the Massachusetts Economic Assistance Coordinating Council**

The agreements are negotiated by the TIFB and shall become effective upon approval by Town Meeting and the Massachusetts Economic Assistance Coordinating Council.

**Severability**

If a court of competent jurisdiction holds any provision of the bylaw invalid, the remainder of the bylaw shall not be affected thereby. The invalidity of any section or sections or parts of any section or sections of this bylaw shall not affect the validity of the remainder of this general bylaw.